April 1984

TABLE OF CONTENTS

Ð

YE!

THE SINGLE BOARD

N

0


S

No. 17

Unn

\$3.00

Big Voice For The BB I 4
The Xerox 820-II and the Dynadisk 10
Pascal Procedures 14
Kaypro Column
SBASIC Column
CP/M 86: A Close Look
FORTHwords
C'ing Clearly
Xerox 820 and Up
BBI Dual Density: New Version From SWP
A Very Calculating BB II
Morse Code Interface For The Kaypro 40
On Your Own 44
Technical Tips
M68K Single Board Computer



SALES MADE SUBJECT TO THE TERMS OF OUR 90 DAY LIMITED WARRANTY. FREE COPY ON REQUEST. ALL

> *TRADEMARK OF DIGITAL RESEARCH. NOT ASSOCIATED WITH DIGITAL RESEARCH OF CALIFORNIA, THE ORIGINATORS OF CPM SOFTWARE **1 TO 4 PIECE DOMESTIC USA PRICE.

MICRO CORNUCOPIA P.O. Box 223 Bend, Oregon 97709 503-382-8048

> Editor & Publisher David J. Thompson

Assistant Editor Eric Belden

Graphic Design Sandra Thompson

Technical Department Dana Cotant

Advertising Director Alice Holbrow

> Staff Assistants Dorcas Dsenis Tracey Braas

Typography Patti Morris & Martin White Irish Setter

MICRO CORNUCOPIA is the single board systems journal supporting systems programming languages and single board systems including the Big Board, Big Board II, Xerox 820, Kaypro, and Slicer.

MICRO CORNUCOPIA is published six times a year by Micro Cornucopia of Oregon, P.O. Box 223, Bend, Oregon 97709.

SUBSCRIPTION RATES:

1 yr.(6 issues)	\$16.00
1 yr.(first class)	\$20.00
1 yr.(Canada & Mexico)	\$20.00
1 yr.(other foreign)	\$26.00
Make all orders payable	in U.S.
funds on a U.S. bank, pleas	se.

ADVERTISING RATES: Available on request.

CHANGE OF ADDRESS: Please send your old label and new address.

SOFTWARE, HARDWARE, AND BOOK VENDORS: We would very much like to review your CP/M & MSDOS compatible products. Send materials to the Review Department, Micro Cornucopia.

CP/M is a trademark of Digital Research, Inc. Copyright © 1983 by Micro Cornucopia All rights reserved

MICRO CORNUCOPIA

April 1984

The Single Board Systems Journal No. 17

Read A Good CP/M Book Lately?



You may have noticed that the editorial is often a collection of things that probably should have been put elsewhere in Micro C, but I just didn't get around to prettying them up enough for a formal presentation. This editorial is no exception for herein is a book review and a plea for help (a little self-help, that is).

Book

I purchased a book called A Programmer's Notebook by David Cortesi at my local bookstore. This is a bit unusual for me because publishers are constantly offering to send me every imaginable (and unimaginable) kind of book, free. I should have saved some of the more "interesting" titles such as A Review of Business Programs for the VIC 20. (I'm sorry, that was a bit facetious.)

Anyway, I bought the book and, with it, an 8" disk containing the programs developed in the book, and I'm delighted with it. Cortesi is a first rate programmer and writer. You get to participate as he works his way through the designing, coding, and debugging of a number of complete CP/M utilities in 8080 code.

You'll learn really good assembly language programming methods, you'll learn a lot about interfacing with CP/M, and you'll feel like you've gotten to know a very interesting person.

You'll need to have some programming experience first, for he notes at the beginning, "If you are a complete novice at programming you might enjoy reading this book, but you will learn little from it. It will probably seem that we are continually leaping from problem to conclusion without any intermediate steps. The programs will seem to grow up of their own volition, like plants. If you have some experience with programming, perhaps in BASIC or Pascal, things will make more sense."

The only complaint I have about the book is that Cortesi is writing in 8080 assembly language rather than Z80. I mean, who has an 8080? Of course anything written for the 8080 will run on the Z80 but Z80 nmemonics are much easier to learn and the Z80 instruction set is more powerful. However, with my trusty little 8080-Z80 translator, I can change all those source files into something more intelligible.

Meanwhile, this is a super book and Cortesi has another book called *System Programming Under CP/M-80* which sounds very interesting. After all, *The Programmer's Notebook* is better reading than most novels.

A Programmer's Notebook David Cortesi Reston Publishing Company Reston Virginia \$16.95 (without disk)

Self-Help Anyone?

Support has turned into a real problem here at Micro C. You see, Dana and I have been scrambling to keep systems running, build new systems (the Little Board and the Latest Slicer), modify our present systems (the Big Board, the Big Board II, the new Kaypro 4, and old Kaypro II), and try out all those software and hardware packages (the PROM programming packages for the BB II, for instance) that people send us and plead with us to review.

Meanwhile, we are spending well over half of our working hours answering calls for help. Mondays and Fridays are the worst with Tuesday, Wednesday, and Thursday a little lighter (usually).

Some people have suggested that we set specific hours when we will handle technical calls, say, afternoons on Tuesdays and Thursdays. Others have suggested that we limit each call to 3 minutes.

I don't like either of these options. Micro C is at its best when it helps people



Dear Editor,

With a few minor problems I got my BB I running.

First, there weren't any display sync. signals, vertical or horizontal. A 74S04 for U11 got the 14.318mhz oscillator running, instead of a 74LS04. Still no sync.

I found the C external pins on the 74LS123 one shots grounded. Even on the schematic it showed this. Most applications I found didn't ground them. After cutting away the Pc ground path, the display took right off.

My ORBIS 76 Disk drive wanted to see 10ms step rate. So I had to change location FF6A from 00 to 02.

When interfacing the centronics 700 printer to channel a PIO, a oneshot had to be added on the "Ready out Line." It seems the 700 wanted to see the positive going trailing edge, before it would send back the ACK or strobe. **Chris Gentile**

3256 Roxborough Ave. N. Clearwater FL 33520

Dear Editor,

I noticed in issue #15, page 2, editor's note to Chris Paulson, the installation of the IFORTH monitor (user disk #18) was not in the recommendation. Everyone I know who has used this monitor has considered it a big improvement over PFM so why was it not included in the list?

I have considered sending in some improvements to IFORTH but I have seen little feedback on it in recent issues of Micro C so I wonder if it is worth my time? **Raymond L. Buvel**

Box 3071 Moscow ID 83843 208-885-8818

Editor's note:

Sorry, Ray. I guess we are as guilty of no feedback as anyone. Yes there has been a lot of interest in IFORTH. We have been recommending it to many BB owners. You should take a look at making it available on the 820. I think that would be very popular. Especially since you are offering inexpensive ROM programming for folks.

Since I don't program in FORTH I haven't put it on my system though it is a very nice extension to the PFM monitor. Dear Editor,

Wow! the gang at Micro C is making the humble little Kaypro into one hot machine. First 5MHz and now 800K per drive. Those PC clones better watch out!

There is one modification that many of us would love to see on the Kaypro—a 256K RAM disk. It ought to make PW swap files and TW work like a dream.

Why not get together with Tony Ozrelic of LA Software and produce a Dyna-Disk for the Kaypro at a reasonable price. I'm sure you'd have a lot of interest especially those of us who can't afford (and see little need for) a full blown coprocessor.

One question . . . will the Pro-Monitor ROM's (II, 4 and 8) work with the Uniform software and still enable the Kaypro to read and write disks formatted for other machines?

Mike Perry 6035 40th Ave NE Seattle WA 98115

Editor's note:

Check with MicroSphere for an inexpensive RAM disk for the Kaypro.

Uniform (as shipped by Kaypro) requires that both A and B drives be correct for that version of Uniform. Since we are also supporting two additional drives, you can make C and D be 96 trackers and still have full use of Uniform.

Also, the CO-power board expects to see Kaypro II or 4 drives as A and B. So by putting 96 track drives on C and D you will still be totally compatible with these add-ons.

Dear Editor,

My sons and I are at an impasse with Adventure. We can accumulate 262 points, but have not learned to kill the ogre or to avoid paying an onerous tax to the troll.

Since there aren't any user groups in our town, we saw your note in Micro C and thought you might be willing to exchange some hints. The advice on what to with the food is in the last paragraph in case you wouldn't want to sully the purity of your one man Adventure.

There can be many saved games, not just one, as your column indicated. Just type "SAVE OGRE", or any other four letter name, and the name will be appended to the ADVD.SAV file, making it ADVDOGRE.SAV.

As you recommended, that file can be made durable by PIPing it under a new name to the same or different disk to be re-PIPed as needed.

Anyway, we're stuck and getting frus-

trated after running out of ideas of what to try. Of course, the solution will seem obvious, and we'll wonder why we never thought of it.

(The food is for quieting the fierce cave bear. Be sure to bring the keys along. Have you wondered why the emerald is the size of a "plover's" egg? Don't be afraid of whirlpools. WD-40 is nice, but oil still works.)

David A. Satchell

Manitowoc Surgical Association 600 York Street Suites 5 and 6 Manitowoc WI 54220

Editor's note:

I've been trying to tread the fine line between saying too much and not saying anything about Adventure. For some people the goal is the struggle, for others, the goal is 550 points.

I'm tempted to include hints (such as yours) in Micro C and mark them plainly so that people can avoid them if they wish. You need the sword to get past the ogre, by the way.

I'd like to know what to do with the broken up skiff.

Dear Editor,

I dropped you this note just to let you know that I am happy to renew my subscription to Micro C.

I have installed the 256K RAM on my BB I as described in issue #12 and it works fine.

At the same time, I installed the 4 MHz modification described in issue #1. It works fine too.

One thing readers should know about the 256K mod. is that you must install all 256K RAM chips in order to run just as before. It took me awhile to realize this. One 64K segment is spread over the 4 rows.

R. Warichet Av. de la Jeunesse 4 1030 Bruxelles Belgium

Dear Editor,

I would like to correct some information in the letter from Charles Woodard published in issue #15.

Yes, I can supply parts and information on MFE 8" floppies. However, the correct daytime phone is 603-893-1921. The evening phone (preferred calling time) is 603-329-5838. Please see my Want Ad in this issue.

Richard H. Breinlinger 51 Wash Pond Rd. Hampstead NH 03841 Dear Editor,

I have been salivating at the possibility of having a 5 MHz Hotrod-Kaypro since I received the issue of Micro C (June 1983) with your column describing the speed-up modification.

First, let me say that since performing the speed-up operation two weeks ago, I have been much happier with my computer. The performance at 4 MHz with all my programs has been substantially improved. But I would sill like to increase the speed to 5 MHz if possible.

However, I was not able to increase the speed to 5 MHz. When I switched the toggle to the 5 MHz position, garbage characters filled the screen and the system would neither boot nor would keyboard commands have any effect. I assumed that although I checked the connections and wires that I added, I had made an error in following the instructions.

At this month's user's meeting, I met another gentleman that had also followed the instructions in your column and likewise was not able to get beyond 4 MHz. So I am writing to you.

I purchased an 'SGS' brand Z80B and 'SGS' brand monitor ROM. I inserted the Z80B into the socket at U63 and the ROM at U43.

Next, rather than soldering to the pins on U66 (as I was advised not to by a good friend who is also an electronics tech. and the half-willing overseer of the job) I cut the leads in the board to pins 4 and 5, and ran trace wires to the destination pins.

As I noted above, the 4 MHz speed-up is great. I cannot imagine doing anything on my computer at the slower speed. Also I have been very pleased that I have not found a single program that would not work at the faster speed. Even without 5 MHz I am a much happier Kaypro owner.


Matthew Kesner 6345 Lochmoor Drive San Diego CA 92120



Editor's note:

Some SGS parts have been slow, especially the ROMs. Get a 250 ns 2732 and burn the ROM data into the top half. Then plug that in place of the 2716-1-that's what we are doing and it has solved the ROM problem completely.

Also, some sources of SGS Z80Bs have been shipping poor quality parts. I haven't tracked down the culprits but some of the SGS's people are getting won't run 5 MHz.



Dear Editor,

I am impressed. I expected the usual 4 to 6 week waiting period between the time when you order a magazine and when you receive the first issue and was really surprised, as well as pleased, when I received my first issue within two weeks.

It came yesterday and I have already read it once. I am assuming this is a statement of the quality of services you strive to provide to your subscribers. Keep up the good work.

I am a newcomer to the computer world and am basically an illiterate with lots of questions. What is an EPROM? Is it edible? It's OK with tabasco sauce if you watch out for the legs.

After reading what my manuals had to say about HEX I felt as though I had been hexed. Is a Slicer any good for cutting tough tomato skins? *Yes, and it is fast.*

One reader, in your letters column in issue #15, talked about stepping in and stepping out at 3ms on a 1771 while forcefully interrupting. Is that a new dance where you try to make more noise than the band?

Is a MONOSTABLE a place where they keep one legged horses?

Seriously, I realize that these things will become clearer as I go along but I can

also appreciate why some people are put off by the bewildering array of strange items, jargon and concepts that they are confronted with when they peek into this field.

I would like to know where I can get some good resource material that is comprehensible to the lay person? I would appreciate any contacts from Kaypro users in my area.

What are the advantages of turning my Kaypro 4 into an 8? If I purchase your Pro-set 4 (or 8) do I need to upgrade my machine first? What needs to be done? How is it done? How much will it cost? Larry D. Ruddell

214 E. Euclid Spokane WA 99207

Editor's note:

You can pop our PRO-8 monitor into your Kaypro 4 without making any changes. You will get faster disk accesses and the setable cursor. You can, of course, also do the speed up to 5 MHz. You will need a copy of issue #12, a Z80B, some wire-wrap type wire and a switch.

With the PRO-8 monitor you can go to the quad density drives if you wish but you certainly don't have to.

(Letters continued on page 50)

Big Voice For The BB I

By James R. Thompson

Communications with the computer—touch sensitive screens, high resolution crt's and graphics printers, voice pattern recognition, speech synthesis, etc.—are the predominant push in the computer industry these days. Along with these come a trend to reduce the peripheral control burden on the CPU and memory and offload it onto the peripheral.

Big Voice

One peripheral for the Big Board that retains most of its control and storage in hardware (thus freeing the CPU and memory for more important work) is the Big Voice speech synthesizer.

The board, based on the Votrax (R)SC-01 phoneme speech synthesizer, contains approximately 1400 English words plus the 64 basic phonemes all in a compressed data format in two 32k EPROMS with expansion capability to two 64k EPROMS (up to about 2800 words). Each spoken word or phoneme requires a two byte code to specify the word and its pitch.

The synthesizer module stacks on top of the Big Board and plugs into its general purpose parallel port. The forty-pin plug is extended above the board for those using the GPI/O for printers or whatever. The only restriction is that the Port A handshake not be used. Port A may be used in Mode 3 and Port B may be used in any mode.

Even though the speech synthesizer was designed primarily for the Big

Figure 1 - Word Mode Data

Board, it could easily be interfaced to any microcomputer with an eight-bit parallel output port and handshake signals.

Software

Speech can be initiated in two ways: word-at-a-time (Word Mode) or phoneme-at-a-time (Phoneme Mode). From the standpoint of communications to the module, these two modes differ only in data rate and address. The following are the protocols for each mode.

1) low byte of the word or phoneme is sent to Port A

2) voice module loads low byte and returns handshake

3) GPIO interrupts CPU requesting high byte

4) CPU responds by sending high byte to Port A

5) module starts speaking

6) upon completion, module returns handshake

7) GPIO again interrupts CPU signaling end of speech

8) Repeat 1-7 for each word or phoneme

One hardware requirement that the software must recognize is that the ready signal must load the high byte within 40 milliseconds after loading the low byte or the chip will do an internal RESET.

Since the module uses only Port A to load successive bytes, some means of automatic reset must be built into the chip to keep the phoneme generator and the computer from getting out of sync.

high byte low byte msb lsb M M A A A A A A A A A A A A A where, M = 00 (low pitch) through 11 (high pitch) A = 0 through 3FBF hex (word starting address)

Figure 2 - Phoneme Mode Data

where,

msb lsb MM111111 11PPPPP

M = 00 (low pitch) through 11 (high pitch) P = 0 through 3F hex (phoneme code) 9910 Leawood Blvd. Houston TX 77099

Word Mode

The word mode data rate averages about 3.5 bytes per second (1.7 words per second). Word Mode data (i.e., the pitch and starting address of the word in the module's EPROM) is shown in Figure 1.

Phoneme Mode

Phoneme mode data rate averages about 23 bytes per second (11.5 phonemes per second). Phoneme Mode data (i.e., the pitch and address of the phoneme in the module's EPROM) is shown in Figure 2.

The two programs labeled SPEAK.Z80 and BSPEAK.Z80 are combination driver and interrupt service routines. They are written in assembly language.

The first is used to setup the Big Board for word or phoneme speech with assembly language programs. The second is used with BASIC when speaking phonemes. Even BASIC at 5 MHz can't feed phoneme data fast enough to keep the speech from sounding strung out, so words are POKEd into memory by BAS-IC and then spoken by CALLing the driver. BASIC is easily fast enough for continuous WORD speech.

SPEAK, when assembled and executed, programs the GPI/O Port A in the output mode, moves the driver and interrupt service routines into memory at FA40H (above PFM), resets the SC-01 and speaks the word "ready." To use this driver routine, load the HL register pair with the address of the word or phoneme to be spoken (formats described above) then CALL FA40H. See Figure 3.

The program DEMO.COM demonstrates the driver SPEAK when used with an assembly language program (see Figure 4).

BSPEAK (see Figure 5) performs essentially the same way as SPEAK except that phoneme codes are loaded into memory in sequence starting at FA7AH (up to 127 phonemes) and terminating the sequence with 40H. A CALL to FA40H will initiate speech. A byte POKEd at FA79H sets the pitch for the entire sequences as shown:

> 3FH = low pitch 7FH = medium low BFH = medium high FFH = high pitch (continued on page 6)

Figure 3 - Big Voice Interrupt Routine

,	,			
 TNTER 	RIPT FLA	G IN MEMORY IS L	oc.	ATED AT FA78H
,	ORG	100H		
: PROGRA		G BOARD GP I/O P	OR	ГА
	LD	A,OFH		PROGRAM THE GP I/O PORT A
	OUT	(09),A		IN THE OUTPUT MODE
	LD	A, 1EH		LOAD THE PORT A
	OUT	(09),A	;	INTERRUPT VECTOR
	LD	A,87H	;	INITIALIZE INTERRUPTS
	OUT	(09),A		ON PORT A
; PUT IN		SERVICE ROUTINE		
	LD			;ADDRESS FOR INTERRUPT ROUTINE
	LD		;	PORT A INTERRUPT ADDRESS IN PFM
	LD	A,OFFH	;	ANY NON ZERO TO A
	LD	(INTPND),A	;	DECLARE NO INTERRUPTS PENDING
; MOVE		TO FA40H		
	LD	HL, SPK	;	MOVE THE DRIVER AND THE
	LD	DE, OFA40H	;	INTERRUPT SERVICE ROUTINE
	LD DI	BC, END-SPK	;	TU FA40H
	LDIR EI			
• DECET		1 AND SAY "READY		
, NEOL I	LD			SEND OUT ANY CODE (STOP CODE) TO
	CALL	SPK	1	START THE SC-01 CLOCK
DELAY	LD	A,80H	:	84 MS TIME DELAY WITH 5 MZ CLOCK
D1	LD	B,OFFH	:	TO RESET THE SPEECH SYNTHESIZER
D2	DJNZ	D2	,	
	DEC	A		
	JR	NZ,D1		
	LD	HL, 3FFFH	:	SEND OUT A STOP CODE JUST
	CALL	SPK		IN CASE THE SC-01 COMES UP TALKING
	LD	HL,OC17H		EPROM CODE ADDRESS FOR "READY"
	CALL	SPK	•	
	JP	0	;	RETURN TO CP/M
; TO US	E DRIVER	R ROUTINE EPROM A		RESS MUST BE IN THE HL REGISTER PAIR
SPK	PUSH	AF		SAVE THE AF REGISTERS
SP1	LD	A,(INTPND)		CHECK FOR INTERRUPT
	OR	A		JUMP BACK IF INTERRUPT
	JR	Z,SP1	;	FLAG IS SET
	XOR	A		ZERO TO A REGISTER
	LD	(INTPND),A		SET INTERRUPT FLAG
	LD	A,L	;	SEND LEAST SIGNIFICANT ADDRESS BYTE
SP2	OUT LD	(08),A	;	TO SPEECH SYNTHESIZER
512	OR	A,(INTPND) A	;	CHECK INTERRUPT FLAG JUMP BACK IF INTERRUPT
	JR	Z,SP2		FLAG IS SET
	XOR	A		ZERO IN A
	LD	(INTPND),A		SET INTERRUPT FLAG
	LD	A,H	:	SEND MOST SIGNIFICANT ADDRESS BYTE
	OUT	(08),A		TO SPEECH SYNTHESIZER
	POP	AF	:	RESTORE THE AF REGISTERS
	RET		'	
; INTER		RVICE ROUTINE		
INT	PUSH	AF	;	SAVE THE AF REGISTERS
	LD	A,OFFH	;	NON ZERO IN A
	LD	(INTPND),A	;	CLEAR INTERRUPT FLAG
	POP	AF	;	RESTORE AF REGISTERS
	EI			INABLE INTERRUPTS
	RETI		;	RETURN FROM INTERRUPT
;				
TUMPUM	500			
INTPND END	EQU END	0FA7AH 100H	;	MEMORY ADDRESS FOR INTERRUPT FLAG

Figure 4 - Example Speech Routine

;"HELLO	MY NAME	IS WILBER I AM	THE SPEECH SYNTHESIZER SAY A TALKING COMPUTER" ADDRESSES ARE 185 AND 47 MS TIME DELAYS ;ADDRESS FOR THE SPEECH SYNTHESIZER
	ORG	100H	DRIVER ROUTINE
LOOP	LD LD CP JR LD INC LD INC CALL	IX, DATA A, (IX) 40H Z, END L, A IX H, (IX) IX SPEEK	;LOAD IX WITH EPROM DATA ADDRESS ;LOAD A WITH EPROM ADDRESS LOW BYTE ;TEST TO SEE IF LAST BYTE ;END IF STOP BYTE ;PUT LOW BYTE IN REGISTER L ;INCREMENT COUNT ;LOAD H WITH EPROM ADDRESS HIGH BYTE ;INCREMENT COUNT ;CALL DRIVER ROUTINE
END	JR JP	LOOP 0	;GET NEXT BYTE
; Data	DEFW DEFW DEFW DEFB	073EH,3FFEH,0A1 0F3DH,3FFEH,078 0000,3FFFH,0D9A 40H	8H,0076H
;	END		

Digital Dynamics' SPEEDPRO-5RTC — It's time for your Kaypro.

Be the master of your time by equipping your Kaypro II or 4 with our SPEEDPRO-SRTC accessory board and TIMEPRO software. Offering the high speed performance of our popular SPEEDPRO-5+, the SPEEDPRO-SRTC adds the fourth dimension to your computing capabilities — TIME! With its built-in, battery backed-up clock/calendar and powerful appointment tracking software, the SPEEDPRO-SRTC makes your Kaypro work like no Kaypro has before.

TIMEPRO

To compliment the clock/calendar of the SPEEDPRO-5RTC, Digital Dynamics has developed TIMEPRO, a complete software system designed to exploit the capabilities of the clock/calendar. TIMEPRO includes SEE-TIME, which displays the time and date on the screen whenever your Kaypro is operating — no matter what software you may be using. APPT is Digital Dynamics' powerful appointment management software containing features like:

Appointment scheduling and maintenance;

Automatic warning of impending appointments, and perennial events;

Time in other places;

Message storage and retrieval, and;

Many other useful capabilities.

TIMEPRO also includes source code in several popular computer programming languages for all of the clock/calendar reading and setting routines so that you can easily incorporate time and date functions into your own programs.

SPEED

The SPEEDPRO-5RTC, of course, shares the performance heritage of its little brother, the SPEEDPRO-5+. Either one of our boards will give your computer nearly twice the standard processing performance.

Our SPEEDPROs soup up your Kaypro with a new Zilog Z80B high speed microprocessor and support circuitry. Externally mounted toggle switches provide the ability to switch from standard speed to high speed and to turn the wait state on and off.

Who says you can'town a time machine? The SPEEDPRO-5RTC is here, now. If you don't need the clock/calendar, but do want increased processing speed, then order the SPEEDPRO-5+. Both SPEEDPROs are available from Kaypro dealers nationwide. And, the prices are right — just \$99.95 for the SPEEDPRO-5+ and \$199.95 for the SPEEDPRO-5RTC with TIMEPRO software.

NOW IS THE TIME! DIGITAL DYNAMICS Performance Products

for Microcomputers

(206) 627.0797
P.O. Box 5653

Tacoma, WA 98405

(continued)

The program DEMO1.BAS demonstrates the use of BSPEAK to handle phoneme speech from BASIC. This program uses the BASIC CALL statement found in Microsoft BASIC Revision 5.xx and above. The program may be modified to use the USR statement in earlier versions of BASIC. See Figure 6.

DEMO2.BAS demonstrates the use of the module in Word Mode. The interrupt service from SPEAK must be loaded into memory prior to using DEMO2 (see Figure 7).

The figure 8 table lists the phonemes in alphabetical order, their code, duration, and an example word. (The list in Figure 8 was extracted from the Votrax data manual.)

Hardware

In order to fit 1400 English words into 8K bytes of EPROM, I used data compression to store 4 six-bit phoneme codes in only 3 bytes of the EPROM. This increases the storage capacity by about 30% over the technique of storing 6 bits per byte. This is done by storing the 6 bits of every fourth phoneme in the 2 otherwise unused bits of the first three phonemes.

For example, take the word "COM-MUNICATE." Broken down into phonetic speech the word looks like this.

K UH2 M Y1 IU U1 N I3 K A1 Y T Stop

Once converted to the six bit code required for the Votrax:

19 31 0C 22 36 37 0D 09 19 06 29 2A 3F

This code is then compressed by taking the codes tagged with an asterisk and shoving them into the previous 3 codes.

99 31 8C 76 B7 0D 99 86 A9 3F

This technique does not yield a full 33% improvement due to word boundaries (a loss of 0 to 6 bits per word) and due to the hardware not counting across 256 byte boundaries (an average loss of 3 bytes per 256 bytes).

Hardware Description

When the low byte of the data shows up at the phoneme counter, a Ready signal triggers the 500 ns one-shot U18a. The leading edge of the one-shot issues a Strobe handshake and triggers the 50 ms

;THE INTERRUPT FLAG BYTE IN MEMORY IS LOCATED AT FA78H ORG 100H : PROGRAM THE GPI/O PORT A FOR SPEECH SYNTHESIZER ;PROGRAM THE GP I/O PORT A LD A,OFH ; IN THE OUTPUT MODE (MODE O) OUT (09).A LOAD THE PI/O PORT A LD A.1EH OUT (09),A ;INTERRUPT VECTOR LD **INITIALIZE INTERRUPTS** A,87H OUT ON PORT A (09).A ;PUT INTERRUPT SERVICE ROUTINE ADDRESS IN PFM LD HL, INT-SPK+OFA40H ; ADDRESS FOR INT. SERVICE ROUTINE LD (OFF1EH),HL ; INTERRUPT VECTOR ADDRESS IN PFM ; MOVE ROUTINE TO FA4OH LD HL, SPK ;MOVE THE DRIVER AND THE LD DE, OFA40H ;INTERRUPT SERVICE ROUTINE LD BC, END-SPK ;TO ADDRESS FA40H DT LDIR EI LD A, OFFH ;NONE ZERO TO A LD (INTPND),A ;DECLARE NO INTERRUPTS PENDING LD A,3FH ;LOAD THE EPROM MOST SIGNIFICANT L.D (PITCH),A BYTE TO MEMORY LOCATION PITCH ;RESET THE SC-01 AND SAY "READY" LD HL, DATA ;LOAD MEMORY LOCATION DATA LD A,OFEH ;WITH A STOP CODE PHONEME LD (HL),A ;AND A 40H STOP BYTE INC HI. A,40H LD LD (HL),A CALL SPK ;START SC-01 CLOCK DELAY A,80H ;85 MS TIME DELAY WITH 5 MZ CLOCK TO LD LD B,OFFH ;ALLOW THE SPEECH SYNTHESIZER TO RESET D1 D2 DJNZ D2 DEC A JR NZ,D1 LD HL, DATA ;LOAD MEMORY LOCATION DATA A, OFFH WITH A STOP PHONEME AND LD LD (HL),A A STOP BYTE INC HL A,40H LD LD (HL),A CALL ;SEND THE STOP PHONEME TO SC-01 SPK LD HL, DATA1 ; MOVE THE PHONEME CODE TO SAY READY LD DE, DATA ;TO MEMORY LOCATION "DATA" LD BC.7 DI LDIR ΕI CALL SPK :SAY "READY" JP 0 ; DRIVER ROUTINE LOCATED AT MEMORY ADDRESS FA40H SPK PUSH AF ;SAVE THE AF REGISTER PAIR PUSH HI. SAVE THE HL REGISTER PAIR LD HL, DATA ;ADDRESS OF SINGLE PHONEME DATA SP1 LD A, (INTPND) ;TEST THE INTERRUPT FLAG OR A ; IF <> ZERO DATA CAN GO OUT LOOP BACK IF ZERO JR Z.SP1 LD A,(HL) CP 40H :CHECK FOR LAST PHONEME CODE JR Z, ENDIT IF NO MORE CODE END XOR ZERO IN REGISTER A LD (INTPND),A ;SET INTERRUP FLAG LD A,(HL) IF NOT END GET PHONEME CODE BACK IN A ADD OFFSET FOR EPROM ADDRESS OR A, OCOH OUT (08),A SEND LOW BYTE TO SPEECH SYNTHESIZER INCREMENT INDEX REGISTER INC HL SP2 A,(INTPND) LD SEE IF HIGH BYTE CAN GO OUT OR SEE IF ZERO JR Z,SP2 LOOP BACK IF ZERO XOR GET ZERO IN A REGISTER LD (INTPND),A ;SET INTERRUT FLAG I.D A, (PITCH) GET HIGH BYTE ADDRESS FOR SINGLE PHONEME OUT (08),A ;SEND HIGH BYTE ADDRESS TO SYNTHESIZER JR SP1 ;GET NEXT PHONEME CODE ENDIT POP HL ;RESTORE THE HL REGISTER PAIR POP AF RESTORE THE AF REGISTER PAIR RET ; INTERRUPT SERVICE ROUTINE FOR SPEECH SYNTHESIZER INT PUSH AF ;SAVE THE AF REGISTER PAIR LD A, OFFH NON ZERO IN A REGISTER LD (INTPND).A CLEAR THE MEMORY INTERRUPT FLAG POP AF RESTORE AF ΕI ;ENABLE INTERRUPTS RETI RETURN FROM INTERRUPT INTPND EQU \$+OFA40H-SPK ;MEMORY INTERRUPT FLAG LOCATION PITCH EQU INTPND+1 MEMORY LOCATION FOR SC-01 PITCH CONTROL

Figure 5 - BSPEAK Program

6.

DATA

DATA1

END

EÒU

DEFB

END

PITCH+1

100H

ADDRESS FOR PHONEME CODE

2BH,02,00,1EH,29H,3FH,40H ;PHONEME DATA "READY"

auto-reset one-shot. The trailing edge increments the load pointer U8a so the system is ready for the high data byte.

Before the 50 ms one-shot can time out, the high byte data from the port must be stable and a second ready signal must be received; otherwise, the load pointer will be reset to low byte.

This second ready triggers the 500 ns one-shot again. The leading edge of the one-shot's output resets all flip/flops and clears the accumulator. The trailing edge then sets the Start flip/flop.

The Start flip/flop issues a STB signal to the SC-01. Once the SC-01 has accepted the data, an ACK is returned. STB is then removed, the phoneme counter is advanced, the accumulator shifts in the most significant two bits of the current EPROM byte, and the accumulator shift counter is incremented. The controller then waits for the SC-01 to return RDY to indicate the completion of the current phoneme.

This process will repeat until a 3FH (STOP phoneme code) is detected by U1. This will set the Stop flip/flop U15b which will issue a Reset pulse to the Start flip/flop U8b.

If the word is longer than three phonemes, the accumulator shift counter U5a,h will be set to 3 (counting sequence is Grey code: 0-1-3-2) indicating that the fourth phoneme is to come from the accumulator, not from the EPROM.

The phoneme counter is disabled by the SWAP signal. When ACK is returned during the third byte, U15a will be set, disabling the EPROM output and enabling the accumulator dump gate U14.

In the single phoneme mode, U4 forces the system to stop after each phoneme and wait for another phoneme and handshake from the port. In this mode, each word or phrase must be followed by an explicit Stop code (phoneme 3FH) or the SC-01 will continue to repeat the previous phoneme.

Package Available

You can get a complete phoneme package from the author for \$70 postpaid. This package includes the printed circuit board, two 2532 EPROMS containing approximately 1400 words, an 8" SSSD floppy containing utilities and the source of the word file and documentation.

(Schematics follow on pages 8 & 9)

```
10 'DEMO1
20 'THIS PROGRAM DEMONSTRATES THE USE OF SINGLE PHONEME CODE
30 'FROM BASIC
40 A=0
50 B=&HFA7A
60 SPEEK=&HFA40
70 FOR I=0 TO 63
80 READ A
90 POKE B+I.A
100 NEXT I
110 CALL SPEEK (A,A,A)
120 THELLO
130 DATA 27,02,35,24,35,53,55,63,63
140 'MY
150 DATA 12,21,0,9,41,63
160 'NAME
170 DATA 13,06,33,41,12,63
180 'IS
190 DATA 11,9,18,63
200 WILBER
210 DATA 45,11,9,24,14,58,63,63
220 'I
230 DATA 21,0,9,41,63
240 'AM
250 DATA 47,0,12,63,62
260 'A
270 DATA 6,33,41,63
280 'TALKING
290 DATA 42,61,25,10,20,63
300 'COMPUTER
310 DATA 25,50,12,37,34,54,55,42,58,63,64
```


Figure 7 - DEMO2.BAS


10	'DEM02
20	THIS PROGRAM DEMONSTRATES THE USE OF PHONEME CODE FROM EPROM
30	WITHOUT USING THE DRIVER ROUTINE. MEMORY LOCATION FA78H IS THE
40	MEMORY INTERRUPT FLAG.
50	READ A
60	READ B
70	OUT 8,B
80	POKE &HFA78,0
90	OUT 8,A
100	C=PEEK (&HFA78)
110	IF C=0 THEN GOTO 100
120	GOTO 50
130	DATA 7,62,63,254,10,29,10,37,8,63
140	DATA 15,61,63,254,7,136,0,118,0,0

150 DATA 13,154,63,254,9,197,2,224

Figure 8 - Phoneme Table

Phoneme Symbol	Phoneme Hex Code	Duration (MS)	Example Word	Phoneme Symbol	Phoneme Hex Code	Duration (MS)	Example Word
A	20	185	day	K	19	80	trick
A1	06	103	made	L	18	103	land
A2	05	71	made	м	00	103	mat
AE	2E	185	dad	N	OD	80	sun
AE1	2F	103	after	NG	14	121	thing
AH	24	250	шор	0	26	185	cold
AH1	15	146	father	01	35	121	aboard
AH2	08	71	honest	02	34	80	for
AW	3D	250	call	00	17	185	book
AW 1	13	146	lawful	001	16	103	looking
AW2	30	90	salty	P	25	103	past
AY	21	65	day	PAO	03	47	no sound
В	0E	71	bag	PA1	3E	185	no sound
CH	10	71	chip	R	2B	90	red
D	1E	55	paid	S	1F	90	pass
DT	04	47	butter	SH	11	121	shop
E	20	185	meet	STOP	3F	47	no sound
E1	3C	121	be	T	2A	71	tap
EH	3B	185	get	TH	39	71 ·	thin
EH1	02	121	heavy	THV	38	80	the
EH2	01	71	enlist	U	28	185	move
EH3	00	59	jacket	U1	37	90	you
ER	3A	146	bird	UH	33	185	cup
F	1D	103	fast	UH 1	32	103	uncle
G	1C	71	get	UH2	31	71	about
Н	1B	71	hello	UH3	23	47	mission
I	27	185	pin	v	OF	71	van
I1	0B	121	inhibit	W	2D	80	win
12	OA	80	inhibit	Y	29	103	any
13	09	55	inhibit	¥1	22	80	yard
IU	36	59	you	Z	12	71	z00
J	1A	47	judge	ZH	07	90	apzure






8

.

Figure 11 - Big Voice Timing Section



- INDICATES CONNECTION TO JI & PI

- INDICATES COMMECTION TO POWER & SPEAKER CABLES

Parts List

Integrated	Circuits
------------	----------

U1, U4	74LS30	C1, C10	200 PF 5% Silver Mica
U2, U3	TMS2516 or TMS2532 or TMS 2564	C2, C3, C4, C5, C7	0.1 UF 50V Ceramic disc
U 5	74LS273	C6	220 UF 20V 20% Tantalum
UG, U7	74LS191	C8	deleted from circuit
U8, U15	74LS74	C9	100 UF 20V 20% Tantalum
U9, U16	74LS00	C11, C12	10 UF 16V 10% Electrolytic
U10	74LS132		
U11	LM386	Diodes	
U12	Votrax SC-01 Speech Synthesizer chip	220205	
U13	7407	D1, D2	1N914 or equivalent
014	74LS365 or 74LS367	51, 52	INGIA OF EQUIVALENC
U17	74LS04	Sockets	
U18	74LS123	DUCKELS	
		for U2, U3	28 min 600 mil lou profile adde wine
Resistors		for U12	28 pin 600 mil low profile side wipe 22 pin 400 mil low profile side wipe
Nestator's		101 012	ss biu 400 mit 10m brottte side wibe
R1, R2, R7, R10		Plugs, Jacks, and	Pins
R12, R13, R16	10K Ohm 1/4W 5%		
R3	5K Ohm 20 turn trim pot	J1	2 x 20 .025" sq. pin male .1" x .1" spacing
R4, R8	3.3K Ohm 1/4W 5%	P1	2 x 20 female plug for .025" sq. pins
R5	7 x 4.7K Ohm sip resistor pack (8 pins)	jumpers (8ea.)	.025" sq. gold wirewrap posts
R6	10K Ohm 20 turn trim pot	Jumper D (Ocar)	sort of Rord willewigh books
R9, R15	4.7K Ohm 1/4W 5%	Cables	·
R11	560 Ohm 1/4W 5%	AGD163	
R14	1K Ohm 1/4W 5%	Deven erble	45°
R17	2.2K Ohm 1/4W 5%	Power cable	15" x 3 cond. #26 cable
N11		Speaker cable	2 cond. #26 cable (length as required)

Capacitors

The Xerox 820-II and the Dynadisk

By Clarence Peckham

13075 SW Davies Rd. Beaverton OR 97005

After owning a Xerox 820-II for over a year, I was ready for some form of mass storage other than floppy disks. The problem was not one of storage capacity, I'm using 8 inch double density drives, but one of performance. One obvious solution was to add a winchester subsystem.

However, the winchester was out due to the high cost. The next solution was a solid state disk. A solid state disk is a medium-cost storage system with performance in the 125 KB/sec range and zero access time. It seemed ideal!

Most of the solid state disk systems available in the marketplace are designed for S100 applications. The one unit I found which was usable was the Dynadisk from LA Software. Tony Ozrelic is the designer of the Dynadisk and after a short telephone conversation, I ordered the documentation and software with the intent to wirewrap a breadboard version of the Dynadisk.

I don't recommend this approach. Tony now has a printed circuit board available at a very reasonable price. I spent a lot of time checking my wiring when the problem was really an error in the software.

Dynadisk

The Dynadisk is a 256 KB RAM array with the necessary TTL logic to provide an interface to the spare parallel interface on the BB I. This is the problem. The Dynadisk was designed to operate with the BB I and wasn't tested for use with the Xerox 820-II. Although the hardware interface is the same, the software is not.

Fortunately, the 820-II still maintains a strong link to it's BB I heritage. The CBIOS for the BB I works fine with both the 820 and the 820-II. This allowed me to use a version of CP/M set up for the BB I on my system for testing purposes. So, armed with Dynadisk and a version of CP/M for the BB I, I proceeded to convert the Dynadisk software to work with the 820-II CBIOS.

Hardware Modifications

No software project is complete without hardware mods. Fortunately, the hardware mods are minimal and only effect the 820-II motherboard. No changes on the Dynadisk board are required. The first change required is to remove the two IC's from the 820-II motherboard. Remove U90 and U91 and replace them with jumper blocks as described in the Dynadisk Operating Manual. U90 and U91 are 74LS243 bidirectional buffers and are not required for the Dynadisk.

The next step is to make the necessary jumper connections in the J11 jumper

block on the 820-II motherboard. The necessary connections are as follows:

3 - 4 5 - 6 7 - 8 13-14 15-16

Once these changes are made, the last step is to connect the cable to the Dynadisk. This connection is made using con-

Figure 1 - CBIOS Patch To Use Dynadisk on the Xerox 820

			title	RAMDSK - Dynadi	sk I/O patcher
		;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;	by Tony	on ddyna - dynadi Ozrelic ht (c) 1982	sk i/o patcher
		;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;		ersion Copyright ence Peckham	(c) 1983
			i∕o por	ts	
0008		ddata	equ	8 ;data p	
0009	-	actl	equ		ntrol A
000A 000B		dcsr bctl	equ		l/status port
OOOD		;	equ	11 ;pio co	neroi B
	•		t Bit pa	tterns	
0000		tlđ	equ	00000000B	;Track load
0001		sld	equ	00000001B	;Sector load
0002		ref	equ	00000010B	;Refresh on bit
ØØØ4 ØØØ8		data rw	equ equ	00000100B 00001000B	;Data selection ;R/W bit
0000		;	equ	000010000	
ØØØ8		dtrack	equ	tld + rw	
0009		dsect	equ	sld + rw	
ØØØC		dread	equ	data + rw	
0004 000a		dwrite drfsh	equ equ	data ref + rw	
UUUA		;	equ	Ter + rw	
		;	•Memory	addresses in 820	-II monitor
F368		seltab	equ	Øf360h + 8	
F384	•	dvrtab	equ	Øf38Øh + 4	
F800		dyna ; ;	equ	Øf800h ;Start	of ram driver code
		;	Here We	go!	
0000'			.28Ø		
0000			aseg org 100	h	
		;	019 100		
		;	load,pa	tch and set up p	io
0100	21 Ø12C	ddyna:	ld	hl,begdyn	;start of code
Ø1Ø3 Ø1Ø6	11 F800 01 0149		ld	de,dyna	;Destination
Ø106 Ø109	01 0149 ED BØ		ld ldir	bc,enddyn-begdy	
0109	ED BU	;	lall		;go to it!
Ø1ØB	3E Ø2	•	ld	a,02 ;Select	disk driver two
Ø1ØD	32 F368		ld	(seltab),a	;Store in table
0110	Ø1 F8ØØ	;	1.4	ha wamdara	etart of driver
Ø113	ED 43 F384		1d 1d	bc,ramdvr (dvrtab),bc	;start of driver ;Go stuff it
		;		· · · = · / /	
		;	Set up	pio	
Ø117	3E 8F	;	ld	a,8fh ;A side	for r/w
0119	D3 Ø9		out	(actl),a	/

nector J8 on the 820-II motherboard and the pinout is the same as J5 on the BB I.

Software

Since I used a version of CP/M for the BB I, I was able to use all of the utility software that came with the Dynadisk. Along with the necessary driver, the Dynadisk comes with a format routine and an extensive test routine. I had an early version of the Dynadisk driver routine, so several changes were required before the driver software would work correctly. Tony has since corrected and released a new version of the software.

The format program must be patched in order to work with the 820-II. The HE-XOUT routine used by the format program is located in a different location in the 820-II monitor than in the BB I. Change locations in DFORMAT.COM with DDT.

014D CDF3D2 should be CDFC1B 01F3 CDF3D2 should be CDFC1B

This is the only change required to use the software distributed with the Dynadisk. But in order to use the CBIOS that comes with the 820-II the next step was to write a driver routine for the Dynadisk which would work with the 820-II software. Two problems had to be resolved.

First the 820-II uses drives A-D for the two floppy disks so I chose drive E for the Dynadisk instead of drive D used by the standard BB I Dynadisk software.

The second problem was the 820-II monitor. There is no listing available for the ROM monitor used in the 820-II and it is radically different from the monitor used in either the BB I or the 820-I. The only solution was to disassemble the monitor which was a slow and tedious process.

The 820-II monitor uses the loadable disk drivers and a standardized command block to communicate with all disk drivers. Two tables in RAM are used to reference the correct driver for each drive. The standard 820-II has two disk drivers built in. One for the floppies and one for the SASI interface option. At boot time the correct driver is configured

(continued on page 12)

Ø11B 3E CF 1đ a,Øcfh ;B side 4 out 4 in Ø11D D3 ØB out (bctl).a a,ØfØh Ø11F 3E FØ ld Ø121 D3 ØВ out (bctl),a ; Ø123 3E ØA 1d a,drfsh ;turn on refresh Ø125 (dcsr),a D3 ØA out Ø127 DB Ø8 in a,(ddata) ;clear ready line ; Ø129 C3 ØØØØ a ;GO TO CPM!! jp ; Here is the disk handler; ; ; ; On entry HL points to a command block wit following information. ; ; ; HL -> defb command -l=select,l=read, defb logicalunit defb physicalunit defw track defw sector ; defw address buffer Ø12C begdyn equ .phase dyna F8ØØ ramdvr: 1d 7 E a,(hl) ;get command F8Ø1 3C inc F8Ø2 28 50 z,select jr ; Not select so set up for read/write ; ; F8Ø4 E5 push hl ;address of cmd block F8Ø5 23 h1 inc F8Ø6 23 inc h1 F8Ø7 23 inc h1 F8Ø8 5E lđ e,(hl) ;track number to DE F809 23 hì inc 56 F8ØA 1d d,(h1) F8ØB 23 inc h1 7E F8ØC 1d a;(h1) ;A = sector F8ØD 23 inc hl 23 F8ØE inc h1 ;pointer to buffer add. F8ØF E5 push hl ;sector is Ø-25 F81Ø 3D dec а F811 EB de,hl ;hl = Track ex ; hl = track; a = sector-1 ; Compute ramadd = $26 \times trk + (sector - 1)$; ; F812 29 add hl,hl ;2*trk F813 E5 push hl F814 D1 pop de F815 29 àđđ hl,hl 4*trk F816 29 add hl,hl ;8*trk F817 E5 push hl cī F818 pop bc 29 F819 add hl,hl ;16*trk ø9 F81A add hl,bc + 8*trk F81B 19 2*trk = 26*trkadd hl,de + F81C 4F 1đ c,a Ø6 ØØ F81D b,Ø lđ :bc= sector-1 Ø9 F81F add hl,bc ;hl= 26*trk + sector-1 ; output to ramdsk ; ; 1 = sector ; h = track ; ; F82Ø 3E Ø8 1d a.dtrack :trk register F822 D3 ØA (dcsr),a out F824 7C a,h lđ ;get track value D3 Ø8 F825 out (ddata).a ; F827 3E Ø9 14 a,dsect :sector register F829 D3 ØA out (dcsr),a ;get sector value F82B 7D lđ a.1 F82C D3 Ø8 out (ddata),a ; now get buffer address and set up for r/w ; F82E Ε1 pop hl F82F 5E īď e,(hl) F83Ø 23 inc h1 ;de = address F831 56 1d d,(h1) ;h1 F832 E1 h1 = address of cmd pop (Listing continued on page 12)

XEROX 820 - DYNADISK INTERFACE

(continued)

into the monitor depending on which interface is installed in the 820-II.

Adding a disk driver for the Dynadisk turned out to be an easier task than I expected (if you overlook the two months spent disassembling the monitor). Each driver has a single entry point and is required to handle three requests; select, read, and write. The read and write requests read or write one sector of information from the track and sector contained in the command block. The select request has to do nothing except return the address of the CP/M disk descriptor block.

The listing contains the complete driver code required to support the Dynadisk as drive E on an 820-II. Note that the sector translate routine is not required by the Dynadisk but it is required by the warm boot routine in the 820-II CBIOS.

Usage

The best way to use the Dynadisk is to bring the system up using a floppy and then copy any compilers and editors you will be using to the Dynadisk and swap the A and E drives using the swap program which is an 820-II utility (SWAP A=E). Then all of the disk accesses will be done using the Dynadisk as the logged in A drive. The A floppy drive can be accessed an drive E.

One thing to remember is that when the power goes off all of the data which was on the Dynadisk goes into the bit bucket. So save all your work before you shut off the power!


Is it worth it? Yes, the performance increase is excellent. Warm boots occur in the blink of an eye and assemblies and compiles are blindingly fast.

I want to thank Tony Ozrelic for designing an excellent product and for being so helpful over the telephone.

CBIOS PATCH LISTING (continued)

CBIOS PA	TCH L	.ISTING (con	tinued)				
F833	Ø6 80	ø		1d	b,128	;sector	length
F835 F836	7E ØE Ø8	0		1đ 1đ	a,(hl)	;r/w = 1	
F838	EB	5		ex	de,hl	;c = dat ;hl = bu	iffer address
F839	3D	_		dec	a .		
F83A	28 ØI	В	;	jr	z,read		
			;	Write re	equest		
F83C	3E Ø4	4	;	lđ	a,dwrite	2	;ramdsk to write
F83E	D3 Ø7	A		out	(dcsr),		
F84Ø F842	ED B3 CD F8			otir call	rfshon		;do write ;turn refresh on
F845	AF			xor	a		;no error allowed
F846	C9			ret			
			;;	read red	quest		
F847	3E Ø0	-	; read:	1d	a draad		
F849	D3 Ø2		reau:	out	a,dread (dcsr),a	ŧ	
F84B	ED B2	2		inir			
F84D	CD F8			call	rfshon		alaan maadu lina
F85Ø F852	AF	2		in xor	a,(ddata a	1)	;clear ready line
F853	C9			ret			
			;;;	select :	ramdisk		
F854	21	200	;			·diek	rameter block
F854 F857	21 F8 AF	589	select:	xor	hl,dph a		rameter block r allowed
F858	C9			ret	- 3-6-1-		
F859 F85B	3E ØF D3 ØF		rfshon:	out	a,drfsh (dcsr),a	1	
F85D	C9			ret			
F85E	ØØ1A		; dpblk:	defw	26	;sector/	track
F86Ø	Ø3		-	defb	3	;block s	hift constant
F861 F862	07 00			defb defb	7 Ø		ask constant mask constant
F863	ØØF2			defw	242	;max blo	ck number
F865 F867	ØØ3F CØ			defw defb 110	63 3000000	;max dir ;allocat	. entries
F868	øø	•		defb	0	;mask	1011
F869	0010			defw defw	16 2	;check s	ize d tracks
F86B F86D	0002 0000			defw	Ø	, leselve	u llacks
			; ;	Sector 1	Franslate	table f	or single density
			;				or pringre according
F86F F873	Ø1 Ø7 19 Ø5		sectab:	defb defb	1,7,13,1 25,5,11,		
F877		3 Ø9 ØF		defb	23,3,9,1		
F87B		2 Ø8 ØE		defb	21,2,8,1		
F87F F883		A Ø6 ØC 3 Ø4 ØA		defb defb	20,26,6, 18,24,4,		
F887	10 16	5		defb	16,22		
F889	F86F		; dph:	defw	sectab		
F88B	0000	0000		defw	0,0,0		
F88F F891	0000 F899	F85E		defw	dirbuf,d	pb1k	
F895	F939			defw	chk,all		
F899			; dirbuf:	defs	128		
F919			all:	defs	32		
F939			chk:	defs .dephase	16		
Ø275			enddyn	equ	\$		
				end	ddyna		
Macros:		•				-	
Symbols	:						
0009	ACTL		F919	ALL		ØØØB	BCTL
Ø12C	BEGD		F939	CHK		ØØØ4	DATA
000A F899	DCSR		ØØØ8 F85E	DDATA DPBLK		Ø1ØØ F889	DDYNA DPH
ØØØC	DREA	D	000A	DRFSH		0009	DSECT
ØØØ8 F8ØØ	DTRA DYNA	CK	F384 Ø275	DVRTAB ENDDYN		ØØØ4 F8ØØ	DWRITE RAMDVR
F847	READ		0002	REF		F859	RFSHON
ØØØ8 F368	RW	מג	F86F	SECTAB		F854	SELECT TLD
- 200	SELT	U	0001	SLD		0000	
No Dot-	1	~~/~					

No Fatal error(s)



A SINGLE BOARD COMPUTER FEATURING THE INTEL 80186 (see Byte magazine April '83) THE SLICER

- Full 8MHz 16-bit microprocessor having complete software compatibility with the 8086 and 8088
- 256K Bytes of RAM plus 32K Bytes of EPROM memory capacity on board
- Floppy disk controller can run the combination of 8", 5-1/4", 3-1/2" drives simultaneously
- SASI port for hard disk controller
- Two full function RS232C serial ports with individually controlled baud rates from 50 to 38,4K baud
- 8K of EPROM contains drivers for peripherals, commands for hardware checkout and software testing

.

SLICER[™]

- Source for monitor and bios included on disk
- Bios for CP/M 86* supports 8", 5-1/4", 3-1/2" drives and the Xebec 1410 controller for hard disks
- Board size 6" x 12" power requirements +5 @ 3A, +12V @ 60mA, -12V @ 50mA
- Complete documentation included.

Sold in various forms:

THE NEW SLICER EXPANSION BOARD

- 256K bytes dynamic RAM using the 86 TMS4500 DRAM controller
- 2 RS232C serial asynchronous ports using the Signetics SC2681 serial communications circuit with baud rates selectable from 38.4K baud to 50 baud
- 2 RS232C serial asynchronous ports using the Zilog 8530 SCC with header connectors for synchronous communications personality cards
- Real Time Clock with battery back-up using the CDP6818 RTC circuit, on-board or off-board battery

- Parallel printer port for Centronics-type printers
- Same size as the SLICER, Power: 5V @ 1.5A, +12 @ 200 mA - 12V @ 100 mA

Sold in various forms:

Assembled and tested	\$800.00
Full Kit	650,00
Memory Board	450.00
3 Port Board and Clock	
	95.00
Regular U.P.S. shipping within	continental U.S.
is included.	

Choose 8 MHz CPU for speed 6 MHz CPU for speedy delivery SLICER COMPUTERS INC. 2543 Marshall St. N.E. Minneapolis, MN 55418 (612) 788-9481

*CP/M a trademark of Digital Research, Inc.

E. Mastercard, Visa, check, money order or C.O.D. orders accepted. Please allow 4 weeks for delivery.

Pascal Procedures

John P. Jones

The first step in programming in any language should be a precise definition of the problem at hand and an outline of its solution. In many cases, this step will be the most time consuming and difficult portion of the entire project.

Program Development

Recently I needed a routine to interpret a message from another computer and perform a series of processes based on the message data and imbedded control codes. The first step was to get a definition of the input message in all of its possible forms.

1. Data in ASCII?

2. Enumeration of all possible fields.

3a. All fields in fixed positions?

3b. Fields delimited by a special character?

4. Enumeration of all possible actions.

5. Enumeration of all codes for 4.

Now the procedures to attack the problem can be logically outlined or flow charted. If the data is in ASCII (it was) the input message can be most conveniently handled as a STRING, since the built in STRING handling procedures can then be used. The first outline would be for a routine to copy the input data to a Pascal STRING variable.

If fields are not in fixed positions, a routine for scanning the data to deter-

mine field positions should then be blocked out, followed by a functional definition for a 'command interpreter.'

Finally, the repertoire of actions to be performed under control of the command interpreter should be outlined.

Start Your Coding

The actual coding can begin at this point. My method is to sequentially develop the routines for a 'test case' and then modify/expand to cover all cases. In my example, the STRING conversion routine is written and debugged using constant input data and a simple calling program before going on to live input data.

In like manner, the field extraction routine is developed first for fixed input, then for variable.

The command interpreter development is only slightly more complex. The routines for each action can be written and tested independently for fixed and variable input. These routines are later integrated into the main program by another independently written module which selects the proper function based on the control code imbedded in the field.

To interpret the input data, the main program needs only to call the STRING initializer, followed by the field extrac6245 Columbia Ave. St. Louis MO 63139 (314) 645-1596

tion routine and command interpreter for each field.

Although this example may not be of specific value to many readers it does point out the method of modular programming. First, define the problem and solution in detail and break it up into small, easily coded routines. Fully test each routine as it is written, then use these modular building blocks to construct the final program.

Variant Records

One of the more difficult data structures to understand in Pascal is the variant record. As you may recall from an earlier column, a record is a structured data type which allows the programmer to access logically related data elements as a group.

In some cases, it may be more convenient to access the person's name as a whole, rather than as last name, first name and middle initial. Rather than copying the data from the record fields into a single char array, a variant record makes this possible in a more convenient way.

The case selector, called a tag field, must be a scalar value (boolean, integer, char, enumerated) and is another field which can be manipulated within the record. The variable 'american' can be

```
Figure 1 - Pascal Examples
```

```
example 1
                                                                       example 3
  type
                                                                          type
                                                                              selector = (this, that, another);
      person_name = record
        last_name : array[1..20] of char;
       first_name : array[1..20] of char;
                                                                                strange_record = record
          initial : char:
                                                                                    recordname : string[23];
   end:
                                                                                    case which : selector of
                                                                                           this : (number : real);
                                                                                           that : (yes_or_no : boolean);
                                                                                        another : (nest : record
                                                                                                      a : integer;
                                                                                                      b : real;
                                                                                                      c : string[12];
                                                                                                           end;)
example 2
                                                                            end:
  type
      person_name = record
                                                                       example 4
       case whole : boolean of
              true : (entire_name : array[1..41] of char);
                                                                          tvpe
                        (last_name : array[1..20] of char;
             false :
                                                                                 ptr_trick = record
                       first_name : array[1..20] of char;
                                                                            case data_type : char of
                                                                                        'I' : (int : integer);
'P' : (ptr : ^integer);
                          initial : char);
   end:
                                                                                                                    {or `whatever}
                                                                           end:
   var
                                                                           var ptr_var : ptr_trick;
     american, gallifreyan, lower_slobovian : person_name;
```

accessed as either a single character array or as two smaller arrays and a char depending on the value of the field 'whole.' Maintenance and use of the tag field is the responsibility of the programmer, NOT the compiler.

In my example 2, even if american.whole = true, the variable american.initial can be modified without restriction. The tag field should be used by the programmer in IF or CASE statements to control proper access to the record's variant fields.

Variant fields do not have to be the same length, but the compiler will allocate variable space for the longest variant. The variant fields can be of entirely unrelated types.

The variant record part must be the last field in the record but since records can be fields of records, variants can be nested. Again, since the variant part must be last, the 'end' terminating the record definition suffices to terminate the variant case statement.

For many Pascal compilers, pointer types cannot be manipulated as integers even though at the binary level they are both 16 bit values. The variant record type in example 4 allows manipulation of the pointer's value as ptr_var.int and use of it as ptr_var.ptr.

To sum up for variant records, it's all in how you look at the data.

Turbo Tips

Those of you who have seen the review of Borland International's Turbo Pascal in Micro C, issue 16, will know that I have a very high opinion of this new native code Pascal system. Because of the product's reasonable price, standard syntax, and superb performance (and the uncertainty of support for the other low priced Pascal compilers), I will be presenting most of my examples in Turbo Pascal. As I come up with bits and suggestions on how to use Turbo effectively they will be included in this section of the column.

Turbo allocates storage for static variables (globals and locals for non-recursive procedures) at compile time. Because of this, a Turbo generated .COM file will not run on another machine with a smaller transient program area or on the same machine if part of the TPA is used

by another program like SUBMIT or DDT.

To get around this problem, compile the program under Turbo with the other program loaded. For example, if you want to debug an application program with DDT, use the steps:

A>DDT TURBO.COM ;load ddt, then turbo ;ddt prompt, execute Turbo

At this point, the Turbo compiler can be run normally. Select the Com option to generate a .COM file of your program. To debug the program, enter:

A>DDT PROGRAM.COM

You can then use all the DDT commands to examine the code, set breakpoints, trace etc. Since the compiler was executed with DDT resident, all variables were allocated in available memory.

When running the terminal installation program, TINST.COM, if you wish to delete a function (such as insert line) enter a minus sign '-' and TINST will reply 'nothing.' Under these circumstances, the Turbo editor will perform the required function in software rather than using a terminal function code.

For any Pascal, the statements:

i := i + 1; i := succ(i);

have the same effect but the second will be much more efficient. The first statement will generate code to execute an integer add routine, while the second will result in a simple increment.



would be a good market for an attractive yet low cost custom enclosure. We have had designed THE perfect enclosure for your Big Board and two eight inch drives. NEW LOWER PRICE

FEATURES:

- * Custom Designed for the original Big Board
- * Heavy Duty all aluminum construction.
- * Mounts Two SA800/801R or equiv. drives (Vertically).
- * Has extra space for Switching or Linear Power Supplies.

* Attractive painted cream finish with natural aluminum pre-punched backplate.

* Pre-punched cut outs for cooling fan, 3 DB25 conn., video conn, keyboard conn., on off switch, AC power filter/plug, fuse, reset switch, and cooling slots. * Built in stand offs for mounting Big Board.

* Can also be used for a dual drive enclosure for other systems besides the Big Board.

* 20 x 12 x 10.25 inches in size.

Canadian Orders add \$8 shipping

NEW LOWER PRICE: \$69.95 (add \$4 UPS) Buy 2 or more at \$65 ea. (Units shipped unassembled)

Limited Qty. of mating PAMOTOR 8500D muffin fans avail. at \$12. Limited Qty. of CDE APF600CEE 6 amp AC 3 wire receptical and line filter that fits our enclosure are avail. at \$3.50 each.

Limited Qty. of 50 conductor dual disk drive ribbon cable and connector assemblies for your Big Board. These feature GOLD Winchester Electronics connectors! \$15 each.

Add extra \$1 UPS on above 3 items. We accept VISA, MC, money orders, or cash. Personal checks OK but cause an extra 2 week delay for clearing. Texas residents add 5% sales tax. We ship to USA and Canada only. \$15 min. order. No phone orders yet

ODD BALL ELECTRONICS P.O. BOX 879 DUNCANVILLE, TEXAS 75116


FOR THE II AND 4's. GRAPHICS ADAPTER FOR KAYPRO COMPUTERS

This simple board adds most of the features of the popular Heath/Zenith H-19 terminal to your Kaypro. These include Reverse Video, Character Mode Graphics, and other advanced features. And because it emulates an existing terminal, there is a wealth of Graphics Game and Business Software packages already available for it. On all but those machines in which the ICs have been soldered in, installation is a simple matter requiring only about 15 minutes.

The Gildertluke & Co. Graphics Adapter retails for \$175.00 (California residents must add 61/2% sales tax). Please include your Kaypro's serial number with order. If you have a Kaypro II which says "KAYPRO" on the boot prompt rather than "KAYPRO II", please indicate this when you order. Dealer inquiries are invited.

AVAILABLE SOON FOR THE '+' AND 10's.

The features it will add to your Kaypro include:



ilderf lu ke

120 Midway Drive Space 013 Anaheim, Calif. 92805 (714) 776-2207

KAYPRO + MA BELL SWAP FILE FULL SIGNALMAN MARK XIL BRILLIANT

The SIGNALMAN MARK XII BRILLIANT (not [™]) MODEM does it all without a loudspeaker to wake your spouse. For KAYPRO

»»\$380.00««

110/300/1200 baud Hayes[™] compatible. INCLUDED (at NO cost) software to use it. 26 entry USER CHANGABLE directory; auto-dial/answer, Baud and file speed control, file utilities and more in SIGXII. COM plus Communication utility programs and other handy stuff with instructions on disk. Prewritten 10 entry PERMANENT directory.

Send SASE for more information.

To Order: please print your name and address (no p.o. box), 10 exact names and numbers (including 1 and area code if needed) for Permanent Directory, send \$380.00, California residents add 6½%, in Money Order or Check (add 2 weeks), COD orders add \$5.00 (Cash or Money order only on COD). No phone orders yet.

We ship prepaid UPS

SWAP FILE FULL 25530 Ave. Stanford, #203 Valencia, CA 91355

BIG BOARD XEROX 820 1/0

Get the parallel I/O you need after you've used up that one PIO on your computer. The board also has a battery backed up clockcalendar chip. Interface that with a simple triac circuit and have your computer turn itself on and off.

*Up to 4 extra PIO's *Lithium cell back up for clock *Easy assembly& installation *Stand by interru output from clock	
Bare P.C.B. 29.95 Complete kit 99.95 Assembled & tested 129.9 Shipping 2.5	
	Send check or M.O. to Goodin Peripherals P.O. Box 5867 Reno Nevada 89513 Please allow 3to6 weeks for delivery

ENTER . . . THE FUTURE!

Introductory offer

\$49.95

THIS IS THE PASCAL COMPILER EVERYBODY'S BEEN WAITING FOR... EVERYBODY EXCEPT THE COMPETITION!

Extended Pascal for your IBM PC, APPLE CP/M, MS DOS, CP/M 86, CCP/M 86 or CP/M 80 computer features:

- Full screen interactive editor providing a complete menu driven program development environment.
- 11 significant digits in floating point arithmetic.
- Built-in transcendental functions.
- Dynamic strings with full set of string handling features.
- Program chaining with common variables.
- Random access data files.
- Full support of operating system facilities.
- And much more.

ORDER YOUR COPY OF **TURBO PASCAL** TODAY TO TAKE ADVANTAGE OF OUR INTRODUCTORY SPECIAL. For Visa and MasterCard orders call toll free **1-800-227-2400 X 968 IN CA: 1-800-772-2666 X 968**

(lines open 24 hrs. a day, 7 days a week) Dealer & Distributor Inquiries welcome.

	Turbo Pascal	IBM Pascal	Pascal MT+
PRICE	49.95	300.00	595.00
Compile & Link speed	1 second!!!	97 seconds	90 seconds
Execution speed	2.2 seconds	9 seconds	3 seconds
Disk Space 16 bit 8 bit	33K w editor! 28K w editor!	300K + editor Not Available	225K + editor 168K + editor
8 and 16 bit	YES	NO	YES
built-in editor	YES	NO	NO
Generate object code	YES	YES	YES
One pass native code compiler	YES	NO	NO
Locates Run Time errors directly in source code	YES	NO	NO

LEARN TO WRITE A SPREADSHEET

Our introductory offer includes MICROCALC, a spreadsheet written in **Turbo Pascal**. It will be on your disk and ready to run. And we've included the source code to show you exactly how a spreadsheet is written!

Turbo Pascal includes a 250 page bound manual with extensive explanations and many illustrative examples.

Benchmark data based on EightQueens in "Algorithms + Data Structures = Programs" by N. Wirth, run on an IBM PC. Turbo Pascal is a trademark of Borland International. MT + is a trademark of MT MicroSystems. IBM is a trademark of International Business Machines.



My s	ystem is: 8 bit16 bit	
Oper	ating system: CP/M 80	<u></u>
CP/N	1 86MS DOSPC DOS	San
· · · · · ·	puter:Disk Format:	<u>- 190</u>
Pleas	se be sure model number and for	mat are correct.
NAN	ЛЕ:	이 안님의 전 영상 위험
ADE	DRESS:	
CIT	Y/STATE/ZIP:	
TEL	EPHONE:	
Californ	nia residents add 61/2% sales tax. Outside Checks must be on a U.S. Bank, and in L	

The Kaypro Column

By David Thompson

K aypro is distributing an update package for the early Kaypro 10 (the one with the Tandon drives) that lets you boot off the floppy.

All systems are supposed to automatically boot off the floppy if there is a disk in the drive but only the more recent systems can do it. Format and Sysgen a floppy with your 10, then hit the reset button with the new disk in place and see if the system will boot off the floppy (the winchester light will not come on). If yours will not boot off the floppy, then you need to get the free upgrade kit from your dealer.

The update package includes a new monitor ROM and a disk of new software. However, the ROM they send is a 250ns part (2732A-25) while the ROM that came in the 10 was rated at 200ns (2732A-20). The first replacement ROM that I got wouldn't run at all, so I swapped it for another and the second one seemed to work fine.

After I put the lid on the system and started using it, it got flaky. It would lock up sometimes, ignoring the keyboard other times it would just reboot with no warning.

So I erased the ROM that had come in my 10 and burned in information from the new (slower) ROM. This cured the flakiness.


So, if you are having random problems with a Kaypro 10, check the monitor ROM, U42. If it is a 250ns part, you should see about getting a faster part. Note that the monitor ROM is a little hard to find since it is tucked under the drive cable. In fact, the cable may well be contributing to the heat problem so if you are desperate, you might prop the cable up away from the ROM temporarily while you're getting a new part.

This ROM problem makes me suspect that there are some hardware timing problems on the Kaypro 10. A select line or a data buffer may be slow, causing critical timing problems.

We've found that IIs and 4s will be absolutely reliable at 5 MHz with the 250 ns ROMs but the 10s will not work at 4 MHz with the same parts.

Sponge

All of you with fans on your Kaypros (and bells on your toes) should remem-



ber to check the little sponge filter behind the fan. That little filter doesn't look like it would filter much, but it sure can clog up. When it does, you get the noise but no action.

Just pull off the little plastic cover and rinse out the sponge. That's all there is to it.

KIPS

Ireceived a "newsletter" from Custom Electronics of Fresno, California. The "newsletter" is called KIPS (Kaypro Information Peripherals and Software) and for \$14.95 per year, you are supposed to get: "Periodical mailings of Hardware and Software tips from users nationwide." You are also supposed to be able to purchase all kinds of Kaypro products at "KIPS DISCOUNT PRICES."

Well, KIPS is really just a 36 page catalog with 3 pages of tips. In these three pages they cover the latest from Kaypro, such as:

The Kaypro 10 has a built-in 10 Meg hard disk. The Kaypro 4 is a Kaypro II with "double sided double density disks." (No mention of the drives.) And that when you have a Kaypro, you have "the ability to dedicate the computer to any language you might want to learn."

After all this, they review JRT Pascal and benchmark it against SBASIC. No indication of the programs they ran, though they called them "time trails." (Yep, trails, which may mean it was a foot race.)

So, we turn to the other 33 pages in this "mag." Here you can purchase at "discount" a Gemini 10X that they say retails for \$499 (retail is really \$399) and which they will sell for \$339.95. (The usually mail order price for this printer is between \$269.95 and \$299.95.) It also appears that they are selling a public domain accounting package for \$199.95 (without manuals). For another \$149.95, they'll send you the documentation!


They also sell a Kaypro II monitor ROM with a custom sign-on. You get 23 characters on the first line and 17 on the second. This is very interesting since I designed a custom monitor ROM for the Kaypro II with 23 characters on the first line and 17 on the second. (When you design something in this business, you never know who will wind up selling it!)

The KIPS people included an advertising cover letter, just in case we might want to put our ad in their "magazine." The letter noted that they would be glad to run any editorial material we wrote about ourselves, if we bought advertising. I may be old fashioned, but that's definitely not my idea of ethical journalism.

PRO-8

Dana and I have gotten some calls from people who are trying to use the PRO-8 copy programs to copy one format disk (say a Kaypro II disk) to another format (say Kaypro 4 or 8). These track copy programs will only copy between two disks of the same format.

So, if you want to format and copy to a disk that is different from the source disk, do the following: Choose the correct version of COPY, select the "O" option and then either "F" to format in B: or "X" to format drive A:. After you have formatted the disk(s), exit the COPY routine and use SYSGEN.COM (comes with CP/M) to put system tracks onto the disk (don't use the "SYSGEN" built into the copy program, it wipes out the system tracks if the disks are formatted differently). Then use PIP.COM to transfer the files.



There is also one small bug in the "2on8" routine. If you put an 80-track drive in A:, this program will not properly format a Kaypro II disk in A:. The following will fix the problem.

A>ddt 20n8.com DDT VERS 2.2 NEXT PC 1F80 0100 -s732 0732 FC f8 0733 F5 . -cnt1-C A>save 30 New2on8.com

In other words, changing the byte at 732 (hex) from FC (hex) to F8 (hex) makes everything work properly.

Tandon 101-4

Tandon has begun shipping a new drive called the 101-4. We've had problem reports from users who have this drive. We borrowed a 101-4 long enough to bring it up on our Kaypro II.

The most remarkable thing about this drive is that it is practically silent. I mean, that little stepper just doesn't realize what steppers are supposed to sound like. It is great. Anyway, check out the following if you have one of these. 1. Be sure that only one drive is terminated (two terminators will overwhelm the driver). The terminators look like blue ICs.

2. Set up the jumpers as follows: W9 open, W19 closed, Jumper on W13 for 6 ms step rate. W10, W11, W12, and W14 should be left open.

3. Drive select is done by W1-W4. If this will be drive A: then jumper W1, if B: jumper W2. The rest of the board should be jumpered correctly as shipped.

4. Be sure you power down the system after setting the jumpers. The onboard processor only checks the jumpers at power-up.

5. You may have to hit the reset button a few seconds after you power-up since these drives take a while to check themselves out.

6. Remember the COPY programs will usually only run at 2.5 MHz.

So far, however, the older Tandon 100-4, as well as the TEAC, and CDC quad density units have been flawless and we've gotten no reports of problems with any of the double and single sided 48 tpi drives.

TEAC

The TEAC drives have the ribbon con-

nectors mounted upside down from other drives so you might wind up finding that your drive data cable is too short if you have one TEAC drive and one Tandon. If they are both TEACs, then you are OK.

CDC

On these drives, be sure to jumper "M." Also jumper the drive number, 1 for drive A:, 2 for drive B: and so on.

Four Drives on the 4

All of the PRO-8 monitor ROMs we've shipped in the last 2 months support 4 drives as well as 2 (see, there is such a thing as a free lunch). That means that you will be able to use two outboard drives as C: and D: if you add a simple drive decoder circuit and the necessary data and power cables. If you get the TEAC half-wide drives you can mount all four drives inside the cabinet and run the whole thing off the built-in supply since the TEACs use only half the power (as well as half the space) of the Tandons. The Tandon and CDC drives will require separate power supplies. The ROMs that support four drives have +'s around the

(continued on next page)

ROM sign-on message (so we call them PRO-8+ ROMs).

We will have a complete Plus-2 package for the PRO-8+. The package will include the decoder board and a disk with the additional formatting and system utilities that you will need for four drives. We're also getting prices on complete cables so if you don't want to build your own we'll have them. More information on these in issue #18.

Note that this will be the genuine Micro C decoder board. You'll be the envy of all the Kaypro users on your block when you show them your very own Micro C decoder. We're waiting for Batman and Robin to order their own copy of this beauty.

Anyway, this way you can leave your original drives in place, if you wish, and add two more of any type (191K, 380K, or 784K) outboard or you can replace your present drives with up to four halfwides (of any persuasion) and not have anything hanging out.

Kaypro II Version A

During the Spring of 83, Kaypro spent several months trying to clean up a disk error problem. During this period they went through three new versions of their monitor ROM. The monitor ROMs (U47) were marked (on the paper stuck on the ROM) with an 'A', 'B', or 'C' suffix. Kaypro shipped a few 'A' versions and almost none of the 'B' versions (I understand they had a bad bug), before they went to the 'C' versions which they are still shipping.

I hadn't been able to find anyone who could tell me what they changed from version to version, but now, thanks to a letter from Terry Kingrey, I have a pretty good clue.

Terry tried installing one of our PROmonitor ROMs on his system but it didn't work (he hadn't told us that he had one of the 'A' ROMs). So he tried substituting parts on his Kaypro to see if he had a defective chip (we would have told him not to bother). He didn't have a 1797 floppy disk controller to swap with the one on his board so he substituted a 1793 from a friend's Kaypro. After he substituted in the 1793 he found that his system worked just fine with our PROmonitor ROM.

That news sent Dana and I to the Western Digital book to see what the dif-

ferences were between the 1793 and the 1797. The 1797 does side select and the 1793 doesn't, but Kaypro isn't using that line. However, the 1797 requires a sector size bit, the 1793 doesn't. That could be the difference.

Anyway, if you are one of the select few with an 'A' version of the Kaypro, it looks like you can upgrade to one of the PRO-monitors (II, 4, or 8) if you will replace your 1797 with a 1793 disk controller. 1793s cost about \$25.00 each. You can order them from Unicorn Electronics 213-341-8833.

If you have a ROM with no suffix or with a 'C' suffix you are just fine. You have the 1793 disk controller already.

Oh, and thanks a bunch, Terry, for the letter. We couldn't have done it without you.

Close Look at the New Kaypro 4

I had heard that the new Kaypro 4 had a Kaypro 10 board, two 390K drives, plus a battery backed-up timer and modem. Whee!

It turns out that the new 4 board is more than just the 10 board with two additions. It contains two new 40-pin ICs that replace a lot of standard ttl chips.

One of them is dedicated to the video section and it looks like the graphics department just got a lot smarter and easier to use (is someone planning 1,2,3 for the Kaypro?).

All the Kaypros will soon contain this new board and meanwhile they've just dropped the price of the Kaypro II to \$1295 (and the board is running 4MHz besides!).

Advantages

Kaypro has added a lot of the features that independent suppliers have been selling (which is unusual for a large manufacturer). Obviously Kaypro has been listening to users.

Also, if Kaypro can resist making changes for a while, you'll see a lot of hardware and software coming out for this board. After all, people will only have to design a product once and it will work on all the new Kaypros.

Disadvantage

However, a lot of present upgrades will not now work on the new board. Dana will be working on new monitor ROMs but, of course, those new ROMs aren't done yet. So those of you with a Kaypro 4 with graphics and two halfwide drives will have to wait a while before making your system distinctive.

And, those of you planning to purchase a Kaypro 10 might want to wait a month or so and then make sure you will be getting a system with the built-in modem.

The MODEM

The built-in modem is a very simple 300 baud direct connect unit. It is locked at 300 baud for now because its UART (asynchronous serial chip) is tied to the same half of the 8116 baud rate generator as the keyboard SIO. Since the keyboard communicates at 300 baud it's obvious that Kaypro figured it could save the price of another baud rate generator by using the same clock twice.

However, until we come up with something sneaky (and if it's sneaky, it's right down our alley) you'll lose use of your keyboard if you try running the modem at, say, 450 baud.

Support For Fat Jack

As a technical journal, we've considered ourselves above the jungle of Kaypro add-ons such as legs (a 1 by 2 board mounted underneath the front gives it a great "pair" of legs), stands (I can't stand them) and reading racks (if God had meant for me to have a reading rack he would have taught me how to read).

However, the Twist people sent us one of the Fat Jack reading racks and a pageclip (which holds books open when they are on the rack). The rack easily hooks to the top of the Kaypro and holds books or papers at just the right level.

Then Sandy spied the rack and started using it. She loved it. In fact, she wouldn't even let me borrow it.

Well, anyone who puts out a product that Sandy won't loan me, and then supports it like this, has earned a mention in Micro C.

Fat Jack Reading Rack \$17.95 Twist Inc PO Box 1406 Renton, WA 98057





FAT JACK READING RACK

- ★ SEE COPY-SCREEN/KEYBOARD AT THE SAME TIME.
- ★ EASILY ATTACHED TO ANY KAYPRO[™]
- ★ 16" WIDE AND STRONG FULLY SUPPORTS - BOOKS MAGAZINES ● REPORTS WITH UNIQUE PAGECLIP[™]

Dealer and group inquiries invited.

ONLY \$17.95 + \$1.50 Shipping (Continental U.S.A.) Washington Residents Add \$1.45 Sales Tax. Cashier Checks & Money Orders Shipped Promptly. (Personal Checks Must Clear – 2 Weeks.) (Price & Configuration subject to change without notice.)

The Best Accessory You'll Ever Buy For Your Kaypro™


ORDER FROM: TWIST, INC. P.O. Box 1406, Renton, WA 98057

S-BASIC TUTORIAL AVAILABLE

Approximately 120 pages of letter size sheets for 3-ring binder covering the aspects of S-Basic Programming (with references to M-Basic)

Send \$20.00 money order (to cover cost for copying and mailing) to:

Sven Erlandsson 3268 Leon Brisebois Ile Bizard, Quebec Canada, H9C 1W2



A LOW COST ALTERNATIVE TO EPROM PROGRAMMING

Reads and programs 2716, 2732, 2764, and 27128 EPROMS. Reads 2-16K ROMS.

Direct connect to any RS232C terminal or computer. Plug selectable as either a data set or data terminal.

All voltages made on board, (no power supplies needed). (User supplies power Xformer, 25.2 to 30 VAC C.T.1 Amp.). Power electronically switched, (can't damage EPROMS).

Zero insertion force socket for EPROM.

Programs, verifies, and dumps in both ASCII and hex.

Edit buffer (like DDT).

Saves hex and/or image files to and from disk.

Saves or loads all or partial buffer.

Completely menu driven for ease of operation.

Commands of Test, Read, Display, Save, Load, Program and more. Check sum calculation.

All software on disk including well commented source code.

Detailed owners manual including schematic

All chips socketed.

Not a kit! Completely built and tested.

48 hour dynamic burn in and test before shipment.

90 day limited warranty on parts and workmanship.

24 hour return policy on repairs.

Delivery from stock.

NOTICE TO PREVIOUS CUSTOMERS: Send us your old disk and a suitable S.A.S.E. for your free copy of our new software, ver. 1.6. PROGRAMMER 4+ WITH OWNERS MANUAL AND DISK. \$199.95

Order from



VISA and MASTERCARD telephone orders welcome.

Please specify Disk format CP/M 8" IBM format, KAYPRO II, XEROX 820, OSBORNE I, others.

Please specify method of shipment, UPS or Postal Service. California residents add 6% Sales Tax. Dealer Inquiries invited.

SBASIC Column

By Jack Rodenhi

Think how rough it would be if every time you wanted to go somewhere, you had to re-invent your car. Likewise, a good programmer will have a library of programming tools for tasks he performs frequently.

In upcoming issues of Micro C, we will put together several tools in SBASIC. The overall game plan is to eventually come up with a program that will demonstrate the desirability of developing software tools, and at the same time, develop a program that will do something useful, like creating a checkbook database program.

Input.bas

The first part of the program involves data input. The classiest kind of input routine is the type used by dBASE II in it's full screen editing mode. So let's do that kind.

One of the nice things about a structured language like SBASIC is that if you don't like the words it comes with, you

can make up your own. We are going to invent the input routine called input4 to go along with the other input statements provided by SBASIC.

Declarations and definitions

The first two sections of code in our input tool are variable declarations and constant definitions. Because global variables make more work when we chain programs and they represent permanent space allocation, we will keep these to a minimum.

Speed is very important in this routine, however, and we will save a good deal of time by not reinitializing these variables on every pass through this routine. Turning off line number generation with the compiler directive "\$lines" will also save time and space.

Cursor commands

Next comes the cursor procedure. With this procedure, we don't have to type "print chr(26)", etc. every time we

EXPAND YOUR BIG BOARD More Memory * More Ports

Rivendell Audiocomp announces an innovative expansion board for your BBI, featuring:

ADD MEMORY

- 4 rows of dynamic RAMs, providing up to 256K (with 64K RAMs) or 1 Mb (with 256K RAMs)
- 32K ROM or CMOS static 2 8-bit D/A converters RAM (8K x 8 devices)

OTHER FEATURES

- Same size as BB1-piggyback mount
- Complex sound generator
- Counter/timer
- Real-time clock
- Plus many more hardware features

Rivendell Audiocomp

Custom Audio and Computer Design

ADD PORTS

- 2 RS-232 serial ports
- 4 buffered parallel ports
- 8-input 8-bit A/D converter

Available as bare-board kit. For more information and prices, write to: Rivendell Audiocomp P.O. Box 28937 San Diego, CA 92128

619-451-3424

1317 W. College Ave. Lompoc CA 93436

want to clear the screen, etc. We just say cursor "up", cursor "down", cursor "erase", cursor "roll over" and so on. You may have to change some of the print commands if you don't have a Kaypro.

Cursor positioning

To position the cursor on the screen, the programmer just enters the row and column and the @ procedure will take care of the rest. Do that a few times without this routine and you'll really grow to appreciate the power of structured programming. Again, this works for the Kaypro and may need modification for use elsewhere.

String search

The "in" function is something I sort of stole from Pascal. Pascal has a neat set operator called "in" and a few predefined sets.

However, in SBASIC we'll have to define our own sets of characters as strings and use this string search function to determine if our test character is in the set. Notice that this function returns a 't' or an 'f'.

In SBASIC these characters are taken for boolean results. This means that we don't have to say "if in(format_set) = 't' ", we can just say "if in(format_set)". We defined the sets at the beginning of the program and the next procedure uses these sets to test input characters.

A Test of Character

The test procedure compares a key to one of our defined sets. Which set to compare to is accomplished by the case statement and the "picture_char."

The comparison is assumed to yield a false and then if the comparison works, it is changed to true. We have given ourselves only four choices here, but this list can be expanded to whatever extent is convenient. A boolean picture_char would probably be very useful.

Get some character


Now, let's look at the routine getkey which is the workhorse for our input tool. This routine was inspired by the book Advanced Pascal Programming Techniques by Paul A. Sand and published by Osborne/McGraw-Hill. This excellent

(Column continued on page 25)

Figure 1 - SBASIC Tools

```
$lines
var numbers, boolean_set = string : 12;
var control_set,small_letters, cap_letters = string:27;
var letters = string : 53
var format_set = string : 5
var ch, control = char
control\_set = chr(13)+chr(05)+chr(24)+chr(25)+chr(08)+chr(04)
numbers = "0123456789.-"
cap_letters = "ABCDEFGHIJKLMNOPQRSTUVWXYZ "
small_letters = "abcdefghijklmnopqrstuvwxyz"
letters = small_letters + cap_letters + ":;?<>@&"
boolean_set = "YyNnTtFf"
format_set = "9ABX!"
procedure cursor(command = string)
    case command of
        "erase": print chr$(26);
         "beep": print chr$(7);
         "left": print chr$(8);
         "down": print chr$(10);
           "up": print chr$(11);
    "right": print chr$(12);
"cleareos": print chr$(23);
    "cleareol": print chr$(24);
    end
end
procedure \theta(row, column = integer)
    print chr$(27)+"="+chr$(row+32)+chr$(column+32);
end
function in(test_set = string : 60; subject = char) = char
    var result = char
    result = 'f'
    if instr(1,test_set,subject) <> 0 then result = 't'
end = result
function test(key = string :1; picture_char = char) = char
    var ok = char
    ok = 'f'
    if in (control_set,key) then ok = 't' else
    begin
        case picture_char of
             '9' : if in(numbers,key) then ok = 't'
'A' : if in(letters,key) then ok = 't'
              'B' : if in(boolean_set,key) then ok = 't'
              'X' : ok = 't'
             '!' : if in(cap_letters,key) then ok = 't'
         end
    end
end = ok
function getkey (picture_char = char) = char
    var key, ok = char
    repeat
    begin
         echo off
         input3 key
         echo on
        if picture_char = '!' and in(small_letters,key)\
            then key = chr(asc(key)-32)
         ok = test(key,picture_char)
         if not ok then
         begin
             cursor "beep"
        end
    end
    until ok
    ch = key
end = key
function mask(model = string :80) = string
    var mask = string : 82
var position = integer
    mask = space$(len(model))
    for position = 1 to len(model)
         if in(format_set,mid(model,position,1)) then\
         mid$(mask, position, 1) = '_'\
         else mid$(mask, position, 1) = mid(model, position, 1)
    next
    mask = ':' + mask + ':'
end = mask
```

```
function input4(row, col = byte; picture, default = string) = string
    var position, done = byte
    var max_length = integer
    var input_line, response = string :82
    control.c.trap off
    max_length = len(picture)
    done = 'f'
    response = default + space$(max_length-len(default))
    input_line = mask(picture)
    @ row,col
    print input_line
    position = 1
    e row,col+position
print default;
    @ row, col+position
    repeat
    begin
        if in(format_set,mid(picture,position,1)) then begin
            case getkey(mid(picture, position, 1)) of
              chr(13) : done = 't'
              chr(05):
                         begin
                              done = 't'
                              control = 'e'
                          end
              chr(24) : begin
                             done = 't'
                             control = 'x'
                         end
              chr(25) : begin
                             response = ' '
                             @ row,col
                             print input_line
                             position = 1
                             @ row, col+position
                         end
              chr(08) : begin
                        if position > 1 then position = position - 1
                        while not in(format_set,mid(picture,position,1))\
                         and position > 1 do begin
                            position = position -
                        end
                        mid$(response,position,1)=' '
                        @ row,col+position
                        print '_'
                        @ row, col+position
                        end
              chr(04) : position = position + 1
             ch
                      : begin
                                 mid$(response,position,1) = ch
                                 @ row, col+position
                                 print ch;
                                 position = position + 1
                        end
            end
        end
        else begin
            while not in(format_set,mid(picture,position,1))\
              and position <= max_length do position = position + 1
        end
        @ row,col+position
    if position > max_length then done = 't'
    end
until done
end = response
remark : the main application begins here
var x, y = integer
var format, autoanswer, answer = string : 80
var again = char
repeat begin
    cursor "erase"
    input2 "Please enter screen coordinates as 'row, column' ";x,y
    print "Please enter input mask using 9's, A's, B's, X's and I's "
    input2 format
    print "Please enter default response "
    input2 autoanswer
    answer = input4(x,y,format,autoanswer)
    € x+1.y
    print answer
    print "Do you want to do it again?"
    again = input4(x+3,y,"B","Y")
end
until not again
                                                             END
```



SINGLE BOARD

COMPUTER

dove grey; front, back and side accents black. Mounts 2 SHUGART SA851R EIGHT INCH FLOPPY DISK DRIVES or MECHANICAL EQUIVALENT*. Lighted reset switch on front panel. Lamp supplied, but not connected. 4 DB25, 1 Delta 50, 1 Centronics connector cutouts, two switched ac receptacles, 6' three wire line cord, EMI filter, 70CFM fan with washable dust filter, line fuse, power switch on rear panel. P2901 removable module power supply: +5@3A, +12@.5A - 12@.5A for computer; +5@2.5A, +24@2.5A-4A peak, -5@.25A for disk drives. Includes power cable from power supply to computer (unterminated wires at computer end) and power cable to 2 disk drives (specify single or double sided drives when ordering).

POWER SUPPLY & ENCLOSURE AVAILABLE SEPARATELY





(SBASIC Column continued)

book will be the source of many useful SBASIC routines if you take the time to do the minimal translation necessary.

With the above routines, the getkey function is easy to accomplish. Getkey simply accepts a key and tests it.

Before the test, getkey will change small letters to capitals if desired. The ASCII codes for small letters are 32 greater than the ASCII codes for their corresponding capital characters.

If the key tests OK then getkey returns to the calling routine. Getkey also sets the global variable "ch" equal to the result of getkey. This allows the calling routine to use the value later.

Role Model

The last thing we want to do before we jump into input4 is provide an input line for the operator to see when entering data. The mask function will build an input line called a mask from the "model" sent to it as a parameter. It builds the mask character by character, substituting underlines for positions occupied by members of the format_set and printing all other characters in their respective positions.


Ready, Input!

On to input4. Input4 is declared as a function rather than a procedure to facilitate later code writing. To use input4, you pass it four parameters. That is, you have to tell it where you want the input to appear on the screen (row and col), what characters will be acceptable in what positions, and what answer should be taken as the default.

We turn the cntl-C trap off because we want everything done under program control. We are going to repeatedly get one key and add it to our "response" until done. Optionally, we can, if certain control keys are pressed, erase the entire line, go to the next or the prior entry or whatever else might be desirable and useful to program in.

How will we know when we are done? If the response is as many characters as were requested or if the operator presses the return key, we will be done.

We initially set the variable "done" to "f". Then we let response equal the default until we know better. Because the string insertion routine needs a string to insert into, we pad the default with spaces to the length of the picture passed to input4. We make a variable called input_line equal to a mask based on the picture. Then we print the default over that.



Now the screen is formatted and the program is ready to accept input. We only want to look for input at those positions in the picture that input is appropriate. So if the character at the current position in the picture is in the format_O set, we will accept input. Otherwise, we go past the case structure entirely and skip over picture characters until we find another in the format_set or we reach the end of the picture.

If we are accepting input, the character input can be any one of the members of the control_set or any other character that will pass by getkey's test step. The case structure oversees execution of the operation for each of the members of the control set that may come through.

The last case is one of getkey returning a value of ch. Getkey always equals ch so this is our "else" statement and this is where characters are added to response.

The last part of the listing is an actual application of this set of tools. Study the application, use it and then use the routine in your programs. After a little use and fine tuning, this tool may become one of your favorites.



CP/M-86: A Close Look

By Dana Cotant

The amount of CP/M-86 software contributed to Micro Cornucopia has not increased since we put out the three Slicer disks about 6 months ago. After speaking with some of you I have the impression that many programmers are uneasy with the prospect of starting anew in this 16 bit environment.

I can certainly understand your apprehension about abandoning your bag of CP/M-80 tricks, but you don't have to start over from the beginning. Actually, the CP/M-86 environment frees you from a lot of the routines you developed for CP/M-80 because of the incredible capabilities of the 8088, 8086 and 80186 microprocessors (hereafter called the 86).

The Documentation

CP/M-86 comes with three separate manuals. The User Guide explains PIP, ED, and the basic operating system commands. The Programmer's Guide covers ASM86 and DDT86 in considerably more detail than the CP/M-80 documentation.

Technical information on the CP/M-86 operating system is in the System Guide, which covers system generation, system interface, and memory management. This manual is not much better than the CP/M 2.2 interface and alteration guides but it provides most of the needed information (if you are already familiar with CP/M-80).

The CP/M-86 assembler

Probably the greatest concern is the assembler. ASM certainly left a lot to be desired which is probably why most CP/M-80 assembly language programmers bought MicroSoft's M80 assembler. ASM86 is a definite improvement but it's no M80.

There is no provision for linking assembled modules though the assembler has an include directive for loading source files from the disk. You can even use an underscore in an identifier to make it more readable.

86 assembly language

The 86 instruction set is a vast improvement over the 8080 set. The 86 instructions are more general, depending on the operands to determine the type of manipulation. The same mnemonic is used to perform a register to register data move as a data to register move.

Most instructions follow the general form OPERATEON (destination), (source) where (destination) and (source) can be any of the usual operands without requiring a change in the instruction mnemonic itself. This improvement provides a comfortable environment for the Z80 programmer who hates the illogical 8080 instructions.

There are enough new instructions available in the 86 set to entice even high-level language programmers. Most noticeable are the string manipulation instructions including compare and scan string operations. Multiplication and division are also done with single instructions.

Z80 programmers will appreciate the repeat and loop instructions but unfortunately the bit-wise operators found in the Z80 instruction set were not included in the 86 set. You will have to go back to OR, XOR, AND, and the rotate instructions to set and test individual bits.

Addressing

The incredible addressing capabilities of the 86 sets it apart from the 8 bit microprocessors. The 86 has a 20 bit address bus which gives it a 1 megabyte addressing capability. Rather than having to use two 16-bit registers to hold a single address and the resulting code bulk, addresses are described by a 16 bit number. Sixteen bits can address 64K bytes of memory (which is called a memory segment).

The location of a 64K segment in the 1 megabyte memory range is described by a segment register. In this way a program can be run any where in memory without changing a single address. All you have to do is change the segment register.

This addressing scheme allows a program to load and execute another program in another memory segment. At first glance this seems like concurrence but since there are no provisions for detaching from a program to run another program, it is not a true concurrent operation.

Still it allows programs like DDT-86 to test a program without relocating. DDT-86 loads into one memory segment and loads the program under test into another. By controlling the segment registers DDT-86 can run the test program or return to its own routines.

In 86 programs the data, code and stack usually lie in different memory segments. There is a segment register for each, and each may be up to 64K. There is also a segment called an "extra segment" if extra data space is needed. These four segment registers are contained in the CPU.

Addresses, either for the program counter or for program addressing are generated using the segment registers and a second operand. The operand can be an offset from another register, an absolute offset, index to a memory location from another register, or a relative address. There are seven addressing modes not counting the operand combinations. I believe this is what scares off most 8-bit programmers but it need not be a problem.

The 8080 Model

CP/M-86 has provisions for accepting programs which have code and data intermixed in a single 64K segment. This is called the 8080 model and was intended to make it easy for CP/M-80 programmers to move their programs over to the 16 bit operations with a minimum of rewriting. CP/M-86 itself was written using the 8080 model. For this reason the CP/M-86 BIOS is nearly identical to the CP/M-80 BIOS.

So, if you are going to move a program from 8080 to 86, you'll need to translate the source to 86 mnemonics and you'll have to modify slightly the way that BDOS is called (for the ASM-86 assembler). After the program is assembled, it is loaded with GENCMD (with the 8080 option set).

This way, you can ignore the complex addressing problems. The program will load at the code segment register + 100h and can expect the usual addresses in the base page for dma, file control block, and memory sizing.

GENCMD also has provisions for loading programs at absolute memory locations. The absolute address for each of the four memory segments can be specified with parameters in the command line when GENCMD is invoked. Absolute addressing is not recommend-

EPROM PROGRAMMER

interfaces to the BBI (XEROX 820) parallel port Requires +5v. @ .3A, +25v. @ .1A, interface cable

 Software and schematic Bareboard and schematic Software and bareboard Software and kit (less ZIFs) Software and full kit Programmer A + T 	29.95 39.95 64.95 99.95 129.95 149.95	
S/H within N.A. S/H foreign orders Big Board II software and source	5.00 10.00	
(uses BB II sockets for programming) Software is delivered on a 8 inch SS SD flopp	29.95 y disk	
 Program, Verify, Load and check for Erased Intel Eproms 2716, 2732(A), 2764, 27128 T.I. Eproms 2516, 2532, 2564 Xicor EEprom 2816A Uses 16k bytes of system memory as a buffe work with up to 8-2716 EPROMs at the same Upload and Download Intel Hex Files Edit the data in the 16k byte memory buffer Define your own addresses for the memory Complete screen error messages Software source included Menu driven Interfaces with most Z80 CP/M systems 	r,allowing you to e time	
options (available later) - EPROM emulator - Adapters for single chip processors		
all prices shown are in US funds	Biegun	& A
P.O. Bo	v 4071 Stn "B" W	innina

WADE-I

Universal Interface Expander

entreiser interface Expander	
Use the WADE-I U.I.E.for Intelligent Communicatio Printer Buffer Parallel driven RAM System multiplexer P/S to S/P converte AND as a BIG BOARD I or XEROX 820 PORT EXP/ Power requirements +5 volts @3A, +/-12 volts @	disk r ANDER
1. Bareboard	85.95
2. Printer buffer EPROM	14.00
3. Printer buffer source on 8" SSSD diskette	25.00
4. 4 MHz Kit (64k) with printer buffer EPROM	359.00
5. 4 MHz A + T (64k) with printer buffer EPROM	459.00
6. 64k byte bank of RAM (8-4164s 200nsec)	79.00
S/H within N.A.	10.00
S/H foreign orders	15.00
BIG BOARD I (XEROX 820) PORT EXP/ - interfaces through the Z80 CPU socket and 1 jum nect the 'IEO-IEI' daisy chain - adds 2-PIOs, SIO, CTC, and a DMA controller FULL MODE 2 INTERRUPT OPERATION - Works with 2.5MHz and 4MHz systems - Complete documentation	
STAND ALONE U.I.E.	
 256k bytes of RAM with DMA capability 4 fully buffered 8 bit parallel ports 4 Mhz - use Z80A parts and 200 nsec dynamic RA 2.5 MHz - use Z80 parts and 250 nsec dynamic RA 	

- configurable EPROM socket (2716 thru 27256)
- 4 fully buffered 8 bit parallel ports
- 2 configurable RS232C serial ports
- Complete documentation

orders shipped within 10 days A.B.O.

Associates

P.O. Box 4071, Stn "B" Winnipeg, Manitoba Canada R2W 5K8

CP/M is a trademark of Digital Research. Inc.

ed since CP/M-86 cannot be sure the requested memory is free. Some of the CP/M-86 programs on our Slicer user disks require an absolute load and the GENCMD parameters are described in the opening comments of the assembly language source.

Calling BDOS

The call to memory location 5 is missing. For this reason the operating system can be located anywhere in memory without providing both an address and an offset. BDOS is called, instead, with a 244 type interrupt.

There are 256 interrupt vectors located at the base of memory in an 86 system. The first 5 are reserved for processor operations. A software interrupt is generated by the instruction INT followed by the interrupt type. The interrupt type is multiplied by 4 to create the address to find the 32-bit interrupt vector.

When the CPU sees the INT instruction and generates the address with the operand, it then pushes the flags, the code segment register and the program counter on the stack. The code segment register and the program counter are then loaded with the interrupt vector so that the next operation will be the instruction pointed to by the vector.

All the BDOS functions in CP/M-80 have the same function numbers and parameter registers in CP/M-86. For example, to output a character to the printer, register CL (was C in CP/M-80) is loaded with the function number (05 for LST: output) and the character is loaded in DL (was E in CP/M-80). Then BDOS is called by interrupt type 244. Since the current program counter is pushed on the stack, the interrupt normally returns to the calling routine with a RETI (return from interrupt) which pops the return address off the stack and restores the flag register. This interrupt processing makes software interrupts more like a call than an interrupt and in some respects easier to use.

As a matter of fact, most CP/M functions are supported in MS-DOS by the same function numbers. The main difference is that in MS-DOS, the DOS interrupt type is 21. Thus a program written in assembly language for CP/M-86 will be transportable to MS-DOS with very few modifications.

Getting Started

It is hard to get your feet wet in a new programming environment. For me, the easiest way was to modify existing code. When you are working on different ways to make a program leaner or more elegant, it is really easy to learn the new instructions one at a time and understand their effects.

You might also try translating your favorite CP/M-80 utility to work under CP/M-86. This method provides the incentive (if the utility is really worthwhile) to get you over the "new processor" hump. High level language compilers can also be used to generate models for assembly language programming. You can compile a small program using the Small C 86 compiler and then take a close look at the assembly language output.

If the speed, improved instruction set and generous memory capacity of the 86 is not enough to entice you to try your 16-bit wings, consider the future. You may not agree that the 8-bit machine is dead (as some will tell you) but one thing is for sure, the 16-bit machines are here to stay.

FORTHwords

By Arne Henden

In this column, I would like to repeat the good news about the FORTH Interest Group, mention some new software and hardware releases, and end with a discussion of operating system interfacing.

FORTH Interest Group

I mentioned this important organization back in one of the early columns, but it is time to refresh your memory. FIG started as a northern California club and has since expanded to provide a worldwide FORTH User Group. Dues are \$15 U.S., \$27 foreign and include a subscription to FORTH Dimensions (FD), the leading FORTH journal. I definitely recommend joining FIG if you are at all interested in FORTH. Their address is: FORTH Interest Group, P. O. Box 1105, San Carlos, CA 94070.

The latest issue of FD (v.5 n.5) includes articles on calculating fixed-point logarithms, a quick sort routine, Laxon's second installment on multitasking, and a review of the 1983 FORML meeting. Many more articles are in the issue surely some would interest you!

FIG is considering the operation of a Software Exchange, to distribute public domain FORTH application software. More on this when plans are finalized.

Ever order anything by charge card from FIG? You will notice that Mountain View Press is the vendor mentioned on the charge. FIG is a low-volume organization and uses MVP for a lot of their services. Both are good groups to know and patronize.

The FIG Z-80 Listing

FIG produces fig-FORTH listings for just about every micro in existence. Tens of thousands of these listings have been sold, making fig-FORTH a familiar dialect of FORTH. Most vendors start with fig-FORTH and then customize to FORTH-79, FORTH-83, etc., adding their own enhancements. Each listing costs \$15, either from FIG or from MVP.

One of the latest listings is for the Z-80. Dennis Wilson has taken 8080 fig-FORTH and translated it into Z-80 mnemonics. The port store and fetch words were modified to use the register C indirect form. The Zilog 2-byte relative jump was inserted wherever possible to re7415 Leahy Road New Carrollton, MD 20784 (301) 552-1295

Figure 1 - BDOS Calls Through FORTH

```
( p1 p2 fcn --- HL A ... call CP/M )
CODE FDOS
     BC POP,
                      get fon into C)
                      NOTE: doesn't work on FIG systems)
     HL POP,
                      first param to HL)
     DE POP.
                      second param to DE)
     BDOS CALL.
                      execute the fcn)
     HL PUSH,
                      put one returned arg on stk)
     A L LD,
                      move other to 16-bit register)
     O H LD,
                      clear top half)
     HL PUSH
                      and put it on stack)
     NEXT, END-CODE
```

place the Intel 3-byte absolute jump. The CP/M interface has been extended, but still uses BIOS calls and direct sector I/O.

If you have a Z80 system and a Z80 assembler, I would recommend buying the Z80 rather than the 8080 listing. However, I'm disappointed in the lack of customization. For example, the 16-bit subtract instruction wasn't used, CMOVE doesn't use LDIR, and many other common changes were neglected.

No Visible Support Software

As mentioned in an earlier column, Mike Perry and Henry Laxon distribute their public domain FORTH-83 software through this company. I purchased the 8080 CP/M-80 and the 8086 MS-DOS versions (\$25 each) and must say that I was impressed! The packaging was nonexistent, but the software is first-rate.

Each version comes on two unlabelled disks: one contains the .COM files and the other is a complete metacompiler with source code to create the .COM files. The systems are FORTH-83 standard, and include an assembler, simple multitasking, editors, a nice decompiler, and much more. You get no documentation and no support, but if you don't mind a few false starts, the price can't be beat.

The Laxon-Perry model has a good chance of being adopted by FIG as their long-awaited next standard system.

Z8000 FORTH

Volume 150 of the SIG/M CP/M User's Group (Box 97, Iselin NJ 08830) is Lou Odette's Z8000 FORTH, originally published in Dr. Dobb's Journal (Sept. 82 p 48). A few bugs have been fixed, minor changes were made to use a different assembler, and polled terminal I/O using the Z80 SIO were added. If you are in need of a Z8000 FORTH, read the original article first to see if Odette's nonstandard FORTH will serve your purpose. If so, the \$14 cost of the disk is a lot easier to part with than the time necessary to key in this long listing!

The only two other Z8000 FORTHs that I know of are the cross-compiled source from Inner Access, and UN-IFORTH hosted on the SBS single board computer. These two latter systems are both vendor-supported, and may be better choices for businesses.

Hardware News

The March issue of Byte ran an ad on page 510 for Cyber Robotics America. They are introducing the CYBER 310, a \$1200 robot arm controlled by FORTH software. I was wondering how long it would take for a commercial robotics firm to discover FORTH. I've wanted to put FORTH on the Heathkit Hero since its introduction, but just never had the time.

Proa Corp. has introduced (FD v.5 n.5) their Proatrol Single Board Computer using the Rockwell FORTH chip. This \$495 board is 5" by 8", and contains an RS232 serial port, 16K bytes of memory, 8 channels of A/D, and several other I/O ports. If someone ever gets hold of one of the development systems using the Rockwell chip, I would be interested in receiving timings on the benchmarks published in one of the earlier FORTHwords columns.

The Slicer

Intel's 8086 family is not really suited to FORTH because of its lack of stacks and proper addressing modes. However, the 80186 is an enhanced CPU that has a separate address calculation section and an optimized multiply/divide circuit, executing the basic 8086 instruction set at significantly increased speed at the same clock rate. The fast clock rates available (8MHz) and the execution enhancements make the 80186 a much better FORTH chip.

A pair of the 10 instructions added by the 80186 are of interest to multitasking/ multiuser FORTH systems. The "push all" and "pop all" instructions quickly save and restore all of the major registers on the hardware stack.

Otto Baude has been nice enough to loan me a Slicer for a few months to finish the development of a stand-alone UNIFORTH for this board. It's really a top-notch computer and I recommend it highly. The monitor and CP/M-86 implementation are excellent.

I think an interesting project for some enterprising engineer would be to package the Slicer and the Digital Research Computer video board into a portable computer. KayPro II's are cheap enough that you could almost buy the computer and replace the Z80 board.

BDOS Calls Through FORTH

There are over 30 functions that a user program can obtain from a CP/M-80 operating system. If you are programming in a conventional language such as FOR-TRAN or PASCAL, you can only use those functions that are included in your vendor's implementation.

One of the advantages of FORTH is its extensibility. If a particular BDOS function is missing from your system, it is easy to add it. Once compiled, any later FORTH word can use the new function. Try that in BASIC! However, each added function must be written in assembly language to be able to "call" CP/M and request service.

There are three basic approaches to providing BDOS support in a FORTH system: the vendor can implement a useful subset, and let the user code any missing functions that he needs (this approach is used by UNIFORTH); the vendor can implement each and every function; or the vendor can provide a general-purpose BDOS calling word so that you can implement new functions from high-level FORTH. The first method is straightforward, but requires short assembly language routines, which many FORTH programmers try to avoid. The second approach is impractical, as 30+ words would be defined and would take up unnecessary memory space.

By examining the CP/M documentation, you will find that CP/M passes arguments in DE and HL registers, and returns parameters in HL and A. Therefore, a general-purpose BDOS calling word might always have two arguments on the stack which would be popped into DE and HL before CP/M was called. Then HL and A would be left on the stack upon exit. One version of this word is given below, written in UN-IFORTH's Z80 assembler. (See Figure 1.)

The big problem with this word is that it always looks for two input parameters, and always returns two parameters. If the particular function you are coding has fewer arguments than this, you will have to include dummy arguments or drop returned arguments, wasting time and code.

A very interesting article by David Cornell in Dr. Dobb's Journal (Jan 1984 page 44) describes a utility for a fig-FORTH system that provides a convenient access to system functions from high-level FORTH. Written for MS-DOS interfacing, the utility is a set of macros that create a BDOS call from high-level FORTH. An example is the 'open-file' call, which would be written in his utility as shown:

> CALL: OPEN-FILE PASS(DX) 15 DOS-FCN RET(AL) ;

CALL: defines a machine-language (CODE) word, in this case called OPEN-FILE. The word "PASS(" will create pop instructions for each register mentioned. DOS-FCN implements the actual BDOS call. "RET(" creates push instructions for each register mentioned.

This novel approach provides assembly language interface with the operat-

ing system, yet the user needs to know absolutely nothing about assembly language, just listing the parameters mentioned in the system call description.

Cornell provides examples of just about all available MS-DOS calls. In all, it is highly recommended reading and should not be difficult to modify for a CP/M-80 interface.

Next Column

If you've been following the benchmark escapades in earlier columns, I will be giving you some more systems for comparison (at least including the 80186 and the Z8000). I promise to devote most of the column to menus and forms generation, a subject that was pushed aside because of the wealth of other subjects this time. Enjoy your Spring, but don't neglect your computer!



HARDWARE SPOOLER and INTERFACE CONVERTER Hardware spooler buffers your printing tasks — Download a 60K listing in 50 seconds!!

Converts to Centronics Interface without Losing Your Parallel Ports

- Input: Serial Port Big Board I or II (9600 Baud)
- Output: Centronics Parallel or Serial (110-9600 Baud)
- 60 K Buffer (up to 30 pages)
- Requires +5 Volts at 275 mA.
- Uses readily available parts (Z80 base system)
- LSPOOL Utility available for documents over 60 K
- 4 x 6 inch circuit board

Bare Board, Documentation, Listing for ROM \$29.95 ROM (2732A with program) ... 10.95 Disk with Source Code and LSPOOL Utility 10.95

> Shipped via Prepaid UPS — No COD or P.O. Box — Check or Money Order to:

L-Band Systems 1037 E. Lemon Ave. Monrovia, CA 91016 (818) 357-0566

Column by Tony Ozrelic

I have always been nuts about computer graphics. Accordingly, I have been reading and saving articles these many years.

Recently, I came across one from my college days which gives some cookbook algorithms for drawing lines and circles. I have rewritten them in C and present them to you now with a bit of explanation.

GRAPH.C

This simple program turns your display into a drawing board. With it, you can draw lines and circles. It could stand improvement, but then can't we all!

GRAPH begins by clearing the screen and using CP/M's BDOS call to look at the keyboard. This way I can move the cursor around without depositing characters on the screen. See Figure 1 for GRAPH's command set.

Figure 1 - GRAPH's Command Set

```
Com. Description
```

```
ъ
      draw concentric circles
      draw circle with set coordinates
с
1
      move cursor up
      cursor left
j
k
      cursor right
1
      draw line using specified coords
```

- m cursor down
- draw a star s
- quit and return to CP/M space store loc. of cursor on stack

Commands b and s show what the circle and line drawing algorithms can do when driven by the computer. To draw your own lines and circles, use the i,j,k,m keys to move the cursor to a point on the screen and hit the spacebar.

This pushes the current row, column coordinates onto a small stack (stk[]) and bumps the stack pointer (sp). Move to a new location and hit the spacebar again; this pushes a second set of coordinates onto the stack.

You are now ready to draw. Hit the l key and the coordinates will be popped off the stack and given to line(), which will then draw the line using asterisks (*) as the plot symbols. Hit the c key instead and you get a circle.

What could be simpler? Hitting any other key than the ones in the command set blanks the screen.

(continued on page 32)

6708 Melrose Los Angeles CA 90038

Figure 2 - Graphics Routines in C

/#

```
graph - simple graphics algorithms
                                                                     */
#include
                 "astdio.h"
#define YES
#define NO
                 ٥
#define CLEAR
                 26
                                   /# ctl - z to clear screen
                                                                     #/
#define ESC
                 27
                                   /*escape char for cursor addressing
                                                                              #/
#define PLTCHAR ***
                                   /#char used for plotting
                                                                     ¥/
                 24
                                  /#height of display
/#width of display
#define DEPTH
                                                                     */
#define WIDTH
                 80
                                                                     */
int row,col,sp,stk[100];
int negx, negy, swap;
main()
        ſ
        char c;
        int x0, y0, x1, y1;
        int dx,dy,r;
        /* clear to home and wait for command */
        putchar(CLEAR);
        row=col=sp=0;
        while(1) {
        /# look at keyboard and decode keystroke #/
                 switch(c=bdos(6,0xFF)) {
                         case '\0':
                                                   /* no key hit */
                                  continue;
                                                    /# draw concentric circles #/
                          case 'b':
                                  bullseye();
                                  break;
                                                    /# draw circle #/
                          case 'c':
                                  while(sp!=0) {
                                           x0=pop();
                                                            /#load coordinates #/
                                           y0=pop();
                                           x1=pop();
                                           y1=pop();
                                           /*get radius by simple approximation*/
                                           dx=abs(x1-x0);
                                           dy=abs(y1-y0);
                                           r=dx+dy/2:
                                           circle(x0,y0,r);
                                  break:
                          case 'i':
                                                    /# cursor up #/
                                  if(row>0) row-
                                  break:
                          case 'j':
                                                    /# left #/
                                  if(col>0) col--;
                                   break;
                          case 'k':
                                                    /# right #/
                                  if(col<WIDTH-1) col++;
                                  break:
                          case 'l':
                                                   /* draw line */
                                   while(sp!=0) {
                                                            /#load coordinates#/
                                           x0=pop();
                                           y0=pop();
                                           x1=pop();
                                           y1=pop();
                                           line(x0,y0,x1,y1);
                                  break:
                          case 'm':
                                                    /# cursor down #/
                                   if(row<DEPTH=1) row++;
                                   break;
```

```
case 's':
                                                   /* draw star */
                                  star();
                                  break;
                         case 'q':
                                  exit();
                         case ' ':
                                  push(row,col);
                                  break:
                         default:
                                  putchar(CLEAR):
                         }
                 moveto(row,col);
        }
                                                                    #/
        push - push current coordinates onto stack
push(y,x)
int y,x;
        stk[sp++]=y;
        stk[sp++]=x;
        pop - pop a coord off the stack. pop zero if stack empty
/*
                                                                             */
pop()
        £
        sp-
        if(sp>=0) return stk[sp];
        else {
                 sp=0:
                 return 0;
        1
/*
        star - draw a star on the screen
                                                                             #/
star()
        int x.y:
        for(x=0;x<WIDTH:x+=3) {</pre>
                 line(x,0,WIDTH-1-x,DEPTH-1);
                 ł
        for(y=0;y<DEPTH;y+=2) {</pre>
                line(0,y,WIDTH-1,DEPTH-1-y);
        }
/#
        bullseye - draw concentric circles at center of screen
                                                                             #/
bullseye()
        int r:
        for(r=1;r<12;r+=2) circle(WIDTH/2,DEPTH/2,r);</pre>
        }
/#
        line - draw a line from x0,y0 to x1,y1
                                                                            #/
line(x0,y0,x1,y1)
int x0,y0,x1,y1;
        int a.b.t:
        /# first, "normalize" line to positive, from/to coordinates #/
        a=x1-x0;
        b=y1-y0;
        negx=negy=swap=NO:
                                  /* make a positive */
        if(a<0) {
                 a#=-1;
                 negx=YES;
                                  /# set this so's we can change back later #/
        if(b<0) {
                                  /* same for b */
                 b#=-1;
                 negy=YES;
        if(a < b) {
                                  /* swap 'em to get from/to direction */
                 t=a:
                 a=b;
                 b=t:
                 swap=YES;
                                  /# set this for later #/
                                  /* now draw line from a to b using xy offset*/
        vector(a,b,x0,y0);
                                                       (Listing continued on page 32)
```

256K RAMDISK KIT NOW ONLY \$49.95!

CANNED LIGHTNING IS CHEAPER THAN EVER!

Make your spelling checker, assembler, or compiler programs run 35-300 percent faster by using dynaDisk!

dynaDisk is a 256k ram board that uses 5V at $\frac{1}{2}$ A and plugs into BB1's parallel interface (J5). It comes with auto-patching software that makes it look like an 8" SS SD disk drive to CP/M. It uses 4164 ram chips, regular TTL, and transfers data 8-10 times faster than a regular floppy. See Micro C #9 for a description and MC #11 for a review of dynaDisk.

FOR \$49.95 YOU GET:

8½" by 6¼" bare PC board Software on 8" SS SD floppy (SOURCE INCLUDED) Assembly & Operation Manual

BARE BOARD ONLY: \$39.95

820 OWNERS 820-II OWNERS

Your hardware will work with minor modifications. Software patches are included in the manual for 820-II owners.

DO-IT-YOURSELF CROSS ASSEMBLERS LANGUAGE TRANSLATORS STRUCTURED LANGUAGES ALL IN ONE \$39.95 PROGRAM!

• Use the XLT Macro Processor as a pre-processor to your favorite assembler and do the job right! To translate, a file of definitions is read by XLT and compared to the input text. A match causes the input text to be replaced with the definition's contents.

• XLT allows up to ten arguments in a definition, arguments containing spaces or tabs, incrementing/decrementing strings, a stack, and conditional text replacement.

• Includes definitions to translate Z80 to 8080 mnemonics and vice-versa, and definitions to implement CSAL, a C-structured assy. language, allowing code like $add a_i/hl$ to be written $a + = \pi h$.

• XLT users can pool their definitions via the XLT Users Group.

For CP/M 2.2 8" single density disk Z80 systems.

ALL ORDERS: Please add \$5.00 for postage and handling. All orders shipped first class. Satisfaction guaranteed. Please, no COD's, PO's, or plastic money.

QUANTITY PURCHASES: Buy five of one item at one time and get one free! Buy ten, get two free, etc.

Send check or money order to:



CA residents add sales tax CP/M is a trademark of Digital Research Prices and specifications subject to change without notice C.

Drawing Lines

Drawing a line begins with a call to draw(). This function takes the xy coordinates given and tweaks them into an 'ideal' set of coordinates for vector(), which then draws the line. plot() untweaks the ideal coordinates and plots the line dot by dot.

Line() makes an ideal line out of the coordinates given by turning (if necessary) the distances a and b into positive numbers and remembering which ones got turned by setting negx and negy true. If a is smaller than b, they are swapped and note of this is made in swap. These normalized distances are then given to vector().

Vector() plots a line starting at zero and ending at a. The variable s accumulates error; as we increment x, b is added to it until it becomes positive which is a signal that y needs to be bumped and s needs to be corrected.

The overall effect is that we plot points that come close to the real line, which we can't get to because the resolution of the display isn't fine enough. So we bounce around the real line, guided by s.

Plot() takes care of turning our line back into the the type of coordinates we started out with originally, plus adding limits on how far the plotting goes so we don't overshoot the screen or start making it scroll, which will happen if we plot a point in the lower righthand corner of the screen.

Drawing Circles

Circle() is much the same as line() in that we come close to the real line guided by an approximation in sector(). This function is invoked eight times for each circle, the idea being that we can plot an eighth of the circle given and then mirror-image the plot by changing signs and swapping coordinates.

Comments, Questions, and References

You will have to play with these algorithms to get a feel for what they do. Don't expect to understand them just by studying them. Those of you who do play will see some problems which need correcting, like scaling x and y axes so that the circles are less egg-shaped.

GRAPH could use some improvement too. There's no way to erase a line, or undo a stored coordinate. How about (continued on next page)

Graphics Routines continued

```
vector - draw vector
                                                                             #/
vector(a,b,x0,y0)
int a,b,x0,y0;
        int x,y,s;
                                  /# start off at zero #/
        x=y=0;
                                  /* as we sweep x, s tells us when to bump y^*/
        s= -a/2;
                                  /* it is updated when we've overstepped our */
                                  /# boundaries #/
        while(x<=a) {</pre>
                 plot(x,y,x0,y0);
                 s+=b;
                 X++;
                 if(s>0) {
                         s-=a;
                         y++;
                         1
                 }
        }
                                                                             */
/#
        circle - draw a circle on the screen
circle(x0.y0.r)
int x0,y0,r;
        1.
        all this does is go thru each octant of the circle and draw a sector.
        #/
        for(negx=0;negx<2;negx++) {</pre>
                 for(negy=0;negy<2;negy++) {</pre>
                         for(swap=0;swap<2;swap++) {</pre>
                                  sector(r,x0,y0);
                                  ł
                         }
                 )
        ł
/#
        sector - plot 1/8 th of circle
                                                                             #/
sector(r,x0,y0)
int r,x0,y0;
        int x,y,s;
        /4
        this is similar to vector() except that we are plotting
        part of a circle. S does the same job, that is, it accumulates
         error until it gets too big (positive), and we reduce x accordingly
        to keep the circumference of the circle within the radius, r
         ÷/
        x=r:
        y=0;
        s = -r:
        while(y<x) {
                 plot(x,y,x0,y0);
                 s+=2#y+1;
                 y++;
                 if(s>0) {
                          s-=2#x+2:
                             -;
                          }
                 }
         }
/#
         plot - move cursor to coords and put a char there
                                                                             */
plot(x,y,xs,ys)
 int x,y,xs,ys;
         int t;
         /* ignore out of bounds coordinates */
         if(x<0 || x>79 || y<0 || y>23) return;
         /* don't plot lower righthand corner - it makes the screen scroll */
         if(x==79 && y==23) return;
```

(Listing continued on next page)

15MB SYSTEM \$1999.00 PAPERS 4"x4"x11/2" TWICE.MOR UPGRADE YOUR II or 4 ONLY \$495 to a 4 or 8twice the storage on \$1 YR WARRANTY àèi ELOPPY DISK DRIVES STAND.MOR Solid Oak KAYPRO® Image: Constraint of the storage on standard of the storage of the stora					24 10 10 10 10 10 10 10 10 10 10			
*QUAD DENSITY 96TPI (794K) \$27900		WING 20"x14"	\$5				54567	890-=
		DESCRIPTION		QTY	COST	Total	WT	SHIP
BEE.MOR ENTERPRISES	1	STOR.MOR Delp	ni 15MB Hard Disk		\$1,999.00		12#	\$6
22-182nd Avenue East Sumner, WA 98390	2	TWICE.MOR DSI	DD 390K Floppy		22500		4	\$3
(206) 862-6310 MC VISA	3	TWICE.MOR Qua	ad Den. 96TPI 794K		27900		4	\$3
	4	VU.MOR COPY S	STAND		19 ⁹⁵		3	\$3
Terms: M/C, VISA, COD, Money Order Registered Check. Two week delay	5	CLIP.MOR LEXA	N PAGE HOLDER		4 ⁹⁵		11	NC with VU.MOR
for checks.		STAND.MOR SOL	ID OAK STAND		59 ⁹⁵		12	\$6
Shipping: UPS in Continental US P.P. insured Outside US, Prepaid.	7	PLAY.MOR GAM	EROM		24 ⁹⁵		1	\$2
Tax 7.8% for Washington Residents Kaypro is a registered Trademark of Kaypro Corp., WordStar is a trademark of MicroPro PacMan is a trademark of Atari, Ladder Yahoo Software, Chameleon by Seequa Campaq Computor Corp, Otrona Advanced Systems.		ACCENT.MOR D	acrit. Accent ROM		20000		1	\$2
		e	Tele #		SUE	B TOTAL		
		ess			Ta	x/Shipping		
			ST			Tota		
		Master Ch	VISA		_ Expiratior	Date		

(C'ing Clearly continued)

dotted lines? printouts? Can GRAPH be adapted to Microsphere's color graphics board? How about altering circle() so it generates conics? Have fun! Let us know what you've done and how you did it.

If GRAPH piques your interest, you might try looking at *Principles of Interactive Computer Graphics* by Newman and Sproull (McGraw-Hill). This is an excellent book since it ranges from simple line drawing stuff like GRAPH to three-dimensional color modeling of shaded surfaces.

The algorithms in line() and circle() were lifted from an article in *Computer Graphics and Image Processing* 5, pp. 280-288 (1976).

The spiffy approximation for the radius of a circle was lifted from Dave Cortesi's *Doctor Dobb's Clinic* column in DDJ, issue 55, May 1981.

One of these days I'm gonna do a graphics terminal that will support these functions. I did a prototype using an 8748 as the controller, but it was too slow and small to do the job right. Next pass, maybe an 8 Mhz 68000 with lotsa memory and a really high-resolution display. Now let's see, where did I put that mouse ...

Graphics Routines continued

```
/# now undo all the "normalizing" done to the coordinates #/
        if(swap) {
                t=x;
                x=y;
                y=t;
}
        if(negy) y#=-1;
        if(negx) x^{#}=-1;
        moveto(y+ys,x+xs);
        putchar(PLTCHAR);
/*
                                                                           */
        moveto - move cursor
moveto(row,col)
int row,col;
        /#
        this is standard stuff for the bigboard and the Kaypro. The
        sequence is ESC, =, row address+32, column address plus 32.
        */
        printf("%c=%c%c",ESC,row+32,co1+32);
/*
                                                                           */
        abs - return absolute value of a
abs(a)
int a;
        return (a<0) ? -a : a;
                                                                       END
```

Xerox 820 and Up

By Jay Jaeckel

While at a private show for a major midwestern university, I talked with the local XEROX demonstration person. During the conversation, this person said that XEROX had quit manufacturing the entire 16/8 820-II family of products in favor of a newer machine coming out of XEROX R&D.

Is this rumor or fact? Only time will tell, but I sure hope they ship my upgrade(s) before they do whatever they decide to do.

Many readers may have noticed the proliferation of inexpensive eight inch, double sided disk drives that seem to be advertised everywhere. This can be a major benefit for those who own a Xerox 820-II single sided, eight inch system.

The double sided disk drive upgrade for your 820-II is a snap. Doing the same thing on the 820 is just a little more difficult because a BIOS change is required for the operating system to acknowledge

Figure 3 - Xerox 820 Disk Parameter Code

;

SECTAB: DEFB

DPBLK

DPHTA

FROM XEROX 820 CBIOS.MAC

1 IN 6 INTERLEAVE FACTOR

1,7,13,19

SECTOR TRANSLATE TABLE FOR STANDARD

DSKTY8

that the new double sided drives are "different."

Ingredients

1 or 2 Double-Sided, Eight-Inch Shugart 850 or 851 Disk Drives

2 AMP 1-480700 (connectors for AC power to drive)

1 AMP extraction tool (a small screwdriver can be used with care)

1 pair of needle-nose pliers

1 OHM meter or continuity tester

1 BIOS patch (820 only)

Procedure

;8 INCH DISK

The first thing you should do is configure the circuit boards on the disk drives. There are two types of configuration jumpers on the 850 and 851. They both have a dip shunt (fancy language for dual-inline-package jumpers), which looks like an IC with metal straps across the top. 418 Kings Way Mundelein, Il 60060 (312) 949-7500

Some of the metal straps may be "punched" or cut. You'll know when you have found the right part because the dip shunt package will have identification letters or abbreviations for the various functions each of the metal straps controls. Both the 850 and the 851 dip shunts should be configured the same according to the 820 and 820-II service manual. See Figure 1.

You're almost done with the drive. Now all you have to do is pull all of the little black two header pin shunts from the board and replace the following as shown in Figure 2.

Replace the drives in the enclosure. Now on to the cable modification. The first cable to modify is the AC power to the drives.

Take the old plastic connector off by using the AMP tool PN#305183 to slide over the connectors inside and gently remove them. This tool is just a metal tube that bends the little ears on the connector inward so you can slide the metal connector out of its plastic shell.

I have had a fair amount of success bending the ears of the metal connectors

Figure 1 - Shugart 850, 851 Shunt Configuration

	DEFB	25,5,11,17 23,3,9,15 21,2,8,14 20,26,6,12 18,24,4,10 16,22 RAMETER BLOCK FOR	R STANDARD 8" FLOPPY	Z(In use from drive select)shorted*HL(Stepper power from Head Load)openA(Radial Head Load)shortedB(Radial Head Load)shortedX(Radial Head Load)openI(Index Output)shortedR(Option for ready Output)shortedS(Sector Output)shorted				
D D	DEFW DEFB DEFB DEFB	26 3 7 0	;SECTORS PER TRACK ;BLOCK SHIFT CONST. ;BLOCK MASK CONST. ;EXTENT MASK CONST.	(Yes, shorted means connected with the two points touching.)				
	DEFW	242	;MAX BLOCK#	Figure 2 - Shugart 850, 851 Jumpers				
	DEFW	63	;MAX DIRECTORY ENTRY#					
	DEFB	11000000B	;ALLOCATION MASK MSB	DC (disk change option)				
	DEFB	0000000B	;' LSB	2S (2 sided output status)				
	DEFW	16	CHECK SIZE	850 (there are three pins here plug between the				
	DEFW	2	;RESERVED TRACKS	two 850 for sector option dis-able)				
				IW (three pins again; plug between IW for				
	DTOT DA	DAMETED UPADEDS I	FOR A 2 DISK SYSTEM	inhibit write when disk-write protected)				
		T TWO REMOVED FOR		C (Alternate head input load)				
1	The last two alloves for Street.			DS (Stepper power from drive select)				
AB:	DEFW	SECTAB.0000H	DPH FOR UNIT O	RS (XEROX says plug it)				
	DEFW	0000H.0000H	,	S2 (four pins here for S1, S2, S3 the center				
	DEFW	DIRBUF, DPBLK		being common - S2 standard side select)				
	DEFW	CHKO, ALLO		E (XEROX says plug it)				
	DEFW	SECTAB,0000H	;DPH FOR UNIT 1	TT (VEDAV save plug 14)				
	DEFW	0000Н,0000Н		IT (XEROX says plug it)				
	DEFW	DIRBUF, DPBLK		TS (true separation)				
	DEFW	CHK1,ALL1		FM (851 only)				
	ENDIF		END OF 8 INCH SECTION	AF (850 only)				

MFM (851 only)

:

inward with a tiny screwdriver, sliding the metal connectors out of the shell, and then bending the ears back to their proper positions. Install the metal connectors into the new shells and plug the cables into the drive.

Cable number two is the signal cable (the big one that plugs into the Display/ Processor from the disk drive cabinet). Start by removing the large metal AMP shell from the DB-37 connector. Then, with your needle-nose pliers, push any two of the pins (I used #27 & #28) on the bottom row of the DB-37 (they are all ground lines), and put them in holes #7 and #8.

These pins are fragile (be careful), and they push out hard but push in and lock very easy. Now using the continuity tester on pin 7 find the small metal connector at the other end (the large edge card connector) and using a tiny screwdriver to release the lug, pull it out and move it to the other side to position "H".

If you look closely, you'll see that one side of the connector is numbered and the other side is lettered. Now do the same thing for pin #8 on the DB-37 and move that respective connector to position "K". All done.

Plug in the drives, enjoy, and be grateful that Xerox provided you with an initialization program that already allows you to do double sided disks. To test your efforts, try to initialize a double sided disk. If it works, you're home free. If you're especially suspicious, PIP over enough files to file your gloriously 980K disk.

If you have the 820-II, you are done. The operating system will automatically recognize your double-sided disks when you use them.

If you have an 820, all that remains is the BIOS patch for your double sided disk parameters. Everyone tells me this is easy. However, my knowledge of assembler isn't the greatest, but I'll include the general area in the CBIOS here for reference. Perhaps some assembler expert out there can be of further help to us all. Drop me a note.



CABINET FOR THE W-I-D-EDISK DRIVES (SA800-2)

Heavy CAST ALUMINUM Cabinet----\$50.00


Cabinet, Pwr Supply and Wiring for 2 drives----\$150.00

Quantities Limited First Come, First Served. Cabinets are USED and sold AS IS. Pwr supplies have been tested.

ADD \$5 Shipp/Hand. Charge Cards ADD 5%

CASCADE ELECTRONICS ROUTE 1 BOX 8 RANDOLPH, MN. 55065 507-645-7997

MN. add 6% sales tax



LOW COST DISK CONTROLLER NOW FOR BB&BBII

- LESS THAN \$10 COMPLETE -

SAVE WEAR AND TEAR ON YOUR DISK DRIVES AND FLOPPIES WITH THE MODEL 3801 ALL SOLID STATE RELAY. SMALL ENOUGH TO FIT EASILY INSIDE YOUR DISK DRIVE, THE 3801 CAN BE INSTALLED IN MINUTES. YOUR BIG BOARD WILL THEN TURN YOUR DRIVES ON AND OFF AUTOMATICALLY AS THEY ARE NEEDED.

- FEATURES -

- * SMALL SIZE 1.75 X 1.40 X
- 0.35 * FAST INSTALLATION DIAGRAM
- INCLUDED ZERO CROSSING ELIMINATES
- ALL SWITCHING NOISE TRIAC OUTPUT NO MECHANICAL PARTS
- DVDT FILTER INCLUDED LOW COST ONLY \$8.80 EACH 1 YEAR WARRANTY
- 30 DAY MONEY BACK GUARANTEE

PHENI COMPANY OF CALIFORNIA


1619 SOUTH MINNIE STREET SANTA ANA, CALIFORNIA 92707

(714) 547-4316

CALIF. RES. ADD 6% SALES TAX ADD \$1.00 POSTAGE & HANDLING PLEASE SPECIFY BB OR BB II .

	BIG BOARD I USERS
SYST	EM MODIFIER PROGRAM \$29.95
Manu	al only \$3
0	Allows easier system modifications by not
	involving the system tracks
0	Provides screen dumps and
	time display on demand
	through escape commands
0	Automatically runs any
0	program on a cold boot Includes both serial and
0	parelel I/O drivers
0	
Ö	Is all in a single program
•	that loads into high memory
	and extends the PFM monitor
0	Includes menu driven
	configuration program
SWIT	CHING POWER SUPPLY \$50
0	5 volts at 20 amps
ō	
0	Call for avalability
	C & D ENTERPRISES 75 North Street
	/5 North Street Saco, Maine, 04072
	(207)-282-4401
	10077-202-4402
	Add \$2 for shipping
	V/SA' WasterCard

SWP's CO-POWER-88 makes Z80, CP/M microcomputers IBM-PC compatible!



ATR8000: SWP's \$499.95 CP/M Computer

SWP's ATR8000 is a 64k RAM, Z80A, 4 MHz computer that includes double density CP/M 2.2. The ATR-8000 runs up to four disk drives that are any mixture of size (5¹/₄" and 8"), type (single-sided and doublesided), and density (single, double and quad). The ATR8000 has an RS-232 port for a modem or serial printer and includes software for both. There's also a parallel port with a parallel printer driver. The ATR8000 inferfaces to an RS-232 terminal or to an ATARI home computer. Software includes a program that allows the ATR8000 to use CP/M disks from other comptuers. The ATR8000 can be upgraded to also run CP/M-86 and MSDOS by adding CO-POWER-88.

Bigboard Dual Density

Hardware

- A daughter board that plugs into the 1771 socket. With this board the system employs automatic density select.
- Instructions tell how to run 51/4" drives. A 50-34 pin disk drive adapter board is included with 51/4" disk orders.

Price: \$149.95

Software V#061983

- One 8" version includes the code to make a 60k double density CP/M for:
 8" SS 2.5 MHz
 8" DS 2.5 MHz
 8" DS 4 MHz
 51/4" SS 2.5 MHz
- Printer drivers are built-in, selectable in the IOBYTE.
- Easy to change port parameters.

We've just released a new version!

- 8" SSDD disk storage is 674k; DS is twice as much! 51/4" is 183k.
- Includes DDINIT for SD and DD initializing and DDSYSGEN for DD sysgening.
- Special features have been added including a deluxe pause, screen print and clock.
- Source code is available for \$25 after you sign a disclosure agreement.

For orders: We accept MasterCard, Visa, money orders or checks. Shipping charges and applicable taxes will be added. Call or write for delivery time. Trademarks: CO-POWER-88, ATR8000, SWP, Inc. Z80, Zilog, CP/M, CP/M-86, Digital Research, Inc. IBM-PC, IBM. MSDOS, Microsoft. Prices and specifications subject to change without notice.



2500 E. Randol Mill Rd – 125 Arlington, Texas 76011 817/469-1181

(We used to be Software Publishers, Inc.)

BB I Dual Density: New Version

Jan Korrubel

In the October issue of Micro C my attention was drawn to the advertisement of SWP microcomputer products, offering their new version of the Big Board Dual Density.

The price, \$150, was the same as for the previous version which already had had a good write-up in Micro C of June, 1982.

I ordered the hardware and software early in December, 1983, and to my surprise, the parcel was delivered in the second week of January. Previous orders I had placed in the U.S.A. (at different firms), usually took much longer for delivery.

Damage

The big disappointment was that the parcel was extensively damaged, sort of folded double, and pins of the enclosed daughter board had pierced the 8 inch disk containing the necessary software.

In trying to straighten the folded pins, two pins broke off!

The excellent 27 page instruction manual accompanying the daughter board gave me the idea that it was possible to stack the board with a 40 pin socket, in order to raise it high enough above the Big-Board to clear the crystal and condensors.

I now used this marvelous idea to solder bridges between the broken pins and the corresponding pins of the stacked socket.

One obstacle had been overcome, and on reading the damaged disk, it became clear that all damage had occurred in the unused part near the center. All files could be transferred to a back-up disk.

Removing the floppy disk controller I.C. and installing the daughter board in its place was no problem at all and my Big Board booted normally as always on single density. By following the clear and precise instructions of the manual I had in no time a double density disk that contained various enhancements to the BIOS.

New BIOS

First, it has a printer driver that I can change from serial (either port) to parallel and can modify as well. This was something I had wanted for a long time. Secondly, four special function keys "ORYX" Welbeloond Rd. Constantia 7800 South Africa.

appeared on my keyboard (apart from a host of others): the screen dump to my printer, the clock toggle, displaying the time of day in the top righthand corner of the screen, the abort key that displays the value of the program counter in the lower righthand corner, and the scroll key that automatically scrolls through 24 linefeeds when in TYPE mode and then generates a pause.

Six escape sequences, identical to the newer terminals, not only make your Wordstar and Supercalc react faster to your commands, but allow you to set bit 7 of the screen memory. Now it becomes possible to add the hardware to do video highlighting, like reverse video or half intensity.

My 8 inch flippy disks, formatted with double density, have more than one Mbyte of user storage and are almost impossible to fill. That is, until I get used to it having so much space.

There are problems, however. The new BIOS generates an audible key-click which I find very annoying. Unfortunately, there is no mention of a key-click toggle in the manual.

The Set Clock program that I obtained from users disk one will not set the clock properly. The program translates the time to a hexadecimal clock display which I find very difficult to read. Hopefully, someone will publish an update to SETCLK.COM so my clock will tell normal time again.

Conclusion

Overall, this is an excellent product which does all (and more) that is promised in the advertisement.

. I only wish for better packaging as my nerves fray easily at the sight of folded and pierced disks. Broken pins I do know how to repair now.

This method of stacking the board on a socket may work equally well for that expensive I.C. with the broken pin(s). If the remaining material is enough to solder to and you are quick in soldering, it is worth a try.

Do not forget to glue the socket to the I.C. as otherwise the two will part next time you extract the I.C. from its socket on the printed circuit board.

Integrated BIOS for BB II

This BIOS adds special features for floppy and winchester users.

Floppies

Read and write almost any 8" and/or 5" disk format. 20 formats included (KayPro, Osborne, IBM . . .)

Use any type of 5" and/or 8" drive (SS, DS, 40 tracks, 77 tracks, 80 tracks).

Boot from any format of disk.

Winchester

Winchester formatter with check for bad sectors automatically assigns alternate track(s) for track(s) with bad sectors.

Winchester sysgen (can make the winchester drive A:)

Also includes codes for New BB II monitor

(with all known bugs fixed).

Note: You must already be running the Bakker's 8" and 5" interface (available from Micro C) before installing the integrated BIOS. Price **\$129.95**

SASI Interface for BB I and Xerox 820 I

Includes Card, BIOS, Formatter, and Sysgen Price **\$99.95**

ANDY BAKKERS De Gervelink 12 7591 DT Denekamp The Netherlands

A Very Calculating BB II

By Per Wallander

In order to increase the mathematical throughput of my BB II, I have added an arithmetic processing unit (APU). Is it necessary to increase the speed of the BB II? Yes, if you want to calculate antenna radiation patterns with millions of trigonometric operations in any kind of reasonable time.

Speedup

I have tested a simple loop of sine calculations, first on the ABC 80, a Swedish microcomputer with a Z-80 running 4 MHz with an 8K BASIC. Every turn in the loop takes 40 ms. On the BBII with MBASIC, every loop takes 15 ms. With Pascal MT+ every loop takes 15 ms. With Pascal MT+ and 8231 APU, every loop takes 2.4 ms., an increase in speed of about 6 times.

Hardware Details

The APU is addressed as an I/O device and I started using the two parallel ports at addresses DA and DB. The system Ljungstigen 9 S-144 00 RONNINGE, SWEDEN

didn't work, however, until I removed U99 and U104 from their sockets. They were in parallel with the APU and kept the data lines at zero.

I then moved the APU to another address to make the parallel ports free for other uses. On the BB II the decoding of the address bus in I/O operations is incomplete. As you can see on the circuit diagram, U27 does not read BA5. Therefore, I could address the APU both at addresses DH-DB and at FA-FB. I compiled the test program for these new addresses and it worked fine.

To make the BB II I/O decoding read DA5, I bent out pin 4 on U27 and connected it to BA5 (19) on the STD bus. With U99 and U104 back in their sockets, the parallel ports are at DA and DB, and the APU is at FA and FB.

I have made two small circuit boards. The first holds the 8231A and 7432 and is located on the modification area on the BB II board (close to U104). The second board is bolted to a connector which fits into the STD bus. This second board carries the 74154, 7400 and 7409.

The data bus, IOD0-7, is taken from U104. I have removed U104, inserted a pin plug in socket U104, and made the connections to the pin plug to avoid soldering on the BB II board. On top of the pin plug, I have added a socket for the original 74LS373 (piggy back).

The RD and WR signals are taken from U97 (soldered on the board). Together with BIORQ from the STD bus (combined in the 7432), they make the RD and WR signals for 8231A.

BA0 and CLOCK are connected directly from the STD bus to 82312A. RESET is inverted in the 7400. The address bus is decoded by the 74154, the inversion of BA1 in the 7400, and the combination of two address lines in 7409. All this is necessary since there are not enough inputs in the 74154.

The PAUSE output from the 8231A is connected to WAITRQ on the STD bus. I have used the 7409 as a buffer, though it is not necessary.

The Intel 8231A I used is a 4 MHz version of AMD9511. It should be possible to use a 3 MHz version if you add a separate clock or divide the BB II clock by two.

There are languages other than Pascal MT+ that can use this APU directly. In the documentation from AMD, you will find assembler routines if you prefer to roll your own.





Figure 1 -Big Board II APU Circuit




Micro Cornucopia, Number 17, April 1984

NEW LOWER PRICES!

NOW IN "UNKIT"* FORM TOO!

"BIG BOARD II" 4 MHz Z80-A SINGLE BOARD COMPUTER WITH "SASI" HARD-DISK INTERFACE



\$795 ASSEMBLED & TESTED \$545 "UNKIT"* \$245 PC BOARD WITH 16 PARTS

Jim Ferguson, the designer of the "Big Board" distributed by Digital Research Computers, has produced a stunning new computer that Cal-Tex Computers has been shipping for a year. Called "Big Board II", it has the following features:

■ 4 MHz Z80-A CPU and Peripheral Chips

The new Ferguson computer runs at 4 MHz. Its Monitor code is lean, uses Mode 2 interrupts, and makes good use of the Z80-A DMA chip.

64K Dynamic RAM + 4K Static CRT RAM + 24K E(E)PROM or Static RAM

"Big Board II" has three memory banks. The first memory bank has eight 4164 DRAMs that provide 60K of user space and 4K of monitor space. The second memory bank has two 2Kx8 SRAMs for the memory-mapped CRT display and space for six 2732As, 2Kx8 static RAMs, or pin-compatible EEPROMS. The third memory bank is for RAM or ROM added to the board via the STD bus. Whether bought as a bare board, an "unkit", or assembled and tested, it comes with a 2732 EPROM containing Russell Smith's superb Monitor.

Multiple-Density Controller for SS/DS Floppy Disks

The new Cal-Tex single-board computer has a multiple-density disk controller. It can use 1793 or 8877 controller chips since it generates the side signal with TTL parts. The board has two connectors for disk signals, one with 34 pins for 5.25" drives, the other with 50 pins for 8" drives.

Vastly Improved CRT Display

The new Ferguson SBC uses a 6845 CRT controller and SMC 8002 video attributes controller to produce a display rivaling the display of quality terminals. There are three display modes: Character, block-graphics, and line-graphics. The board emulates an ADM-31 with 24 lines of 80 characters formed by a 7x9 dot matrix.

STD Bus

The new Ferguson computer has an STD Bus port for easy system expansion.

The new Ferguson computer has a Z80-A DMA chip that will allow byte-wise data transfers at 500 KBytes per second and bit-serial transfers via the Z80-A SIO at 880 Kbits per second with minimal processer overhead. When a hard-disc subsystem is added, the DMA chip makes impressive disk performance possible.

SIZE: 8.75" x 15.5" POWER: +5V @ 3A, +-12V @ 0.1A

"SASI" Interface for Winchester Disks

Our "Big Board II" implements the Host portion of the "Shugart Associates Systems Interface." Adding a Winchester disk drive is no harder than attaching a (loppy-disk drive. A user simply 1) runs a fifty-conductor ribbon cable from a header on the board to a Xebec controller that costs only \$295 and implements the controller portion of the SASI interface, 2) cables the controller to a Seagate Technology ST-506 hard disk or one compatible with it, and 3) provides power for the controller-card and drive. Since our CBIOS contains code for communicating with hard-disks, that's all a user has to do to add a Winchester to a system!

Two Synchronous/Asynchronous Serial Ports

With a Z80-A SIO/O and a Z80-A CTC as a baud-rate generator, the new Ferguson computer has two full RS232-C ports. It autobauds on both.

■ A Parallel Keyboard Port + Four Other Parallel Ports for User I/O

The new Cal-Tex single-board computer has one parallel port for an ASCII keyboard and four others for user-defined I/O.

Two Z80-A CTCs = Eight Programmable Counters/Timers

The new Ferguson computer has two Z80-A CTCs. One is used to clock data into and out of the Z80-A S10/O, while the other is for systems and applications use.

PROM Programming Circuitry

The new Cal-Tex SBC has circuitry for programming 2716s, 2732(A)s, or pincombatible EEPROMs.

■ CP/M 2.2**

CP/M with Russell Smith's CBIOS for the new Cal-Tex computer is available for \$150. The CBIOS is available separately for \$25.

* The "unkit" is a fully-socketed, wave-soldered "Big Board II". It requires NO soldering. All an "unkit" purchaser must do is carefully insert the prime ICs we supply in the proper sockets and systematically proceed to bring up and test the board.

**CP M is a registered trademark of Digital Research

Terms: Orders paid for with a cashier's check or bank card will be shipped within three working days. Orders paid for with a personal check will be shipped within three weeks. Add \$5 for packing & shipping in North America.

CAL-TEX COMPUTERS, INC. 780 E. TRIMBLE ROAD #504 • SAN JOSE. CA 95131 • (408) 942-1424

Morse Code Interface For The Kaypro

By James E. Shaffer

445 Los Robles #307 Pasadena CA 91101

It doesn't take an expensive or complicated interface to make the Kaypro II receive and transmit international morse code. Plus, a license isn't required to receive Amateur Radio Morse Code, only to transmit it. So, here is a way for the non-amateur radio computer hacker to have some fun watching the dit-dah-dits magically appear on the Kaypro screen in English.

The Cheap and Dirty CW Interface

The following cheap and dirty interface and software will also enable experienced Hams to send and receive CW (continuous wave) at incredible speeds.

Cheap Hardware

The hardware has only 13 components and receives its power from the Kaypro. All connections are to the parallel printer port.

The LM567 tone detector converts audio from the speaker jack of any shortwave receiver to digital pulses. These CW pulses are sent to Kaypro via pin 11.

The Kaypro outputs CW on pin 9 of the printer port to a 4N33 optoisolator which will key most modern transceivers.

I used pin 30 for ground, and pin 18 for +5 volts. I understand that earlier models of Kaypro II did not have +5 volts on pin 18. So if you have an old II, you may have to go inside to get power for the cheap and dirty.

Dirty Software

The software is MBASIC so everyone can understand and modify it to suit their needs. It has lots of GOTO's, so I guess the PASCAL folks will call it dirty.


The program starts out in the receive mode. The cursor keys are used to control the program.

Up arrow Down arrow		 smit N ive Mo		
Left arrow Right arrow				

The software is adjusted to run with a 4 MHz clock. If you have a 2.5 MHz version change the S+4's to S in lines 230, 240 and 250.

Speak English, please!

To calibrate the cheap and dirty interface, tune in a clear CW signal, then adjust R3 until you see the dit-dah-dits converted to English on the screen. Sometimes Amateur Radio operators use so many abbreviations it's hard to recognize that the message is English. Have fun with the cheap and dirty. I have been using it for over a year now without any problems. It performs like an expensive and complicated interface.



0,1,1,1,3,0,0,1,3,3,0,0,0,3,1,1,3,0,0,3,1,3,3,0,0,3,3,1,1,0,0



innininininin 🖓 📖 🕅

POWER: +5V 1.5A, ±12V 0.1A

PCB SIZE: 10" x 5.5"

FLOPPY DISK CONTROLLER: Auto density check 8" DDDS, 8" SDSS, 5" KayPro format, 8" compatible 5" drive (1.2 MB double track quad density)

FLOPPY DISK DRIVE, KEYBOARD, CRT, POWER SUPPLY ARE NOT INCLUDED

 \$699
 Assembled & Tested + CP/M PLUS (RMAC, MAC, ED, SID with manuals)
 Assembled & Tested + CP/M PLUS + 8" compatible Disk Drive (1.2mb double track quad density)
 *RAM DISK BOARD, NEC7220 Graphic Board with GSX, 68000 + CP/M-68K Board will be available soon!!
 *CP/M PLUS, GSX, RMAC, MAC, ED and SID are trademarks of Digital Research For more information write or call: **SOUTHERN PACIFIC LIMITED** 1-3-18 Tsurumi-chuo, Tsurumi, Yokohama, Japan 230 Phone: (405) 501-8842 Telex: 3822320 SPACIF J

Exclusive United States Distributor: **ARTISOFT, INC.** 2450 East Speedway #4, Tucson, AZ 85719 Phone: (602) 327-4305 Orders: (800) 821-6010

Micro Cornucopia

KayPro Disk K1 Modem software

This disk is absolutely priceless if you will be using a modem to communicate with bulletin boards, other micros or mainframes. MODEMPAT. COM: Menu selection of baud rate, bits/character, stop bits, & parity for serial

MODEM7.COM: Very popular MODEM 7

with anything! KMDM795.COM: Super-version of MODEM7 set up for KayPro

TERM.MAC: Commented disassembly of the

TERM program you get with your KayPro so you can configure it for any interface. SQ/USQ.COM: Programs to squeeze and unsqueeze files for faster transfer.

KayPro Disk K2 Utilities

Really oodles of spiffy little (and big) programs to help you get full use of your KayPro. ZESOURCE.COM: A true Zilog format disassembler for 8080 and Z80 object(.COM)

files. Now you can turn .COM files into . MAC files

UNERA.COM: Simply enter "UNERA" followed by the name of the file you just erased and presto, the erased file is back! A lifesaver. FINDBD54.COM: Checks an entire disk, reports bad sectors, and then creates a special file containing those sectors. You save a bundle on disk

disks. CAT2: This a group of programs which create and maintain a single directory of all the programs you have on all your disks. Even keeps track of which programs are backed up and which aren't. UNSPOOLCOM: Use your KayPro II and print files at the same time. Doesn't slow down evertem response!

system response! DUMPX, DU-77, COMPARE, SUPERSUB, FORMFEED, DIR-DUMP, . . . and all have documentation on disk.

KayPro Disk K3

Games PACMAN.COM: Despite the KayPro's lack of graphics, this one looks and plays amazingly like the real thing! Keep it hidden. ZCHESS.COM: Chess with a 1-6 level look

ahead

OTHELLO.COM: You learn it in minutes, master it in years. BIO.COM: Generates custom graphic biorhythm.

MM.COM: Master Mind. WUMPUS.COM: Classic wumpus hunting.

KayPro Disk K4

Adventure This disk contains one 191K game, Adventure. ADV.COM: This is the latest, greatest, most cussed adventure ever devised by half-mortals. This is the 550-point version so the cave is greatly expanded and the creatures are much smarter.

KayPro Disk K5 MX-80 Graphics A complete MX-80 graphics package including example files.

KayPro Disk K6

Word Processing Utilities A powerful line oriented text editor that looks

like Unix's EX, plus a scad of text utilities written in C which handles pretty printing, shortening a file, multiple space output, add tabs, remove trailing whitespace, and more. Also includes **ROFF.COM** a very neat text formatter.

KayPro Disk K7

Small C Version 2 Compiler This is a greatly extended version of Ron Cain's Small C compiler. Version 2 has more expressions and larger library, true subset of Unix C. Disk contains compiler, documentation, and library — everything you need.

KayPro Disk K8 Small C Version 2 Source This disk contains the source (written in Small C) of the Small C version 2 compiler. Get K8 if you want to try extending the compiler. (You must have K7.)

KAYPRO USERS DISKS

for KayPro II, 4 and 10

\$1200 each

The following are full disks of software assembled for the KayPro. Each program has a .DOC (documentation) file and many come with source.

KayPro Disk K9 2CPR CPR: The big news on this disk is the self-installing version ZCPR available only from Micro C. Once you have ZCPR in your CP/M, you'll never go back to straight CP/M! For instance, ZCPR searches drive A for any program not found on drive B, so, even an empty disk in drive B appears to contain every program on A. It's great for text editors, compilers, etc. Works on KayPro II and 4. **PASWORD:** Letts you encrupt and decrupt your

PASWORD: Lets you encrypt and decrypt your

Precious files. Includes source. EX14: a super replacement for SUBMIT. Plus many more: TREK, FIX, FIND, SNOOPY ALIENS and DIF2.

KayPro Disk K10

Assemblers We've received a lot of requests for a Z80 assembler. So Dana put in some long hours getting the Crowe Z80 assembler to run on the Kurde down and a 200 km and a 20 KayPro (and every other Z80 machine). CROWECPM: This is a first class Z80 assembler. We use this assembler daily (and we included

Lis source). Takes standard Zilog mnemonics. LASM: This is a more powerful version of the ASM assembler you received with the KayPro.

This will link multiple programs together at sembly time

PRINTPRN: This program makes it easy to print the listing files generated by the Crowe assembler.

KayPro Disk K11

KayPro Disk K11 Library & Checkbook Programs CHECKS: This has been a very popular group of programs. Categorizes checks so you can keep track which are tax deductible and which get charged to which projects. Includes source and excellent example check files. Very powerful. LIBR: This is a complete set of library routines which let you group files into a single file called a library. Then CP/M sees them as a single program, but with the library routines. you can list them but with the library routines, you can list them out separately, run them separately, or divide them up again. Almost like a unix environment. **DISPLAY, VLIST, PGLST:** Additional screen and print utilities.

KayPro Disk K12

FORTH Yep, this is FORTH, one of the most unique, most extendable languages known, and for a paltry \$12.00. This disk contains not just one paltry \$12.00. This disk contains not just one FORTH, but two, along with an editor, decom-piler and 8080 assembler! The editor even uses the cursor control keys.

FORTH: This is true fig-FORTH.

KFORTH: A very nicely extended version of fig-FORTH. **PLUS**, all the rest of the FORTH goodies. (Forth Heaven!)

KayPro Disk K13 Source of fig-FORTH All this disk contains is the 40K ASM source of fig-FORTH with the hooks in place for the KayPro. This disk is for FORTH hackers who just have faults, too.) The source of FORTH is here because there isn't room on K12. This is the only disk that isn't stuffed.

KayPro Disk K14

Smartmodem Programs This is the disk for you if you have a Smartmodem compatible modem.

SMODEMK: Smartmodem program set up for

SMODEM: Sinartinodem program set up for the KayPro (and source).
 XMODEM: Lets you remotely control your KayPro from a distant computer.
 KAYTERM: This is the information you need to run or write modem software on the KayPro.



KayPro Disk K15 Hard Disk Utilities This disk is for the KayPro 10 or any KayPro with a Winchester drive. With these routines you can not only backup files (with printed directories of the backup disks), you can also break up large files. The backed-up files are not encoded (as they are with KayPro's backup routine) so you can access them on any system. access them on any system.

KayPro Disk K16

Pascal Compiler This is a real Pascal compiler. It supports only a subset of the language (no records, pointers, booleans, reals or complex) but it generates a real .COM file. Everything is on this disk: the compiler, its source, example programs and documentation.

KayPro Disk K17

Z80 Tools This is for those of you who are into Z80 assembly

XLATE.COM: A very good 8080 to Z80 translation routine

DASM.COM: An easier to use version of ZZSOURCE (the Z80 disassembler). This full disk includes source and documentation for both routines.

KayPro Disk K18 System Diagnostics

Just as we finished editing the routines on this disk, we received a copy of KayPro's diagnostic disk. The memory test, drive exercise, and drive alignment routines on this disk are more powerful than KayPro's versions. (Plus, it's only \$12!) Setup for KayPro II and 4.

KayPro Disk K19

Prowriter Graphics This is a complete Prowriter graphics package written by the same Micro C subscriber who wrote the MX-80 graphics package. Plot points, lines, circles, boxes, and more. Examples, documentation, and more.

Kaypro Disk K20

NEW! **Color Graphics Routines** PACMAN.COM: This is a deluxe version of pacman for MicroSphere's color graphics board. **PIE.COM:** Pie chart generator.

SKETCH.COM: An easy way to sketch color graphic designs. You can even use a joystick with this software (see Micro C issue #15 for joystick interface).

Kaypro Disk K21

NEW! SBASIC Routines & Screen Dump SBASIC: Finally a disk of SBASIC software. SBASIC: Finally a disk of SBASIC software. There are some good examples of structured programming on this disk (including one program written both ways so you can see the difference). SCREEN DUMP: This is a screen dump for the Kaypro II and older 4 (any system without graphics). You can buy a similar package else-where for \$60.

Kaypro Disk K22 Fancy ZCPR

NEW! This ZCPR lets you pass any control charac-ters to your system (they aren't trapped like the old version). Also, this version comes with installation routines for every Kaypro now on the market (including the 4-84 and the 10).

We have something special for your Kaypro!

ROMs from Micro Cornucopia

There are two ROMs in each Kaypro, a monitor ROM and a character ROM. The Monitor ROM supplies information for the Z80 processor on such things as how to get information from the disk drives, and which character to use as a cursor. The character ROM works entirely in the disk drives, and which character to use as a cursor. The character ROM works entirely in the video circuit and it determines what the characters look like on the screen (for instance, does the "f" have a high, small cross bar, or a lower, longer one of the Micro C character ROM). When you speed up your Kaypro, you are speeding up the processor clock so you have to use a monitor ROM that will also run at the higher speed. You are not changing the video clock when you speed up the Kaypro so you don't need to change the character ROM (unless you want the nicer looking character set). Since the monitor ROM tells the processor how to do disk accesses you are going to have to change that ROM in order to upgrade to larger drives.

Pro-Monitor II for Kaypro II

This ROM is a fast part so you can run 4 or 5 MHz with your Kaypro II.
 It gives you a non-blinking block cursor (much less irritating), though you can specify a standard blinking underline if prefer it.
 It does faster disk accesses (even if you don't speed up your system).

4. It throws away null characters (those little asterisks that sometimes garbage the screen during data communications).

5. Includes complete printed instructions for simple plug-in installation. (takes 5 minutes). Pro-Monitor 4 for Kaypro 4

This ROM does everything the Pro-Monitor II does, only it's for a Kaypro 4. Though the ROM that comes in your Kaypro 4 will run 4 or 5 MHz (unlike the ROM that comes in the II), this ROM also gives you:

1. Non-blinking block cursor

Faster disk accesses.
 Throws away null characters.

4. Complete printed instructions for simple plug-in installation (takes 5 minutes).

Pro-Monitor 8 package for Kaypro 4

This ROM package does everything the Pro-Monitor II and 4 do (it will run at 5 MHz, ignores nulls, has the fast disk accesses). In fact, even if you will be using your original 191K or 390K drives for now, you can use this ROM package. The Pro-Monitor 8 features include: 1. You get 784K per disk with quad density (96 tpi, double sided) Tandon 100-4 (or equivalent) drives

2. You can use any combination of Tandon 100-1 (Kaypro II), 100-2 (Kaypro 4), or 100-4 drives as drives A and B.

3. You can boot from any disk with normal system tracks (Kaypro II, Kaypro 4, or Kaypro 8). The disk needs no modification.

You can choose any character (including space) as a cursor and you can choose to make the character blink or not blink. Plus, you can change the cursor at will.
 You get a disk which contains a new copy routine for copying and formatting 784K disks, and a drive diagnostic routine for checking out the quad density drives.

6. You get complete printed instructions for installation of ROM and drives (takes 10 to 15 minutes, including drives). 7. The installation requires no cuts or jumpers, everything simply plugs into a Kaypro 4. (If you have a Kaypro II, see the modification article in Micro C issue 15 to turn your II into a 4.)

Pro-Character ROM (for Kaypro II and 4)

The character ROM gives you a nicer looking character set. Kaypros have come with two different character ROMs, the early character ROMs had a rotten g, y, q, f, and t as well as commas and semi-colons that were hard to tell from periods and colons. On the newer systems (manufactured since Sept 83) half of the characters (notably the g) have been improved, but they haven't gone all the way.

Also, many of the older character ROMs were poor quality parts so they generated snow information scrolled up the screen. This white flecky snow disappears when you install a Pro-Character ROM.

The character ROM comes in two flavors:

1. The standard Greek Pro-Character has the nicer character set plus the standard Kaypro Greek characters.

2. The Clean Pro-Character has the nicer character set but no Greek characters. This is the ROM for people who get strange Greek characters on the screen when interfacing with Mainframe

Systems.
Complete printed instructions for simple plug-in installation (takes 5 minutes).
Note: These ROMs will not work in the KayPro 10 or the latest KayPro 4 with graphics (it contains the KayPro 10 board). We are working on new ROMs for these systems.

Prices:

Pro-Monitor II Pro-Monitor 4 Pro-Monitor 8 (pac Pro-Character (either	kage)	 	 . 29.95
Pro Sat II (Pro Mari	ton II & Pao Chan		55 00

Pro-Set II (Pro-Monitor II & Pro-Character)		9.00
Pro-Set 4 (Pro-Monitor 4 & Pro-Character) .		5.00
Pro-Set 8 (Pro-Monitor 8 package & Pro-Cha	racter) 7	0.00



Pro-8 ROM Package

The PRO-8 package from Micro Cornucopia upgrades your KayPro 4 to a KayPro 8 with 784K bytes (96 directory entries) per Tandon 100-4 (or equivalent) quad-density drive. Plus, you can select your own cursor character (and change it at will).

The package includes the new PRO-8 monitor ROM, a disk of formatters and copiers, and printed instructions. (We even tell you how to turn your KayPro II into a KayPro 4.) All you add is one or two double-sided double-density (390K), or double-sided quad-density (784K) drives. You get over 1.5 Megabytes on a twodrive quad-density system!

This new system can read, write, and format KayPro II and KayPro 4 disks as well as KayPro 8 disks. And it recognizes each disk type automatically!

All this for only \$4995!

Watch Micro Cornucopia for more KayPro compatibles. Call or write for information on the other KayPro II and 4 ROMS from Micro Cornucopia.

KayPro II Schematic Package

This is a complete schematic of the KayPro, logically laid out on a single 24" x 36" sheet no more searching to see where a signal goes or comes from. Even the unused gates are shown.

It's drawn in positive logic, lines are labeled, and we've tossed in hours and hours of careful checking for accuracy. Then we added a Theory of Operation that's keyed to the schematic.

\$2000

Micro Cornucopia P.O. Box 223

Bend, OR 97709

503-382-8048



9-5 Pacific Time Monday-Friday



On Your Own

By David Thompson

This is a definite departure from previous columns. The idea for this "On Your Own" was triggered by a letter I received from Ralph Freshour of 7 Silver Eagle Road, Rolling Hills Estates, CA 90274. In that letter, he mentioned that he had been publishing a newsletter for NEC 8001A's and then he mentioned that he was going to be terminating the newsletter. Of course I had give him a call.

What follows are Ralph's comments about what happened. I've taken the liberty of doing some organizing and editing but then that's my job.

NEC newsletter

A year ago, I started a newsletter for the NEC PC-8001A computer. The computer is Z80 based and has two operating systems, NECDOS and CP/M-80.

It seemed like a natural system to support since there were over 18,000 users in the U.S. and since there was very little technical support from the manufacturer.

When I bought the NEC, I was very strapped for dollars so I bought it in modules. I mean, here was a machine I could buy as I could afford to, plus it was reliable and CP/M-80 compatible.

The newsletter was the same thing, a low investment thing I could build slowly. I invested \$300 at the start for materials and a classified ad. I sent releases to Byte, Creative Computing, Personal Computing and a few others. I purchased a classified ad in Computer Shopper (it wasn't a display ad, just a bit of text announcing the newsletter). By far, the best response was from the ad in Computer Shopper. Plus, the ad was cheap.

However, in March of this year I mailed out issue #7. This issue marked both the first anniversary of the publication and the end of the publication. Circulation was 150.

Marketing

It's hard to know why there were so few readers, but it's probably because most owners of the system never found out that the newsletter existed.

I started on a shoestring and spent just enough to have a classified ad in computer shopper. People who saw our ad and contacted us said they were pleased to know someone was doing it. Most were computer professionals—most felt alone and most felt that they weren't getting much help from NEC.

The magazine continued to grow at about 6 subscribers a month even after I stopped advertising which indicates that there has been some word-of-mouth advertising.

Production

It took me a while to get the printing costs down. I was having only 150 printed but I was paying \$250 per printing. You see, I was having so few printed that most of the cost was for making the plates and putting them on the press. I looked for a long time for someone cheaper and then, by accident I found a printer who was willing to do it for half as much. That helped a lot. The magazine was running 10-12 pages (5-6 sheets printed on both sides).

I was charging \$20 per year for a subscription so I wasn't exactly getting rich on the deal, but if I didn't count my time, I wasn't losing any either. (If I counted my time, I just got depressed.)

Time

I'm sure I spent 60 hours per issue, much more than I anticipated. In the beginning I did all the typing myself, then I had it typed by a professional. However, the original writing took a lot more time than I expected and product reviews often took weeks.

In fact, it was this demand on my time that really killed the magazine. If it had been financially more worthwhile, I would have stayed with it. But my other business, writing software packages in dBASE II, has really taken off so ending the newsletter is giving me that 60 hours to devote to this more profitable project.

Contents

The magazine contained mostly reviews of CP/M software that would run on the NEC.

In the process I reviewed the products of my advertisers and I lost some advertisers because I was critical of their products. However, they had to understand that I wore two different hats. One was advertising sales and the other was reviewer. The two didn't cross. I wanted to be able to get inside my system like Micro C gets inside the Kaypro and Big Board, but I don't have the technical knowledge to do that. Not being able to come up with nice system expansions was a real handicap because that would have made the publication unique and would have really helped sell it.

You really need a mix of software reviews and hardware mods to have a balanced publication.

Support from NEC

My relationship with NEC was very standoffish. They acknowledged my existence and referred a few people to me but the introduction of the new PC-6000 and PC-8800 meant they were really rushed and didn't want to bother with me. So I couldn't get the kind of information I needed from their customer support.

However, don't worry about factory support when you consider getting into the publication business. If you base your publication on the factory support then you are in a very difficult position. You are at the mercy of the whims of some big business. You need to remain independent so if something is a piece of junk, you can say so without fear of repercussions.

But, it would really have helped if NEC could have sent out my literature with their systems. That would have been great and I would have respected them more if they had done it. I don't think that would have tied me too closely to them. The only thing they did along that line was they mentioned me in their dealer newsletter, just my name and address.

Would I Do It Again?

I would definitely start another magazine. This small newsletter really kept me in tune with what is going on in the industry. If you are strong technically, you can really do a service to the reader by fielding technical questions.

Sharing is what the publication business is all about. It makes the computing more personal because you become isolated when you are off programming by yourself. I really enjoy that part of it.

Be sure to pick a popular computer

EXPAND YOUR PROTENTIAL

*** HARD DISK ADAPTOR**

Allows you to add megabytes of storage. Easy to install. Includes complete software and documentation. \$95.00 single unit quantity.

☆ CP/M 3.0 BIOS UPGRADE

Allows installation of CP/M 3.0 giving you a faster more powerful system. \$50.00 single unit quantity.

* PRONET

 – local network for Kaypro computers. Call to order or for information

OEM/DEALER INQUIRIES WELCOME Quantity Discount Available.



Solutions that work for you

307 SIXTH STREET HUNTINGTON BEACH, CA 92648 (714) 960-7498

with a popular operating system. If there are too many magazines already trying the water then maybe you shouldn't launch yours, but definitely look for a large audience.

Feedback, the Important Bonus

I was trying to create something that would meet the needs of my readers but I had very little feedback. A few people would write several times but most of them I never heard from.

That human connection is very important. I remember, when Arne Henden mentioned that in Micro C's FORTH column. People need to see that someone else is having the same problems and working on the same solutions that they are so they don't feel alone. Readers sign up for a publication so they can have contact with an editor who is using the same system or the same language. Of course, the editor needs contact too.

Though it was meager, this feedback was the most important bonus I got for producing the newsletter. I'll miss that.

GET IN THE FAST LANE

WITHOUT BURNING YOUR WALLET with a

U.S. ROBOTICS 1200 BAUD MODEM

Product: Password: Password 300: Telpac: Lamp:

Cash Price: 1-4 5+mix List: Features: Auto Dial 212A: 1200/300 baud, auto answer/dial..\$425..\$405..\$599 Coat-pocketable Auto Dial 212A...\$339..\$319..\$449 300 baud version of Password.....\$159..\$147..\$199 Modem Software from USR.....\$69...\$59...\$79 CPM/80 Modem Software from Widener Consulting.\$20

Latest Technology-----Fewer Parts-----Two Year Warranty

All units are direct connect, full or half duplex, 1200/300 baud, software compatible with the Hayes Smartmodems. The Auto Dial has two RJ11C jacks, analog selftest, status LED's and a metal case; Password has a smaller plastic case, no status LED's and a built-in RS232 cable with choice of male or female connector. Password 300 available soon. S-100 and IBMPC board modems also available. Lamp is based on YAM from BBUD #9.

---NEW PRODUCTS FOR BB AND KAYPRO!---

All those who have lusted after several add-ons for the Big Board I, but been discouraged by the shortage of parallel ports, take notice! Now you can run all the add-ons at once with the

Parallel Port Expander.....\$189 assembled, \$59 board + instructions

- eight I/O ports, compatible with Big Board I&II and Kaypro II&IV.

- operate 2 parallel printers, rom burner, hard disk, and Dynadisk! and if you are a real hog, parallel four expanders for 32 ports! bios with three printer drivers (1 serial) selected by IOBYTE. installation instructions for all mentioned devices included.
- - adapt Big Board add-ons to the Kaypro.

THE ULTIMATE

255 CONTINUOUS CHARACTER AND REVERSE VIDEO CURSOR BIG BOARD I AND KAYPRO II/IV MOD

Now you can have a significant increase in the writing power of your Now you can have a significant increase in the writing power of your system, with the ability to key in, display, edit, and print 212 characters, including continuous line graphics. Other features are blinking or constant reverse video cursor, character sets to match NEC 8023 and C.Itoh Prowriter, key labels, reverse video fields, install program for Perfect Writer, a growing library of software, and improvements in the monitor rom. The mod comes assembled and Software included tested and requires about 45 minutes to install. to define custom characters and down-load them to printers. Coming features include graphics software, circuit board layout tools and prototyping services, and H19 and IBMPC emulation.

NEC Extended character set (C.Itoh has same set, just re-arranged):

 $2 \cdot * \le 7 \cdot \uparrow \mathbb{M}_{4} \leftarrow \rightarrow + () = \mathbb{M}_{2} = \{ P \circ \notin \Omega P \circ \{ K \Sigma \alpha \nu \Delta P \in \uparrow \Theta \} \pm U \pi \Lambda^{2} \Theta + \tau \phi \omega \approx J^{2} \otimes J \phi \approx \chi^{2} \circ \xi \chi \mu$ ╾╾╾╼_═┺╔╋╅┫┫<mark>╱╎┥┲┚</mark>╺┚╺╧╼╌╛╱╲[┿]╲┯╖╽╽┎╶╝╎╎╓╲╵╵╵

The Ultimate Video Mod.....\$189.00 Perfect Writer.....\$209.00

Cash price with U.S. shipping; Visa/MC/Net30 add 3%, COD \$6. Dealer inquiries invited - quantity discounts available.

Widener Consulting 2835 NE Brogden Hillsboro, OR 97124 (503) 648-0363



Parallel Pulse Stretcher


When implementing King's parallel printer interface in issue #14, I did not have the ECG-220 FET. A local parts house had the item stocked, but at a price of \$4.50 each!

It seemed to me that a 2N2222 transistor should work in the circuit. The lower input resistance could be compensated for by using a larger capacitor. I substituted a .01 for the 470pf capacitor and a 2N2222 for the FET. I also used a 1N4148 (1N914) for the diode because it's what I had.

The circuit gives a strobe pulse of about 5ms and works fine with my Prowriter printer. I didn't make any attempt to optimize the capacitor value. The capacitor value may not be correct for all printers, but it seems fine in my system. **Cliff Nunnery**

313 Vaughn St. Fort Walton Beach FL 32548

Figure 1 - Parallel Pulse Stretcher



* * STOP THIEVES * * * * HAVE YOUR SCREEN SAY ANYTHING YOU WANT. * WITH A CUSTOM PROGRAMED ROM * * * * * * * * * * * * * * KAYPRO * HAVE YOUR NAME * Other * * * All Models* -COMPANY NAMEbrands * * * call first \$45 * PHONE NUMBER * * * * * disc on 2+ * * * * * * * WITH A CUSTOM PROGRAMMED "ROM" YOUR * * * SCREEN WILL SAY ANYTHING YOU WANT IT TO * * * Specify Model! * To order or more info: * Don Asquith 213-306-2146 * * Venice Ca. 90291 * 446 Sherman Canal * (please include: what your kaypro says now* *

Diablo 620 Proportional Spacing

The Diablo 620 printer is less than perfect when using the proportional spacing feature of Perfect Writer. To achieve perfection, make sure you have the 10 pitch pica wheel on the Diablo when you turn it on. Then while the unsuspecting printer awaits its mission, quickly slip on the proportional spacing wheel. It seems that when the Diablo is initialized with the proportional wheel, it is incompatible with the proportional writing of Perfect Writer.

John Beckett

Computer Service Department Southern College Collegedale TN 37315

E Z PROMMER EPROM PROGRAMMER

FOR THE BIG BOARD AND XEROX 820

FEATURES:

- Supports 2716, 2732, 2732A, 2764
- Easily installed with only two connections
- No external supply needed, all power derived from +5 Volts
- All power controlled by software
- Extensive MENU driven software to Read, Program, Save, Load, Verify CRC check, Dump, Erase check complete with source code
- Over one year of troublefree use.

EZPROMMER

A&T w/Harness, Disk\$125 Kit with Disk \$90

APL

CHARACTER GENERATOR FOR XEROX 820-II

Upgrade kit allows the 820-II to display all the standard characters and attributes while permitting the display of all APL characters. Kit includes ROM and software.

APL UPGRADE KIT ... \$49.95

NY RES. ADD LOCAL TAX. POSTAGE AND HANDLING \$2.00 VISA, MC, CHECK or COD

716-377-0369



	ally for the Big n Micro Cornuc	
REMEMBER FREE Users Disks in exchange for submitted software or articles	P.O. Box 223 Bend, OR 97709 (503) 382-8048	BB II DRIVE INTERFACE For 5¼° and 8° Drives Andy Bakkers is making this special software package available through Micro C. Complete source, HEX, & documentation files on an 8° SS SD disk. Also outlines on disk the hardware changes needed. \$29.95
	Cestercord, VISA	
	OX 820 USERS DISKS	USERS DISK #17 - Small C version 2 SMALLC2, this substantially expanded version of
	software. Each program has a .DOC	Small C now includes for, goto, label, switch (case); external declarations; new preprocessor commands;
USERS DISK #1 -Two fast disk copiers 4-Two disk formatters -The manual for Small C+ 5-Modem 7 -Crowe Z80 Assembler 6-Othello -Serial print routine-Port B USERS DISK #2 -Two single disk drive copy programs, both with	d many come with source. USERS DISK #11 - Printer Utilities 1-Microline 92 printer routine 2-Graphics display package for MX-80 with Graftrax, very fancy 3-Epson MX80 setup for BB 1 with 59.5K CP/M 4-Epson MX80 setup for any CP/M, lets you set print modes. 5-Micro Tek print driver, Ports A & B	external declarations, new preprocessor commands; expanded I/O includes redirection; initializers; plus 12 new expressions. The I/O and runtime libraries have been greatly expanded (including printf). Source & documentation on one full disk. USERS DISK #18 - FORTH IFORTH, this is Idaho FORTH which can be burned into ROM or loaded from disk. It replaces the PFM monitor & handles all the monitor functions. See issue #11 FORTH column for more info about
source 2-Crowe Z80 Assembler source 3-New Crowe.COM file, debugged version 4-New CBIOS with parallel print driver & other extensions for CP/M 1.4 & 2.2 5-Disk mapper with source USERS DISK #3	USERS DISK #12 - Games for BB I 1-ALIENS, a fast, exciting arcade game 2-ZCHESS, chess with a 1-6 level look ahead 3-MASTERMIND, match wits with the computer 4-BIO, Biorhythm charts complete with graphics on the BB I	IFORTH and this disk. USERS DISK #19 - BB I Double Density New BB I Monitor, BIOS, character ROM, Winches- ter Interface, ZCPR, and formatter from Trevor Marshall. See BB I expansion article in Issue #11. USERS DISK #20 - Assemblers
-EPROM burning software for BB 1 -Reset bit 7 (unWordStar a file) -Disk file CRC checker -New fast copy program & source -DU77, disk inspector/editor -FINDBAD, isolates bad disk sectors	5-LIFE, so fast it's real animation! 6-CRAPS, see how much you'd lose in Vegas 7-WUMPUS, a caver's delight, kill the Wumpus or be killed 8-PRESSUP, similar to Othello 9-Games, 7 games in one program, includes blackjack,	CROWEASM: This is the Crowe assembler modi- fied so that it runs on any CP/M system (including the BB1, BB1I, Xerox). Includes .COM .Z80 and .DOC files. LASM: This assembler is similar to the ASM that comes with CP/M except that it can link files at assembly time.
Print fancy page headings USERS DISK #4 -CBIOS, custom bios for Tandon drives -ZCPR, dynamite CCP checks drive A for missing .COM files; improved commands -ZCPRBLOC, identifies CCP location	maze and animal USERS DISK #13 - General Utilities, BB 1 1-ZZSOURCE, disassembles to real Zilog mnemonics 2-EX14, superset of submit or supersub 3-MOVPATCH, lets you use MOVECPM on other copies of CP/M	PRINTPRN: Print routine for CROWEASM.PRN files. LIBRARY: Utilities which let you combine many files into one, then you can run, type, or extrace any file within the larger system.
USERS DISK #5 -CAT, disk cataloging routines -Modem 7 for Port A -Modem 7 for Port B -PACMAN, the arcade game -FAST, buffers the disk to speed up assemblies	 4-XMON, 3K expanded BB I monitor, use in ROM or as overlay. 5-CURSOR, prompts you for cursor char you want 6-UMPIRE, very fancy RAM test 7-2SIDFIX, display improvement for ZSID 8-PIPPAT, modify PIP so you can reset system from 	USERS DISK #21 • Winchester Utilities BACKUP: Helps you back-up the winchester onto multiple floppies. Creates a catalog of the files on each disk and includes the date of the latest backup. Will not back-up an unchanged file more than once. Plus many more super features. FLOPCOPY: Lets you make floppy copies (with
>-NOLOCK, removes BB 1 shift lock 1-VERIFY, cleanup & verify a flaky disk 3-DUMPX, enhanced for BB 1 3-UNLOAD, create. HEX file from .COM file	within PIP 9-@, Lets you use the BB as a calculator, including HEX 10-SORT, sort package written in C80.	only one floppy drive) by using the winchester as a buffer. BIGBURST: Backs up a very large winchester file
USERS DISK #6 I-REZ, 8080/Z80 disassembler, TDL mnemonics 2-PRINTPRN, prints Crowe listings 3-RUNPAC, run-time utility package for 8080 assem- bly language programs. Has 51 functions. Includes	USERS DISK #14 - BB II Software 1-PRO32, latest 2732 reader & programmer 2-SMODEM2, lets BB II talk to Hayes Smartmodem 3-GRAFDEMO, demonstrates BB II graphics (in BASIC)	onto multiple floppies. Joins the copies to recreate the original file. MULTCOPY: Use this like PIP but it prompts you to change disks. Accepts ambiguous file names. MDIR: Displays files in all user areas on selected drive. Many features.
source which assembles under ASM. USERS DISK #7 I-CHNGPFM, PFM monitor mods	4-ATTRTEST, demonstrates BB II graphics (in JRT Pascal) 5-INITSIO, initializes port B for 300 or 1200 baud	MAKE, MOVE: PIP-like utilities that make it easy to move files between user areas. SWEEP: The famous disk cleanup and transfer
2-TERM, terminal routines let you set up BB as simple terminal, as a file receiver, or as a file sender 2-Checkbook balancing package 2-Disk Utilities - copy to memory, from memory, and dump.	6-MENU, displays menu of .COM files, enter number to run file 7-SETCLK, sets realtime clock built into BB II 8-PRINT2, modified print which accesses BB II clock 9-BOX, draws a thin line box on screen determined	routine that does just about everything you can do with TYPE, ERA, DIR, and PIP. UNSQ: This is the latest, greatest file unsqueezer. Enter UNSQ *.* and it will check every file on the disk. All squeezed files will be unsqueezed.
USERS DISK #8 1-BDSCIO, custom BDSC I/O for BB 1 (both .h and .c)	by HL and BC 10-ALIENS, space invaders arcade game 11-LISTSET, printer interface, auto-enables RTS, ignores DCD.	8" Users Disks
2-YAM, Yet Another Modem program in source & .COM form. Turns BB into paging intelligent terminal, complete with printer interface, baud rates to 9600. D-ROFF, text formatter	USERS DISK #15 - Word Processing 1-EDIT, very fancy line editor similar to EX (Unix). Includes help menu, programmable key, and full manual on disk. 2-TED, simple minded line editor, easy to learn &	\$15.00 each
-SIGNS, prints large block letters USERS DISK #9	use. Very fast. 3-TTYPE, typing training program written in BASIC	OTHER GOODIES
I-ADVENTURE, expanded 550 pt version 2-Keyboard translation program 3-CBIOS, serial & parallel printer interface 1-EPROM programming package for BB II, for 2732s	 4-TINYPLAN, very simple-minded spreadsheet. Whets your appetite for a fancy one. 5-C80 Text Utilities 6-CHOP, cuts off file after N bytes 	Screen Editor in Small C \$39.00 A simple but full-function screen text editor plus a text formatter, all written in Small C by Edward Ream. This package includes the editor and formatter
only USERS DISK #10 - Lots of Disk Utilities 1-REBOOT, sets up the CP/M auto load 2-SWEEP, directory/file transer routine 3-A, Lets BB I recognize a double sided drive as one drive with 494K of usable space	 7-ENTAB, replace spaces with tabs where possible 8-MS, double or triple spaces a file to output 9-RTW, removes trailing spaces from file 10-TRUNC, truncates each line to specified length 11-WRAP, wraps at column 80, plus pretty printing, page #s 	.COM files setup for the Big Board, Small C itself, and source code for all. With the documentation this is over 400K on a flippy disk. Edward is selling this package for \$50, you can buy it from us for \$39 (and Ed gets a royalty). Where else can you get an editor, a formatter, a C compiler, and source for all, for under

- 3-A, Lets BB I recognize a double sided drive as one drive with 494K of usable space
 4-FIX, super disk utility, does everything, much easier to use than DU77
 5-Compare files routine
 6-UNERA, retrieve erased files
 7-FIND, check all drives on system for a file
 8-MENU, menu program for CP/M
 9-NEWCAT, enhanced disk catalog program
 10-Single drive copy program that does track by track copies rather than file by file

MICRO CORNUCOPIA - P.O. Box 223 - Bend, Oregon - 97709

- USERS DISK #16 BB I Modem Software I-RCPM27, list of U.S. bulletin boards 2-SMODEM, interfaces BB I with Hayes Smartmodem 3-PLINK66, easy to use with non-CP/M host, for port A
- 3-PELINNOO, casy to use minimum port A
 4-BBPAT, menu selection of BAUD rate, bits/char, parity, & stop bits
 5-MODEM 7+, Modem 7 plus BBPAT, lets you talk to anything from port A

formatter, a C compiler, and source for all, for under \$40?

M68K Single Board Computer

By Raymond L. Buvel

About a year ago I needed a computer based on the Motorola MC68000 microprocessor, but I didn't want to spend a fortune on it. I already had a Big Board up and running with lots of nice software and didn't want to buy another complete system.

What I had in mind was a slave coprocessor with its own memory that could run independently of the Big Board. The M68K single board computer from EMS (Educational Microcomputer Systems) fit the bill nicely. It cost me about \$600 to build (I think it can be done for \$500 at today's chip prices) and has been running reliably since I brought it up.

Strengths

The M68K computer can run at 10MHz with the MC68000 chip from EMS and 250ns RAM and EPROM chips since there is a 200ns wait state built in. There is 20K of static RAM (10 6116's) and 16K of EPROM (2 2764's) on the board. The machine also has two RS-232 serial channels and a 16-bit bidirectional parallel port for the built-in I/O.

There are also five 16-bit counter/timers provided by the AM9513 System Timing Controller (which is also the baud rate generator for the serial channels).

The timer chip is wired up to one of the vectored interrupts on the board (there are 7). There are two separate memory expansion busses, so you can add up to 384K of RAM and EPROM to the system. I/O expansion is provided through an MC6800 compatible 8-bit peripheral expansion bus with address space for 1024 ports.

The monitor is almost identical to the Motorola MACSBUG monitor. It has built in execution and trace features usually found only in a debugger like CP/ M's DDT. The monitor takes up 8K of the 16K EPROM space (two 2764s).

If you are building this computer, I recommend that you purchase the monitor (even though it is overpriced in my opinion). Then you will have a convenient way to test out the hardware.

I plan on writing a very simple resident operating system for M68K that will allow me to produce programs on the Big Board and send them over to the M68K

through the parallel port (it is currently attached to my Big Board through a serial channel). There should be plenty of room for this while still allowing the monitor to be resident for debugging.

Weaknesses

The documentation supplied with the M68K is terrible (but adequate for people who know what they are doing). I would not recommend constructing this computer unless you have built a Big Board or some other computer of equivalent complexity.

When I brought up the M68K, I had to wire pins 12 (BGACK*) and 13 (BR*) on the MC68000 chip to +5V to get the computer to run. These lines are not used in this design and EMS just let them float. As it turned out, they floated to the wrong state and locked up the CPU.

I also had trouble locating a crystal oscillator module until someone pointed out that Jameco sold them. I wrote to EMS but they didn't even bother to tell me where to find the module.

One other complaint I have with the board concerns the 16-bit bidirectional port. The port is buffered but not latched so it is a lot more trouble to use than the parallel ports on the Big Board. Also, the handshaking on the port is not nearly as nice as that on the Big Board PIO.

The most serious problem with this machine is the lack of software. I have partially solved this problem by writing my own cross compiler that runs on my Big Board under Z80-FORTH. (It will hopefully be available on a user disk soon.)

With this compiler and a cross assembler, I can write the software I need. I use the M68K for doing high speed numeric calculations so I don't need a fancy operating system or a lot of utilities. The Big Board is perfect for that task.

For those who need a cross assembler to run under CP/M, EMS offers one, but I don't know how good it is. There is also a public domain cross assembler written in FORTRAN that may be available from some user group. I have also seen several ads in BYTE and Dr. Dobbs Journal for 68000 cross assemblers that run under CP/M.

Conclusion

I have used the M68K computer for about a year and I am satisfied with it. This is definitely the least expensive MC68000 computer I have found.


For use as a co-processor, the M68K is a nice machine. However, anyone who needs an MC68000 based microcomputer in their business should look elsewhere.

Prices

The bare board with documentation is \$99.95, the debugging monitor in 2764s is \$120, and the CPU and memory map ROM is \$115.


M68K Single Board Computer **Educational Microcomputer Systems** (EMS) PO Box 16115 Irvine CA 92713-6115 (714) 553-0133

CP/M 2.2 LICENSE AND SUPPORT



Box 3071 Moscow ID 83843

Big Board and Xerox 820 **EPROM** programmer kit



\$75.00

Backed by our "Money Back Customer Satisfaction Policy"

- Programs 2516, 2716 (5 V), and 2532 EPROMS. (Most users only require the above list, so why pay for more?)
- Plugs into parallel port
- User friendly menu-driven software written in BDS C with all 1800 lines of source code included.

Now available in the the following packages:


Software and Documentation only	\$25
Software, Documentation, and Bare Board	\$55
Complete Kit	\$75
Demo Disk and Documentation (refundable)	\$5

Send for the package that suits your needs or for a free brochure describing all the features of our EPROM programmer. Be sure to include \$5 shipping charge for any of the packages above. All prices are in U.S. funds. New York State residents please add 7% sales tax.



Kenmore Computer Technologies 20 Landers Road Kenmore, NY 14217 (716) 877-0617

ABLE II VT INTELLIGIENT STAND ALONE **VIDEO TERMINAL WITH** MANY HIGH END FEATURES



ASK ABOUT OUR EMULATION SOFTWARE FOR USE UNDER

CP/M (CP/M is a TM of DIGITAL RESEARCH INC.)

RT CLOCK

ON-SCREEN SET-UP

VIDEO ATTRIBUTES

* Easy Emulation * A Very Powerful Low Cost Terminal Board * 6502 CPU & 6845 Video Controller * 4K Control in 2732 EPROM

Emulate or Customize with powerful download feature Custom programs and escape tables retained during power down * Defaults to control ROM tables (H19 Compatible) when not modified * Month to MSEC Real Time Clock; Display to Sec, Transmit to MSEC * Reliable battery interface for clock and 2K user RAM * Menu driven set-up * Powers up as previously configured * History, for communcations analysis, displays last 256 video, escape and control char received * 2 Program/Menu selectable RS-232 compatible ports, with Daisy Chain * 16 Program/Menu selectable baud rates (50 to 19,200) * TTL and RS-232 level baud clock outputs * 6 Program/Menu selectable bell tones * 9 Menu cursor selections (Box, underline, overline/ solid, blink fast or slow) * Menu selectable auto LF on CR and/or Auto CR on LF or neither * Local, full duplex, simplex operation * 80x50 video with 80x24 screen window * Up/Down scroll with non-destruct mode * Transmit screen from top to cursor * cursor home, forward, backward, up, down * Horz. tab * full X-Y cursor control including save, restore and report cursor ' cursor on/off * clear screen, clear line, erase to end of screen, to beginning of screen, to end of line, to beginning of line * Char selectable, normal, inverse, blink and low intensity * 96 Upper and Lower case with descenders * 32 interconnecting line/block graphic set * type ahead buffer * 8½x11 silk screened, double sided, glass-apoxy PC board * only uses easy to get parts * requires parallel ASCII keyboard and standard composite video monitor * made in U.S.A.

Bare Board, Programmed Control ***CALL OR WRITE*** & Char. Gen EPROMS, Complete Detailed Documentation Including Schematice and Source Listing.

– NOW ONLY \$79.95 —

Complete Documentation - \$10 (Refundable with purchase)

Will Accept MC & VISA

LINGER **ENTERPRISES, INC.** P.O. Box 5783 Newport News, VA 23605 804-244-3874

Add \$2 shipping & handling (VA residents add 4% tax)



Dear Editor,

The recent Micro C answered a question I had about why the Kaypro II CRT displays go belly-up above 2400 baud (in serial input > CRT). I thought it was only juggling 1 ball; but with 1920 in the air, I see why one more is too much.

Software scroll seemed like a dumb idea until I read about screen-dump calculations on hardware scroll.

Al Paarmann 368 El Gaucho Road Santa Barbara CA 93111

Editor's note:

Actually, the very early Kaypro IIs had the hardware scroll circuit installed. They didn't use it because Gilbert Ohysnty couldn't figure out how to do the hardware scroll calculations in the monitor. Later, they removed the 3 ICs because they weren't using them.

Dear Editor,

In the installation of ZCPR to CP/M, I SYSGENed a blank disk, PIPed the six programs (3 from CP/M and 3 from ZCPR), and entered EX14 INSTALL (cr).

The program just gets rolling when the message, 'Synchronization Error' appears, and the program locks up. RE-SET is the only way out.

Since you have my interest whetted with ZCPR, I hope you can get me 'synched'!

J. Karl Jones 220 Wilson Hall Kansas Wesleyan Salina KS 67401

Editor's note:

Yep, I can get you synched. You see, MOV-CPM is part of the installation routine in IN-STALL. MOVCPM looks at the serial number on the system tracks and at its own serial number before starting to work. If the serial numbers are different, it displays a synchronization error and locks up. That's Digital Research's method of encouraging people to purchase their own copies of CP/M.

So, you need to get out your original CP/M distribution disk. It has the system tracks and MOVCPM that match. Copy the system tracks (use SYSGEN.COM) onto a blank, formatted disk and then copy MOVCPM-.COM. Then add the other programs you need to create the ZCPR disk. Dear Editor,

I received your K2 disk yesterday and am very happy with all of the programs as I have been with your other disks.

However, my main reason for ordering the disk was to get a copy of the UN-.COM and UN.DOC for getting back to the source on protected MicroSoft BAS-IC files.

As far as I can determine the programs are not on the disk although your advertising and the disk directory indicates that they are. Charles Clark 689 N. 800 W. St. Provo UT 84601

Editor's note:

Sorry, those utilities are not on the disk. UN.COM doesn't work on MicroSoft BASIC any longer (MicroSoft obviously made some changes to defeat UN) so we took them off the disk. Unfortunately, our ad brochures still show the files.

Dear Editor,

I am looking for a good, well debugged version of Kermit so I can talk to a person who doesn't have MODEM7 configuration yet for his system. Steve Schick 4244 Cheeney St. Santa Clara CA 95054

Editor's note:

Yep, we have Kermit configured for the Kaypro. It's on two full disks and costs \$24. Just ask for Kermit.

Dear Editor,

I've had some problems using the keypad when running ZCPR. Any suggestions?

Also if you could consolidate all of the Kaypro modifications that you have discussed, and write them in a fashion similiar to your reply to Chris Paulsen in issue #15, it would be a big help.

Charles Dugan 3834 136th Ave SE Bellevue WA 98006

Editor's note:

See the Kaypro column in issue #15 for the ZCPR patch.

As far as the Kaypro II is concerned, I'd do the following.

I'd do the Kaypro II to Kaypro 4 mod first, and then get the PRO-8 set. After installing the new monitor ROM (and Z80B) I'd speed the system up to 5 MHz (definitely include the switch so you can go back to 2.5 MHz). Then I'd purchase a copy of Uniform for the Kaypro 4 from the Uniform folks (supports about 25 formats) and install two halfwide Kaypro 4 drives (the double sided TEACs) as drives A and B and two half-wide quad density TEACs as drives C and D.

I'd also get a copy of Plu-Perfect for the Kaypro 4 and ZCPR. Plu-Perfect is great if you use Perfect writer and want to custom configure the keypad.

I would put ZCPR on all but my Plu-Perfect disks.

Once you are finished with all this, you can add the Co-Power board if you wish or the Delphi winchester system (we're using it with the PRO-8 now and it's great).

Of the stuff coming up, I'm really interested in the MicroSphere 64K add-on which gives you a 128K Kaypro. The additional 64K will act as a track buffer which makes disk accesses really scream. They are doing Logo for their color graphics board which has my two grade-schoolers very excited.

Dear Editor,

I have a few questions about the Kaypro end of Micro C. Regarding user disks, do you know if the Epson MX-80 is enough like the Gemini 10X that I would have any use for disk K5 (MX-80 Graphics Software)?

Also, I know that ZCPR is usually available as an ASM file, so that some options can be modified. Will you be making it available on Kaypro format?

Incidentally, as to why more people don't use SBASIC, in my case the answer is that like many compiled highlevel languages, it doesn't generate very compact programs.

For example, the little program in the Kaypro User's Guide to turn off the keyboard beeper compiles to a little less than 2K (780H).

A routine in assembly language to do the same thing occupies only four bytes: (MVI A,8 ! OUT 5). This is because SBA-SIC puts portions of its library files into each program.

So far I have used SBASIC to test concepts, but I have used assembly language for the final effort.

Philip E. Bond 27 Sharon Drive

Spring Valley NY 10977

Editor's note:

Yes, Philip, disk K5 does work on the Gemini 10X. Also, you can send for Kaypro disk K22 which has a newly updated version of ZCPR which works on the Kaypro II, 4, and 10 and it's complete with source.



Order Line: (214) 272-5724 9 AM - 8 PM CST	EPIC SALES	132 Plano - Walnut Cente Garland, Texas 75040
¹ /4" WINCHESTER SUB-SYSTEM	8" FLOPPY DRIVES	5¼" DRIVE SUB-SYSTEM
NEW	SIEMENS FDD 200-8	
Includes: 10M Seagate ST-412 Drive, Host Adapter Board, Controler Board, Software Case, Fan, Power Supply & Cables.	DSDD 8" Floppy Drives [Shugart 850 Compatible]	
Available For:	\$229 NEW	Includes: [2] 5¼" Half High Panasonic Drives, Power Supply & Case [Vert. or Horiz.]
IBM PC Apple Xerox 820, BB-1 S-100 S-100	8" DRIVE SUB-SYSTEM	\$459 NEW
	DSDD Drives, Horiz. Case and Power Supply	5¼"HALF HIGH DRIVES
Multibus } \$1399	\$749 NEW	
[5 and 15 Megabyte Systems also Available]	ψ/ 1 .5 ΠΕΝ	Panasonic Drives
	MULTIBUS BOARDS	[SA-455 Compatible] 40 Track, 48TPI
5 ¼" SEAGATE WINCHESTER DRIVES	SBC 86-30 256K \$899 SBC 86/12 \$449 \$449 SBC 80/30 \$299	\$199 NEW
St-406 [5M]\$399 ST-412 [10M]\$599 ST-419 [15M]\$799	SBC 80/20 \$199 SBC 534 \$199 SBC 544 \$499 SBC 519 \$199 SBC 519 \$199	DISK DRIVE CABINETS
All are New Drives	SBC 218 \$199 SBC 215 \$499 SBC 208 \$449 TI 512K ECC \$899 10 512K ECC \$89	5¼" Dual ½ High Case with Power Supply [Vert. or Horiz.] \$72.00
WINCHESTER CONTROLLER	18 Slot Backplane\$'75	8" Dual Full High Case with Power
& HOST BOARDS		Supply [Horiz.] \$325.00
	FLOPPY CONTROLLER CHIPS	5¼″ Dual Full High Case
Xebec 1410 Controler \$325 IBM Host [Xebec] \$125	1771 \$12.95 1791 \$19.95	7" H X 7" W X 10" D \$15.00
Apple Host [Xebec] \$125 S-100 Host [Xebec] \$125	1793 \$19.95 1797 \$24.95	
Multibus Host [Xebec] \$195 Software for above \$ 20	2793 \$39.95	ROBINSON NUGENT IC SOCKETS
Xerox & Bigboard Host [Epic] \$ 75		Low Profile Solder Tail Sockets All Sizes .10 Each, \$70/1000 \$25.00 Minimun Order
LATE SPECIALS	ALL PRODUCTS BACKED BY	
Disk Drives Cables 5¼"	OUR 90 DAY GUARANTEE!	64 Dram 200ns \$5.25



Are you signing your name with an X because spelling doesn't come easily?

Then you need SpellSys!

With this full-feature package, you can write prose with the pros. SpellSys features a 42,000 word dictionary and all the bells and whistles of those expensive checkers—including rhyming, crossword search, letter unscrambling, etc.

SpellSys is made up of a group of individual programs which you can use together or separately. With SpellSys you can setup and maintain your own custom dictionary (in addition to the main dictionary). These are real dictionaries, not hash tables, so you edit or remove words from your own dictionary at will.

micragraup

EDITORIAL (continued from page 1)

exchange information. The phone has become a very important part of that and when someone calls with a problem or request that eventually leads to an important solution, then we all gain. And, even more significantly, some of the calls are from people who have figured out answers to problems that have been bothering folks for a long time.

However, a large share of the requests for information are from people who are simply too lazy, or too stubborn, or too something, to get the information for themselves. The fact that we are accessible leaves us at the mercy of anyone with a spare hour (or two!) and a Sprint line.

If You Need Help

We are glad to help. Your questions can be very basic or very advanced. However, Please! Try to help us too.

1. Try your darndest to find the information for yourself. If the question is about a software package or a piece of hardware you purchased from someone other than Micro C, contact the manufacturer about the problem. We can't possibly know every nook and cranny in Just enter "SPELLSYS", select which disks you'll use, and file you're checking. Then SpellSys takes over. Everything is self-prompting—so sit back and relax. Word Review Operations C...show Context in file L...Lookup word in dictionary

- M .. Misspelled (correct file to.....)
- **D**...put in user Dictionary
- I ... Ignore

IT'S EASY TO USE!

- N ... Next word
- P ... Previous word
- E ... Exit review

? .. (or any other key) displays menu

ORDER AT NO RISK!

Check out the manual and if you don't agree that SpellSys is a super bargain, just return the package with the disk unopened within 30 days and we'll refund your money.

SPELLSYS \$29.95 ppd. in US & Can Other Foreign add \$5.00	
Requires 32K CP/M*	ļ
Formats: 8" SS SD or	
5" SS DD for KayPro, Xerox, Osborne, Morrow, Superbrain.	
*CP/M is a trademark of Digital Research	•
P.O. Box 65 Bend, OR 97709	
MC (503) 382-8048 Visa	

every product we've mentioned (or haven't mentioned).

If they won't take the time to support their product, then maybe the best thing we can do is push them a little. Send us a letter to the editor detailing the problem and the lack of support. They'll get to hear about it.

2. If you're working on something that we've covered in a back issue, please be willing to order the issue. Don't call and expect us to spend half an hour telling you what the article said so you can save \$3.00.

3. Try to locate your own sources of parts like disk drives. If you call, we'll tell you to check the ads in Micro C, in the back of Byte, or in the Computer Shopper. We'll also try to keep you posted on good sources in our columns. Cascade Electronics and Micro Processors Unlimited are both good places to start.

4. We encourage you to dig into your system, but don't do it if you are totally lost. Read up, get help, practice on something a little less important than your computer.

In almost every community there is a CP/M users group. Check with your local computer stores to locate such a



12" GREEN ball brothers TV-12 monitor in enclosure $19 \times 16.5 \times 14$ ". Room for mounting BB1, BB2 & X820 type SBC's; 8" drive(s) & power supply (see below). Needs +15 Vdc @1.2 Amp, Non composite (separate sync) input. Used & 100%Tested.

MONITOR & ENCLOSURE (30#) \$65.00

Matching keyboard & enclosure $19 \times 4 \times 5^{"}$, 77 keys. Non-functional lighted pushbuttons on far right missing. sold only with monitor. **KEYBOARD & ENCLOSURE (6#)** \$45.00

Unregulated power supply; outputs: 9 v @10 A, 30 vct @ 2 A, 18v @ 1.5A, 14 v @ 0.5 A. Includes transformer, capacitors, rectifiers & heatsinks. Add 3 terminal regulators for cheap power. Removed from used equipment. UN-REG POWER SUPPLY (25#) \$15.00

Regulated power supplyu; 6 outputs: 5v @ 4 A, +/- 12 v @ 0.2 A, +24v @ 1.2A, -24v @ 0.2A, +15v @ 2.6 A. $14 \times 4 \times 3$ ", 10 lbs, New. **REGULATED POWER SUPPLY** \$35.00

ARKON ENGINEERING PO BOX 60, Rome NY. 13440 (315) 336-4381 anytime or (339-2232 evenings) TERMS: Prepaid or UPS COD (CASH OR CERTIFIED CHECKS ONLY.)

group. Then get active. You'll find a wealth of support and training as well as access to people with test equipment. It's very difficult for us to help you service your system by phone, especially if you have no test equipment. (We wouldn't dream of tackling our own systems without at least a logic probe.) And, much of what we can tell you on the phone we've already covered in the magazine.

5. If you are totally in a bind with nowhere else to turn, then call us. But before you pick up the phone:

Try to get as much information about the problem as possible. When does it happen? When doesn't it happen? Is it heat sensitive? Is it consistent? Have you tried swapping parts? Have your tried the ice bag trick on all the chips (including your new Z80B)? Can you undo things you did one by one and get it to work again? Did you take any shortcuts? Meanwhile, you really need some way of seeing what is happening inside the circuit (a scope or logic probe).

Now, have the system in front of you (preferably messing up), take a test probe in your left hand, the phone in your right hand and then call us (no fair swapping hands).

WANT ADS

The following folks are reaching you for only 20 cents per word. If you would like to reach the same audience, send your words and 20 cents for each to Micro Cornucopia.

Protect your schematics. Heavy duty vinyl sheet protector, 11X17, 3-hole punched, perfect for BB schematics! Six for \$6.00 postpaid. Tony Ozrelic, LA Software, 6708 Melrose, Los Angeles CA 90038.

dBASE II Consulting Service. Los Angeles area. Give us a call, we may be able to help you solve your dBASE II problems. Call 213-375-6391. Ralph Freshour, consultant.

Xerox 820 boards, completely assembled and tested. \$150, includes shipping, manual, schematics, ROM source code listing. Call evenings (818) 340-5410, or write Jiri Kratt, 20311 Sherman Way #316, Canoga Park, CA 91303.

Big Board II System: BBII, 20meg Rodime Winchester, Xebec Controller, Siemens 8" DSDD in Ferguson enclosure with power supply, \$2475 o.b.o. Keyboard with Amdek 300A 12" amber monitor, \$150. All used only one month. Jay Tucker, 501-227-9079. 8" Disk Drives Used, clean, working disk drives. Several models available, SSSD at \$100; DS, DD \$225; Cases available. Quantity discounts. 12" B&W Hi resolution monitors 80 column. DC model 15VDC @ 1.1A \$35. AC model 115V \$45. Both drives and monitors work with BB or Xerox 820. Call evenings. R. Breinlinger, 51 Wash Pond Road, Hampstead, NH 03841 603-329-5838.

BBI ROM Terminal Emulator. Menudriven selection of SIO port, baud rate, parity, etc. Interrupt-driven I/O loafs at 9600 baud. Uses one EPROM slot. \$29.95 ppd (\$34.95 for 2716-1). Unified Software Systems, PO Box 2644, New Carrollton MD 20784.

Public Domain UG Software Rental: CP/ M UG Vol 1-92 on 46 8" Flippies \$45.00, SIG/M UG Vol 1-150 on 75 8" Flippies \$75.00, PICONET Vol 1-34 on 17 8" Flippies \$25.00, Pascal-Z UG Vol 1-25 13 8" Flippies \$20.00, UG Games 20 Vols of the best ones \$20.00, UG Modem 20 Vols of the best \$20.00, UG Business 20 Vols of the best \$25.00, UG Utilities 10 Vols of the best \$20.00. Rental is for 7 days after receipt with 3 more days grace for return. Credit cards accepted (preferred). 5" disk formats also available. Downloading-disk format conversions. Call. User Group Software Automatic Update Service—\$7.50 per 2 volume set PP. 619-727-1015 24 hrs. 619-941-0925 info. P.J.'s National Public Domain Software Center, 1062 Taylor Street, Vista CA 92083.

Kaypro SoftwareMemory Bugout—Isolates defective Memory Chips for easy repair. Pays for itself with first failure. (Assembly Language). \$19.95. Maillist— Create and maintain your Personal / Business Mailing List. Prints Mailing Labels, Menu driven, easy to use. \$34.95. ABRAMS CONSULTING (Custom Kaypro Software), 9615 Cecilwood Dr., Santee CA 92071. CA residents add 6%.

For Sale: P-Mate Text Editor, world's best full-screen, macro-command editor; versions for CP/M, CP/M-86, MS-DOS, PC-DOS; customized version using BigBoard I memory-mapped video for fast display (Kaypro, Xerox similarly). Sage Microsystems, 1435 Centre, Newton MA 02159, 617-965-3552 (voice) or 617-965-7259 (RCPM, 300/1200 baud, 24-hrs, logon password = BIGBOARD).

4116's 8/\$3.99. 250 ns pullouts. 200 ns 8/ \$4.99. Add \$1.50 per order for shipping. Claire Love, 621 'M' St., Hoquiam WA 98550 206-533-3484.

SUPERB MAILING LIST PROGRAM for CP/MTM 2.2 supplied on 8" SSSD or now available for Kaypro 5.25". Requires two disk drives and printer capable of 132 columns for maximum usage. Installation program module included. Special introductory offer by ABLE DATATM SOFTWARE, INC., P.O. Box 86923, Station C. North Vancouver, B.C. V7L 4P6 only U.S. \$19.95 postpaid check or money order.

Just remember, any time we are talking on the phone is time we aren't working on new Kaypro, Xerox, Slicer, or Big Board projects. Anything you can do for yourself, will be a big help to us and to everyone who reads Micro C.

Text Co-Processor Reports

You folks calling us must wonder what the heck is going on at Micro C these days. If you're wondering why there's a bit of confusion, it's because of the rapid increase of employees (yep, 2 new ones since January, me included).

Both of us are getting our feet wet at once (the carpet is getting soggy in places) and that's causing all the stammering, stuttering and groping for answers that is part of learning a new language and system. Please bear with us through these fluid times.

Structured vs. Unstructured

Those reading Micro C know that we're structured programming zealots. However, you may not realize that we're also unstructured work-lifestyle zealots. This, of course, creates the mayhem and anarchy that makes working here so interesting.

For example, last week I decided to work most of the days of the week, but only 2 to 4 hours at a time, popping in whenever convenient. This really makes Alice envious. She has to be here, 8 to 5, Monday through Friday, chained to her desk.

Tracey will be working Monday, Wednesday and Friday. Dana works a Monday through Thursday schedule, plus countless odd hours. Dorcas works Monday through Friday, like Alice and, of course, no one ever knows when Dave will be here or won't be here.

Having explained all this, I hope the insight will give you a couple of chuckles next time you call and find that those who are here aren't even sure who's here. (Which may come from some of us not ever being all here).

David Thompson Editor & Publisher



Micro C works because it is a central information exchange for the doers in this crazy industry. So we encourage you to share your trials and tribulations. That way we can invent new wheels rather than redoing the old ones over and over.

What information would you like to see in Micro C?

What kind of exciting adventure (misadventure) are you working on?

o			Price Each		
Quantity	Description	U.S.	Can & Mex	Other Foreign	Total
	SUBSCRIPTION (1 year—6 issues)	🗆 \$16 (Bulk)	□ \$20	□ \$26	
	New Renewal	□ \$20 (1st Class)	(Air Mail)	(Air Mail)	
	USERS DISKS – 8" SSSD, CP/M #'s	\$15	\$15	\$15	
	CP/M 86 DISKS – 8'' SSSD #'s	\$15	\$15	\$15	
	KAYPRO DISKS for the II, 4, & 10 – 5" SSDD #'s	\$12	\$12	\$12	
	BACK ISSUES #'s	\$ 3	\$3	\$5	
	OTHER ITEMS:				•
		· · · ·			
Prices inclu	ıde media, package, 1st Class postage (Air Mail for C	Other Foreign)			
	r money order enclosed ds only, payable on a US bank)	Make checks j MICRO COR		TOTAL ENCLOSED	
Card No	0	Exp		<u></u>	
□ Visa	□ MasterCard		Signature		
NÅME		I	PHONE (?) _		
ADDR	ESS			- <u> </u>	
אידיזר/			STATE	ZIP	
_11 Y					

BACK ISSUES

\$3.00 each US, CAN, MEX

\$5.00 each Other Foreign

ISSUE NO. 1 (8/81) Power Supply **RAM** Protection Video Wiggle 1/2 PFM. PRN 16 pages

ISSUE NO. 2 (10/81) Parallel Print Driver Drive Motor Control Shugart Jumpers Program Storage Above PFM 1/2 PFM.PRN 16 pages

ISSUE NO. 3 (12/81) 4 MHz Mods **Configuring Modem 7** Safer Formatter Reverse Video Cursor FORTHwords begins 16 pages

ISSUE NO. 4 (2/82) **Keyboard Translation** More 4 MHz Mods Modems, Lync, and SIOs Undoing CP/M ERASE Keyboard Encoder 20 pages

ISSUE NO. 5 (4/82) Word Processing Two Great Spells **Two Text Editors Double Density Review** Scribble, A Formatter 20 pages

ISSUE NO. 6 (6/82) **BB I EPROM Programmer** Customize Your Chars Double Density Update Self-Loading ROM Terminal in FORTH 24 pages

ISSUE NO. 7 (8/82) 6 Reviews of C Adding 6K of RAM Viewing 50 Hz On Your Own begins 24 pages

ISSUE NO. 8 (10/82) Drive Maintenance Interfacing Drives Installing a New BIOS Flippy Floppies C'ing Clearly begins Xerox 820 begins 28 pages

ISSUE NO. 9 (12/82) **BB II EPROM Program** Relocating Your CP/M Serial Print Driver **Big Board I Fixes** Bringing Up WordStar Cheap RAM Disk 32 pages

ISSUE NO. 10 (2/83) Saving a Flaky Disk Hooking Wini to BB II The Disk Inspector JRT Fix Serial Keyboard Interface Pascal Procedures begins 36 pages

ISSUE NO. 11 (4/83) **BB I Expansions BB II Details** Dyna, RAM Disk Review Easier Reverse Video Cursor PlannerCalc Review KayPro Column begins 36 pages

ISSUE NO. 12 (6/83) 256K for BB I Bringing Up BB II dBase II Look at WordStar Double Sided Drives for BB I Packet Radio 5MHz Mod for KayPro 40 pages

ISSUE NO. 13 (8/83) CP/M Disk Directory More 256K for BB I Mini Front Panel Cheap Fast Modem Nevada Cobol Review **BB I Printer Interface** KayPro Reverse Video Mod 44 pages

ISSUE NO. 14 (10/83) **BB II Installation** The Perfect Terminal Interface to Electronic Typewriter BB I Video Size Video Jitter Fix Slicer Column starts KayPro Color Graphics Review 48 pages

ISSUE NO. 15 (12/83) Screen Dump Listing **Fixing Serial Ports Playing Adventure** SBASIC Column Begins Upgrading KayPro II to 4 Upgrading KayPro 4 to 8 48 pages

ISSUE NO. 16 (2/84) Xerox 820 Column Restarts **BB I Double Density** BB II 5"/8" Interface Fix KayPro ZCPR Patch Adding Joystick to Color Graphics

Recovering Text from Memory

CP/M 86 DISKS

DISK 86-1 — Disk Utilities D.CMD/A86, SD.CMD/A86, XDIR.CMD/A86: Three extended directory pro-grams. Each does it differently, so we included all three. FILE-EXT.CMD/A86: Disk status program with

good display format. PAGE. CMD/A86: A text paging program. Dis-

PAGE. CMD/AGE at me. PRINT.CMD/A86: File printing routine. Puts a header at the top of each page along with page number and file name

MUCHTEXT.CMD/A86: Counts words and

lines in a text file. ERQ,CMD/A86: Selective file erase program. Displays all selected files and then asks you one at a

time for a Y/N. INUSE.CMD/A86: Prints "In Use" on your terminal and asks for a password. It will not release the console until you enter the password. FINDBAD.CMD/A867. Finds and collects bad

sectors on a disk. If there are no bad sectors, information on the disk is unaltered.

Disk 86-2 — DU and Modem Programs DU-V75.CMD/A86/DOC: This is the popular disk utility from CP/M 80. It lets you read, write, and modify disk sector

MODEM4.CMD/A86: This is a modem program set up for the Slicer. This program includes a built-in help file. MODEM7SL.CMD/A86/DOC: No modem disk

would be complete without this standard. This is modem7 set up for the Slicer. It displays a menu when it is called.

Disk 86-3 — Small C C86.CMD: This is the original Small C compiler which appeared in D Dobbs Journal in 1980. It runs under CPM-86, and generates 8086 source for the

ASM86 assembler. C86. COM: This is the C86 compiler which runs under CPM-80. This 8080 program produces 8086

assembly language. **C86LIB.A86:** This is the C86 I/O library. **SMALLC86.DOC:** Documentation on Small C. C2777.C: Source of the C86 compiler.

Plus, there are a number of demonstration files and ENTAB (insert tabs in place of spaces) and DETAB (replace tabs with spaces) programs all written in Small C.

8" CP/M-86 Disk

\$15.00 each

BOOKS



52 pages


times when you need a break from monitor watching.

•MICRO CORNUCOPIA - P.O. Box 223 - Bend, Oregon - 97709 ·

FERGUSON ENGINEERING

817-640-0207

BIGBOARD-1 / 820-1 256K RAM EXPANSION MODULE



Very legible C size 820 schematics set of six drawings	. \$18.	.00
STD BUS connector for BBII	. \$12.	50
CRYDOM S312 OV switching SSR	.\$7.	50
Complete 820 Documentation Package	. \$15.	.00
820 CBIOS & Rom monitor source	. \$35.	.00
CP/M Primer (Xerox CP/M handbook)	. \$10.	00
8" Dual Drive Cable 17"	. \$30.	00
DB25S to 26 Pin Header. 18" Long	. \$15.	00
AMP Mini-Jumpers for easy configuration		
strapping	\$.	10



UNINTERRUPTABLE POWER SUPPLY \$**195**00 **UPS 5-200**

+ 5 V @ 8.5 AMPS, + 12 V @ 7.2 AMPS

-12V @ .5 AMP, +24V @ 2 AMPS [4A Pk]

This supply is designed to power entire computer systems with Winchester and floppy disk subsystems, as well as providing emergency battery backup capability. Designed to meet the needs of single-board Winchester systems. 24V 4.5 AH battery pack, BP-1\$65.00. FEATURES:

High Reliability

High Efficiency (75% TYP.) High Power - 200 Watts 25 Khz Switching Frequency (inaudible) Soft Start Built-In Quick-Response O.V.P. Cycle-By-Cycle Fold-Back Current Limiting Drop-Out Immunity for up to 250 Ms (without battery) Uninterruptable (with addition of BP-1 battery pack) 5 Output Voltages

FERGUSON ENGINEERING

817-640-0207 P.O. BOX 300085 ARLINGTON, TEXAS 76010


BIGBOARD-1 / 820-1 256K **RAM EXPANSION MODULE**

Now you can add a quarter-megabyte of RAM to your Bigboard-1 or 820-1 in a clean and efficient manner. This module can be used as a RAM disk, a spooler buffer, a disk cache or anything that requires more memory than the basic 64K. This module uses none of your precious I/O. Instead, it plugs in to five device sockets below the existing RAM array as a daughter board. It adds only i inch to the overall height of the computer board. The interface is accomplished with absolutely NO wires, cables or jumpers. The interconnect hardware, PAL and difficult-to-obtain discrete components are provided with the bare board, kit and tested versions. Only 7 TTL devices are required.

This memory array resides in the address space of the CPU as 16 blocks of 16K. Any 16K physical block can be mapped into any 16K logical block addressable by the CPU. A bipolar RAM mapper controls which 16K blocks the CPU has access to. The mapper is configured by easily-understood single-byte commands written to memory location OFFFFH. This extremely flexible architecture will accommodate a wide variety of applications, such as MPM, CPM+ and a host of highspeed data acquisition tasks. This RAM upgrade will work at 4 Mhz. This product comes with complete schematics and a full theory of operation with many programming examples. Assembly, installation and test procedures are thoroughly documented. PAL code is not available.

We have modified XDRIVE, a public-domain RAM disk software package, to run with the 820-256K. By the end of the 2nd quarter, we will have a CACHE BIOS melded with ZCPR that will give you nearly all the flexibility of CPM+ at a fraction of the cost.

BARE BOARD & DOCUMENTATION \$ 67.5	50
KIT W/O RAM95.0	ю
2.5 Mhz A&T (250 nS RAM)	ю
4.0 Mhz A&T (150 nS RAM)	ю
NEW MONITOR ROM SOURCE & XDRIVE SOFTWARE45.0	ю



Dual RS232 Serial I/O W/Current Loop Option on "A" Channel (both strappable as terminal or modem in RS232 Model

- 16 Programmable Baud Rates on each serial channel
- 32 Bits Buffered Parallel I/O Assignable on 4 Bit Boundaries, W/Strappable Handshake Polarity {2xZ80-PI0}
- 4 Channels of Counter-Timer. 4 Inputs, 3 Outputs
- Accommodates 16K Mix of Ram or Rom or EEPROM on 2K Boundaries in 2716 or 2016 or XICOR EEPROM
- 2.3" x 10" Sea of Holes Prototyping Area
- All I/O Fully Mode II Interrupt Compatible
- Watchdog Timer for Long-Term Unattended Operation

TERMS: VISA

MasterCard/VISA add 3%, money order, certified check, UPS cash COD. Allow 2 weeks for personal or company checks to clear. Shipping/handling extra. Texas order add 5% tax.





Tired of the slowness of BASIC? Find that the bugs in FORTRAN are bugging you? Step up to FORTH, the language that gives you total control over your computer! **UNIFORTH** is the only version of FORTH available either "captured" under an operating system (such as CP/M), or "standalone", acting as its own operating system. Our standalone versions are customized to your single board computer, providing serial and parallel port support, a real-time clock, formatting, fast disk copy, and disk access up to twice as fast as CP/M! All systems are FORTH-79, and include a video editor, macro assembler, debugger, decompiler, top-notch documentation, and much more. Write for our free brochure, or order direct from the special Micro-C reader prices listed below.

UNIFORTH Version

System	Integer	Floating	Multi-	Multi-	
		Point	Tasking	User	
Big Board	\$60	\$100	\$125	\$150	
Big Board II	80	125	150	200	
Slicer	100	150	200	250	
Any CPM-80	60	100			

Unified Software Systems

P.O. Box 2644, New Carrollton, MD 20784, 301/552-9590 DEC, VAX, PDP, RT-11, RSX-11 (TM) Digital Equipment Corp; CP/M (TM) Digital Research; MSDOS (TM) Microsoft; VIC-20 (TM) Commodore.

	CS PRO SAME I			,
		IAMIC R		
	256K	200 ns	\$59.90	
	64K	200 ns	5.87	
	64K	150 ns	5.99	
	64K	120 ns	7.50	
· .	16K	200 ns	1.15	
•		EPROM	• • • • • •	
	27128	300 ns	\$22.50	
	2764	250 ns	9.25	14 14
	2732	450 ns	8.50	
	2716	450 ns	3.60	
e jan	2532	450 ns	4.75	
		ATIC RA		
	6264P-15		\$42.00	
	6264LP-15		44.00	
	6116P-3	150 ns	6.56	
	3 01			
		ISA or UPS (ιP∞
	MICROPROC	New, Prim	e runo -	
	24.000 South Peo		8) 267-4961	
	BEGGS, OK. 744	21 (91	8) 267-4961	



P.O. BOX 223 BEND, OREGON 97709

FORWARDING POSTAGE GUARANTEED

BULK RATE U.S. POSTAGE PAID Bend, OR Permit No. 447