

## **NETWORK PRODUCTS**

# COMMUNICATIONS CONTROL PROGRAM VERSION 3 DIAGNOSTIC HANDBOOK

CDC® OPERATING SYSTEM: NOS 2

## **REVISION RECORD**

Revision	Description
A (11/10/76)	Original release at PSR level 439 for CCP 3.0, which supports NOS Version 1.
B (04/28/78)	Revised to support CCP Version 3.1.
C (12/01/78)	Revised at PSR level 480 to include miscellaneous technical changes.
D (06/22/79)	Revised at PSR level 487 for CCP Version 3.2.
E (10/09/80)	Revised at PSR level 528 for CCP Version 3.3.
F (01/07/83)	Revised at PSR level 580 for CCP Version 3.5, which runs under NOS Version 2.1.  Appendix A, Standard Character Sets, has been removed. Miscellaneous technical changes are included. This manual is no longer proprietary and no longer applies to NOS Version 1 systems. This is a complete reprint.

REVISION LETTERS I, O, Q, AND X ARE NOT USED

© COPYRIGHT CONTROL DATA CORPORATION 1976, 1978, 1979, 1980, 1983 All Rights Reserved Printed in the United States of America Address comments concerning this manual to:

CONTROL DATA CORPORATION
Publications and Graphics Division
P. 0. BOX 3492
SUNNYVALE, CALIFORNIA 94088-3492

or use Comment Sheet in the back of this manual

## LIST OF EFFECTIVE PAGES

New features, as well as changes, deletions, and additions to information in this manual are indicated by bars in the margins or by a dot near the page number if the entire page is affected. A bar by the page number indicates pagination rather than content has changed.

Page	Revision
Front Cover	-
Title Page	-
ii	F
iii/iv	F
v	F
vi	F
vii/viii	F
ix	F
1-1 thru 1-5	F
2-1 thru 2-35	F
3-1 thru 3-36	F
4-1 thru 4-25	F
A-1 thru A-6	F
B-1 thru B-6	F
C-1	F
D-1	F
E-1 thru E-5	F
Index-1 thru -3	F
Comment Sheet	F
Mailer	_
Back Cover	, <del>-</del>

iii/iv

## PREFACE

This handbook describes messages associated with Version 3.5 of the Communications Control Program (CCP 3.5) which is used with the CONTROL DATA® 255x Series Network Processor Unit (NPU). The CCP is the operating software for the NPU and provides front-end and remote message distribution functions for a CDC® 6000 or CYBER 170 host computer system. The CYBER host system operates under control of the NOS 2 operating system.

Two types of diagnostics are described: the in-line diagnostics, which are an integral part of CCP; and the optional on-line diagnostics, which are used for testing network lines. Off-line diagnostics are discussed in the appropriate hardware reference manuals.

These descriptions are designed to assist system operators and customer engineers (CEs) in isolating system faults. Any codes appearing within these messages are described and defined. Brief instructions on dump interpretation are also provided. To interpret the dump, either with or without a halt code, you will need a link edit listing of the CCP for this NPU.

Diagnostic information of the NPU includes:

Service messages to the host computer that are unrelated to an NPU halt; these in-line diagnostic messages include alarms, CE errors, and statistics (described in section 2)

Halt codes and dump interpretation information (described in section 3)

On-line diagnostic tests (described in section 4)

Off-line diagnostic tests (described in the NPU Hardware Reference Manual, MSMP Diagnostic Reference Manual, CYBER 18 Computer System Field Repair Guide, and in the ODS Reference Manual; other equipment-oriented hardware tests are described in the appropriate hardware maintenance manual for the individual equipment)

The CE error codes, statistics service messages, halt codes, and on-line diagnostic test responses are given in the form of Diagnostic Decision Logic Tables (DDLTs) which aid the troubleshooter in interpreting the message and isolating and correcting the hardware or software malfunction.

## RELATED MANUALS

Related material is contained in the publications listed below. Other manuals may be needed, such as the hardware, firmware, or emulator software reference manual for the devices serviced by a given program. Also, communication standards and device operating literature can be useful.

The NOS 2 Manual Abstracts is a pocket-sized manual that contains a brief description of the contents and intended audience of every manual available for NOS 2 and its product sets. The abstracts manual can help a particular reader determine which manuals are of greatest importance.

Another manual, the Software Publications Release History, gives the titles and revision levels of software manuals available for the Programming System Report (PSR) level of NOS 2 installed at your site.

Publication	Publication Number
AA132, AA133, AA153, DT120, FC402 CYBER 18 Computer Systems Central Processor Field Repair Guide	60475001
CYBER 170, CYBER 70 and 6000 Series Concurrent Maintenance Library Reference Manual	60454740
CYBER 18-25/30 Communication Multiplex Subsystem Hardware Reference/Maintenance Manual	96768610
Hardware Performance Analyzer (HPA) User Reference Manual	60459460
MSMP Diagnostic Reference Manual	96700000
Network Processor Unit Hardware Maintenance Manual (for 2551-1, 2551-2, and 2552-2)	60472000
Network Processor Unit Hardware Reference Manual (for 2551-1, 2551-2, and 2552-2)	60472800

## Publication

## Publication Number

NOS 2 Installation Handbook

60459320

NOS 2 Operator/Analyst Handbook

60459300

Operational Diagnostic System (ODS) Version 2 Reference Manual  $\,$ 

96768410

Order CDC manuals from Control Data Corporation, Literature and Distribution Services, 308 North Dale Street, St. Paul, Minnesota 55103.

This product is intended for use only as described in this document. Control Data cannot be responsible for the proper functioning of undescribed features or undefined parameters.

## **CONTENTS**

NOTATIONS	ix	Communications Lin	e Fault Isolation	4-22
			nd External Loopback	4-22
1. INTRODUCTION	1-1	External Data		4-22
1. INTRODUCTION			formation Required	4-22
Automatic In-Line Diagnostics	1-1		Loopback Tests	4-24
Alarm Messages	1-1		back Test Sequence	4-24
CE Error Messages	1-1		-	
Statistics Service Messages	1-1			
Halt Codes and Dumps	1-1			
Operator-Initiated On-Line Diagnostics	1-1	APPENDIXES		
Diagnostic Decision Logic Tables	1-2			
Assumptions	1-3	A Messages		A-1
Conditions	1-3	B Glossary		B-1
Responses, Actions, and Sequence	1-3	C Data Line Prob	_	C-1
		D CLA Replacemen	t	D-1
		E NOP Commands		E-1
2. ALARM, CE ERROR, AND STATISTICS				
SERVICE MESSAGES	2-1	ILIBEV		
	0 1	INDEX		
Alarm Messages	2-1			
CE Error Messages	2-2	FIGURES		
Statistics Service Messages	2-33	FIGURES		
		1-1 Flowchart Sh	owing Entry to Diagnostics	1-3
3. HALT CODES AND DUMP INTERPRETATION	3-1		r CE Error Code DDLT	2-3
J. HALI CODES AND DOME INTERFRETATION	J-1		or Statistics Messages DDLTs	2-33
Halt Codes	3-1		r Halt Codes DDLT	3-2
Hardware Malfunctions	3-1	3-2 Sample NPU D		3-34
Hardware or Software Problems	3-1		e Starting Address Format	3-36
2250 Dumps	3-34	4-1 CLA Status W		4-6
Interpreting a Dump Without a Halt Code	3-35		r On-Line Diagnostic DDLT	4-9
interpretary a surp manner a manner control			nts for Test Selection	4-23
4. ON-LINE DIAGNOSTIC TESTS	4-1			
NOP Console Operating Instructions	4-1	TABLES		
Disable a Trunk or a Line	4-1	·ADELS		
Request Connection to On-Line Diagnostics	4-1	1-1 Sample DDLT		1-2
On-Line Tests for CLAs and Modems	4-2	•	ering Diagnostic Mode	1-4
Start Testing of CLA Logic Using		2-1 CE Error Cod		2-4
Internal Loopback Test	4-2	2-2 Statistics S	ervice Messages DDLT	2-34
Stop Testing of CLA Logic Using		3-1 Halt Codes I	DLT	3-3
Internal Loopback Test	4-3	3-2 Address Tabl	e	3-35
Start Testing Lines Using External		4-1 Modem Classe	s	4-2
Loopback Test	4-7	4-2 Responses to	Start On-Line Diagnostic	
Stop Testing Lines Using External		Test Comma	nd From NOP Console	4-3
Loopback Test	4-7	4-3 On-Line Diag	nostic Test Error Codes	4–4
Start Testing Modem Drivers Using			Terminate Diagnostic Test	
Modem Loopback Test	4-8	Command Fr	om NOP Console	4-6
Stop Testing Modem Drivers Using		4-5 Connectors N	eeded to Run External	
Modem Loopback Test	4-8	Loopback T		4-7
Disconnect From On-Line Testing	4-8		e Switch Settings	4-7
Reenable a Trunk or a Line	4-8		nostics DDLT	4-11
Diagnostic Decision Logic Tables for			s and Loopback Tests	,
On-Line Diagnostics	4-8	Available		4-22

60471500 F vii/viii ●

## **NOTATIONS**

Throughout this manual, the following conventions are used to present statement formats, operator type-ins, and diagnostic messages:

UPPERCASE Uppercase letters indicate acronyms, words, or mnemonics either required by the network software as input, or produced as output.

lowercase Lowercase letters identify variables for which values are supplied by the network or terminal user, or by the network software as output.

Ellipsis indicates that omitted entities repeat the form and function of the entity last given.

- [] Square brackets enclose entities that are optional; if omission of any entity causes the use of a default entity, the default is underlined.
- Braces enclose entities from which one must be chosen.

Unless otherwise specified, all references to numbers are to decimal vaues and all references to bytes are to 8-bit bytes and all references to characters are to 7-bit ASCII-coded characters. Fields defined as unused should not be assumed to contain zeros.

This handbook gives you, the customer engineer or systems operator, the procedures needed to interpret two types of diagnostics for the 255x Series Network Processing Unit (NPU):

Automatic in-line diagnostics

Alarm messages sent to the network operator's console

CE error messages sent to the host computer

Halt codes interpreted with the associated  $255 \times dump$  in postmortem dumps

Operator-initiated on-line diagnostics

A third type of diagnostics, which is initiated off-line, is described in the NPU Hardware Maintenance Manual, the ODS 2 Reference Manual, and the MSMP Diagnostic Reference Manual.

Use the network processing unit operator's (NOP) terminal to help with diagnostic processing. A NOP uses the commands discussed in section 4 to help control trunks, logical links, lines, and terminals.

# AUTOMATIC IN-LINE DIAGNOSTICS

Alarm, CE error, and statistics service messages are types of in-line diagnostics. They are sometimes called service messages because they are sent directly to the host computer and are not related to an NPU halt.

#### **ALARM MESSAGES**

Alarm messages are generated by the Communications Control Program (CCP) in response to detected hardware error conditions. If the number of failures for a class of CE error messages exceeds a predetermined threshold, CCP sends an alarm message to the NOP console.

#### **CE ERROR MESSAGES**

CE error messages also are generated by CCP in response to detected hardware errors. If an individual failure occurs, CCP sends a CE error message to the host, where it is logged into the CE Error File.

#### STATISTICS SERVICE MESSAGES

Statistics service messages are generated periodically for individual NPUs, trunks, and lines. Like CE error messages, statistics service messages are sent upline to the host computer's engineering file where they are later processed by the Hardware Performance Analyzer (HPA).

#### HALT CODES AND DUMPS

The fourth type of in-line diagnostic, halt codes, is keyed to NPU hardware and software failures. If a fatal error stops the NPU, an NPU subroutine saves the cause of the halt in a halt code field. The information in the NPU memory, the microprocessor file l registers, and a microprocessor checksum are dumped into a host computer file. This file is processed by the Network Dump Analyzer (NDA) utility program in the host. The output from the file processing is available at either a line printer or a terminal.

Analyzing the halt code and its associated dump helps you to determine the cause of the NPU malfunction. If the halt code message is not generated, you still can analyze the failure by using information saved from the dump.

Halt codes and associated NPU dump interpretation are discussed in section 3.

#### NOTE

Other actions, such as the failure of the NPU to respond within a specified amount of time, are detected by the host; therefore, this type of diagnostic is not part of the CCP diagnostic software package. See the NOS 2 Operator/Analyst Handbook for a description of these messages, their delivery mode, and the actions you should take when the host receives such messages.

# OPERATOR-INITIATED ON-LINE DIAGNOSTICS

You can use on-line diagnostics to test network lines. You can request on-line diagnostics from the NOP console by entering commands that trigger individual tests. These tests are closed-loop tests for single network lines. The tests send and return eight characters of data on a closed-loop path. The returned characters are compared with those you sent to check for data quality along with other test functions.

Be sure either to disable or ask the Host Operator (HOP) or controlling NOP to disable the line you want to test. Then, in order of increasing complexity, you can test the line in several ways: by a CLA internal loop test, by a modem loop test, or by an external loop test. You will need a jumper plug to run the external loop test. For the first two tests, you will need the proper software commands. You may also need to position the test switches that are located on either remote or local equipment. The telephone company may ask you to do other line testing. You will find additional terminal tests described in the hardware manuals for the individual terminals.

On-line, operator-initiated diagnostics are discussed in section 4.

# DIAGNOSTIC DECISION LOGIC TABLES

To help you in trouble-shooting problems, most of the diagnostics in this handbook are described through Diagnostic Decision Logic Tables (DDLTs).

Use DDLTs for:

Starting the diagnostic mode

Analyzing errors detected by CE error messages

Analyzing errors indicated by statistics service messages

Analyzing halt codes and associated dumps

Performing operator-initiated on-line diagnos-

DDLTs help you to identify and isolate equipment malfunctions in replaceable assemblies. A DDLT aids you in analyzing a situation for specific conditions and then directs you to those actions that should correct the situation. The most likely action is listed first. Each DDLT has five sections: assumptions, conditions, responses, actions, and sequence of actions, as shown in table 1-1.

#### TABLE 1-1. SAMPLE DDLT

#### ASSUME

- 1. The communications Control Program is loaded, initialized and operating, at least to the idle state.
- 2. MLIA is working since the system has not halted.
- 3. After each corrective action, the test should be retried.
- 4. The operator is familiar with the DDLT format.
- 5. The operator is using the operating instructions given on the previous pages.

	CONDITIONS				
	CONDITIONS	1	2	3	4
1.	Look at the eighth byte of data in the diagnostic test response at the console. This is the response code.				
	Is the response code AB thru DB, or DF?	Y	Y	Y	N
2.	Have you already successfully tested the CLA in the external loopback mode using an external test connector? (If the CLA type does not allow an external loopback test, have you run the internal loopback mode successfully?)	¥	¥	N	_
3.	Have you already run the modem loopback mode test on this communications line with the local modem looped back towards the CLA successfully?	Y	N	-	_
	ACTIONS				
1.	Replace the local modem.	1	4	•	-
2.	Have local telephone central office check the local telephone line.	2	5	-	_
3.	Run the CLA loopback external mode test.		-	X	_
4.	You have misinterpreted the directions. Return to sheet 6 and run the DDLT again.	-	-	-	х
5.	Run the modem loopback mode test on this communications line with the local modem looped back towards the CLA.	-	1	-	_
6.	If the local modem has no loopback, replace the modem cable.	-	2	-	_
7.	If the local modem has no loopback, replace the CLA.	-	3	-	-

#### **ASSUMPTIONS**

The upper section of a DDLT contains the prerequisites for the specific tests you should do. A DDLT is valid only if all assumptions are true.

#### CONDITIONS

The center left section of the DDLT contains the conditions or tests you should make. Each condition asks a question to which you can answer yes or no.

## RESPONSES, ACTIONS, AND SEQUENCE

The center right section of the DDLT contains the response to the question asked in the conditions section. Each condition, which is asked in question form, can be answered with a yes (Y) or a no (N). The example shown in table 1-1 has four unique responses, numbered 1 to 4, from left to right. The shaded area in the example shows the conditions that define response 3.

The first condition limits the range of the response. If the response is yes, go to the next condition. In table 1-1, the response is no, which indicates that the appropriate test has not been run. Note that the next condition cannot be checked. By reading down column 3, you can see that only one action (marked by an X) is appropriate. The hypothetical operator in this example should run the CLA external loopback test. This test will give its own response code, which will take the operator back through the DDLT again.

Note that if the response to both the first two conditions had been yes, the operator would have taken either the action in column 1 (third condition = yes) or column 2 (third condition = no). In either case, more than one action could have been taken. Each action would have been done in the indicated sequence until the appropriate action fixed the problem, or until all suggested actions were tried.

The DDLTs assume that your inputs are entered correctly. Any incorrect entry may cause the DDLT to direct you to an incorrect action. If you have any doubts about the accuracy of your entry, repeat the sequence of DDLT steps that led up to an action before going further.

Figure 1-1 is a flowchart that shows how diagnostic mode is entered.

Table 1-2 shows the information presented in figure 1-1 in DDLT format.




Figure 1-1. Flowchart Showing Entry to Diagnostics

## ASSUME

1. Operator is familiar with DDLT format.

		т—								
	CONDITIONS		RESPONSES							
		1	2	3	4	5	6			
1.	Are you responding to a halt message?	Y	N	N	N	N	N			
2.	re you responding to a dump?				N	N	N			
3.	Are you responding to a terminal user's telephone call stating that the line is not working, or to a network system operator's report that a line is bad?	-	_	Y	N	N	N			
4.	Are you reponding to a HPA (Hardware Performance Analyzer) report?	-	-	-	Y	N	N			
5.	Are you responding to an alarm message from the NPU?	-	-	-	-	-	Y			
	ACTIONS				SEQUENCE					
1.	Go to sheet 2.	х	-	-	_	-	-			
2.	See section 3 for halt codes and dump interpretation.	-	х	-	-	-	-			
3.	See section 4 for on-line diagnostic tests. Run diagnostics on the specified line(s) following the communications line fault isolation techniques described at the end of section 4.	-	_	Х	-	_	_			
4.	Go to sheet 3.	-	-	-	Х	-	_			
5.	Pick the condition most similar to one of the four listed conditions. Then take the action indicated.	_	-	-	-	х	_			
6.	Run HPA in the host to obtain more information on the malfunctioning line, MLIA, or coupler. Then go to sheet 3.	-	-	-	-	-	х			

TABLE 1-2. DDLT FOR ENTERING DIAGNOSTIC MODE (Sheet 2 of 3)

	CONDITIONS		1	RESP	onses	5	
	CONDITIONS	1	2	3	4	5	6
1.	Are you responding to a system halt?	Y	N	N	N	N	N
2.	Are you responding to a line-related problem?	-	Y	N	N	N	N
3.	Are you responding to a service message?			Y	N	N	N
4.	4. Look at the PFC byte of the service message. Is the PFC byte = OA and the SFC byte = 00? (This indicates a CE error message.)					N	N
5.	. Is the PFC byte = OA and the SFC byte = O1? (This indicates an alarm message.)				Y	N	N
6.	6. Is the PFC byte = 07? (This indicates a statistics message.)					Y	N
	ACTIONS		SEQUENCE				
1.	Take an NPU dump and go to section 3 (Halt Code DDLTs).	х	_	Ŀ			
2.	• See section 4 for on-line diagnostic tests. Run diagnostics on the specified line(s).		х	_			
3.	See section 2 for CE error messages.	<u>_</u>	<u>_</u>	х			
4.	Discard the message and see section 2 for alarm messages.	_	<u>_</u>	_	х		
5.	See section 2 for statistics messages.	<u>_</u>	_	_	-	х	Ŀ
6.			_	_	_	-	х

TABLE 1-2. DDLT FOR ENTERING DIAGNOSTIC MODE (Sheet 3 of 3)

	govp.rm.rovg	RESPONSES				
	CONDITIONS	1	2	3		
1.	Are you responding to a CE error message?	Y	N	N		
2.	Are you responding to a statistics message?	-	Y	N		
	ACTIONS			CE		
1.	See section 2 for CE error messages.	X	-	1		
2.	See section 2 for statisctics messages.	-	х	1		
3.	On HPA reports, only CE error messages and statistics messages concern the CCP system. Ignore other types of message.	_	-	x		

This section discusses how to interpret service messages and gives suggested Customer Engineering (CE) actions for:

Alarm messages, which indicate that a device has caused more CE error messages to be generated than is consistent with reliable operation. When this threshold number is exceeded, an alarm is sent to the network processing unit operator's (NOP) console.

CE error messages, which detail an equipment failure and are sent to the host's engineering file. A CE error message is created for every detected hardware-related abnormality, including all network processing unit-related hardware, such as the coupler, Multiplex Loop Interface Adapters (MLIAs), and Communication Line Adapters (CLAs); and all connected hardware, such as modems, lines, and terminals.

Statistics service messages, which give a history of Network Processing Unit (NPU) or line functioning. They are sent upline to the host's engineering file. A statistics service message is generated periodically. After one statistics service message is generated for each NPU or line, the cycle starts again. Statistics service messages also are generated when any counter holding statistics information overflows. A line statistics service message is generated when a line is disconnected or deleted.

## **ALARM MESSAGES**

An alarm message is sent to the NOP because the abnormality it reports is serious enough to degrade network performance. Do not ignore alarm messages. Follow the actions indicated, such as running the Hardware Performance Analyzer (HPA). Use the information displayed by the HPA to do the appropriate CE or statistics diagnostic tests.

The HPA does not purge CE error and statistics information automatically from the host files when it is run. See the CYBER 170, CYBER 70, and 6000 Series Concurrent Maintenance Library reference manual for a description of how the HPA works.

The format of the alarm message in the network (each numeric byte contains two hexadecimal digits) is:

Link header		SN		P/RES/ BT=04			TEXT
----------------	--	----	--	-----------------	--	--	------

DN Destination node - Coupler of supervisory host

SN Source node - NPU

CN Connection number - 00 for service messages

P/RES Unused

BT Block type - 4 is CMD block

PFC Primary function code - OA

alarm message

SFC Secondary function code - 01

TEXT One of three formats as described in appendix A.

MAINTENANCE ALARM PORT xx, ERROR=ec
MAINTENANCE ALARM MLIA, ERROR=ec
MAINTENANCE ALARM COUPLER n,ERROR=ec
xx is a hexadecimal number

## **CE ERROR MESSAGES**

The creation of CE error report messages is separate from, and in addition to, statistics accumulated in the NPU and periodically suppplied to the host.

An error message counter is incremented each time an error message is generated. This prevents swamping the NPU or host with error messages when an oscillatory condition arises. When the counter reaches a pre-established threshold, the error is discarded rather than recorded. The counter is periodically reset to zero based on another counter whose threshold is also a pre-established parameter.

The format for CE error messages (each byte contains two hexadecimal digits or one ASCII character) is:

Link DN SN header =00	CN P/RES/ BT=04		EC TEXT
-----------------------	--------------------	--	---------

DN Destination node

SN Source node

CN Connection number - 00 for service

messages

P/RES Unused

BT Block type - 4 is CMD block

PFC Primary function code - 0A

CE error message

SFC Secondary function code - 01

EC Error codes (described in appendix A)

TEXT Error code dependent (1 to 8 bytes long as described in appendix A)

These CE error messages are divided into 6 categories:

- Modem signal messages (error codes 02 through 03 and 0C)
- CLA messages (error codes 04 through 09 and 0D through 10)
- 3. MLIA messages (error code 11)
- 4. Coupler messages (error codes 20 through 29)
- 5. Real-time clock messages (error code 18)
- TIP-detected terminal errors (error codes OA, OB, 2A through 2D, and 30 through 32)

Figure 2-1 is a flowchart that summarizes the DDLT procedure for CE error messages.

Table 2-1 lists the CE error messages in DDLT form. The DDLTs suggest actions you should taken when a certain messages appears.

All references to the off-line diagnostics in the CE error messages DDLTs refer to diagnostics listed and described in the NPU Hardware maintenance manual, the ODS manual, and the MSMP Diagnostic reference manual. These books give you procedures for running those diagnostics and supply hints on using them to isolate equipment malfunctions.

CE error messages and text definitions are described in appendix A.




Figure 2-1. Flowchart for CE Error Code DDLT

## CE Error Codes Index

## ASSUME

- 1. Operator is familiar with DDLT format.
- 2. CE error message has error code.

CONDITIONS		RESPONSES  1 2 3 4 5 6								
1. Look at the error code byte of the CE error message to find the error code (byte follows SFC byte).	+	2	3	4	3					
Is the error code = 01?	N	N	N	N	N	Y				
2. Is the error code = 02?	N	N	N	N	Y	-				
3. Is the error code = 03?	N	N	N	Y	-	-				
4. Is the error code = 04?	N	N	Y	_	-	-				
5. Is the error code = 05?	N	Y	-	-	-	-				
ACTIONS		•	SEQ	JENCI	E					
1. Go to sheet 2.	х	-	-	-	-	-				
2. Go to sheet 11.	-	х	-	-	-	-				
3. Go to sheet 12.	_	-	Х	,	-	-				
4. Go to sheet 13.	-	-	-	Х	-	-				
5. Go to sheet 14.	-	-	-	-	х	-				
6. Go to sheet 20.	-	_	-	,	-	х				

TABLE 2-1. CE ERROR CODES DDLT (Sheet 2 of 36)

CE Error Codes Index ASSUME						
		I	RESPO	ONSE	3	
CONDITIONS	1	2	3	4	5	6
1. Is the error code = 06?	N	N	N	N	N	Y
2. Is the error code = 07?	N	N	N	N	Y	-
3. Is the error code = 08?	N,	N	N	Y	-	-
4. Is the error code = 09?	N	N	Y	-	-	-
5. Is the error code = 0A?	N	Y	-	-	-	-
ACTIONS		SEQUENCE				
1. Go to sheet 3.	х	1	-	-	-	-
2. Go to sheet 15.	-	Х	-	-	_	Ŀ
3. Go to sheet 16.	-	-	х	-	-	Ŀ
4. Go to sheet 16.	_	-	_	х	_	_
5. Go to sheet 12.	-	-	_	-	х	
6. Go to sheet 17.	-	_	-	-	-	)

	CE Error Codes Index											
	ASSUME											
1	CONDITIONS	RESPONSES										
		1	2	3	4	5	6					
	1. Is the error code = OB?	N	N	N	N	N	Y					
	2. Is the error code = OC?	N	N	N	N	Y	-					
	<pre>3. Is the error code = OD?</pre>	N	N	N	Y	-	-					
	4. Is the error code = OE?	N N Y			_							
	5. Is the error code = OF?	N	Y	-	-	-	-					
	ACTIONS			SEQ	UENC	E						
	1. Go to sheet 4.	х	-	-	-	-						
	2. Go to sheet 18.	-	Х	-	-	-	-					
	3. Go to sheet 20.	_	-	х	-	-	-					
	4. Go to sheet 19.	-	-	-	х	-	-					
	5. Go to sheet 29.	x				-						
<b>ا</b> ا	6. Go to sheet 15.	-	-	-	-	-	х					

CE Error Co	odes Index	ASSUME							
					]	RESP	ONSE	s	
		CONDITIONS		1	2	3	4	5	6
l. Is the	error code = 10?			N	N	N	N	N	Y
2. Is the	error code = 11?			N	N	N	N	Y	_
3. Is the	error code = 12?			N	N	N	Y	-	_
4. Is the	error code = 13?			N	N	Y	_	<b>-</b>	_
5. Is the	error code = 14?			N	Y		-	-	-
		ACTIONS				SEQ	UENC	E	
l. Go to a	sheet 5.	<u>, , , , , , , , , , , , , , , , , , , </u>		х	-	-	-	_	-
2. Go to s	sheet 20.				Х	Х	Х	_	_
Go to s	sheet 21.			-	-	-	_	Х	_
4. Go to s	sheet 18.			-	-	-	-		х

TABLE 2-1. CE ERROR CODES DDLT (Sheet 5 of 36)

			ASSUME							
						1	RESPO	ONSE	5	
		CONDITIONS			1	2	3	4	5	6
1.	Is the error code = 15?				N	N	N	N	N	Y
2.	Is the error code = 16?				N	N	N	N	Y	
3.	Is the error code = 17?				N	N	N	Y	_	-
4.	Is the error code = 18?				N	N	Y	_	-	_
5.	Is the error code = 19?				N	Y	-	-	-	-
		ACTIONS		·	SEQUENCE					
1.	Go to sheet 6.				х	-	-	-	_	-
2.	Go to sheet 20.				_	х	Х	х	х	,

	CE Error Codes Index										
	ASSUME										
	CONDITIONS			RESPONSES							
-		1	2	3	4	5	6				
-	1. Is the error code = 1A?	N	N	N	N	N	Y				
	2. Is the error code = 1B?	N	N	N	N	Y	-				
	3. Is the error code = 1C?	N	N	N	Y	1	-				
	4. Is the error code = 1D?	N	N	Y	-	-					
	5. Is the error code = 1E?	N	Y	-	-	-	-				
	ACTIONS	SEQUENCE									
-	1. Go to sheet 7.	х	-	_	-	-	口				
	2. Go to sheet 20.	-	х	х	х	х	х				

TABLE 2-1. CE ERROR CODES DDLT (Sheet 7 of 36)

CE Error Codes Index							
ASSUME							
CONDITIONS		]	RESP	ONSE	s		
CONDITIONS	1	2	3	4	5	6	
1. Is the error code = 1F?	N	N	N	N	N	Y	
2. Is the error code = 20?	N	N	N	N	Y	-	
3. Is the error code = 21?	N	N	N	Y	-	-	
4. Is the error code = 22?	N	N	Y	-	-	-	
5. Is the error code = 23?	N	Y	-	-	-	-	
ACTIONS	SEQUENCE						
1. Go to sheet 8.	х	-	-	-	-	-	
2. Go to sheet 24.	-	х	-	-	-	-	
3. Go to sheet 23.	-	-	-	Х	-	-	
4. Go to sheet 22.	-	-	-	-	Х	-	
5. Go to sheet 20.	-					х	

#### CE Error Codes Index **ASSUME** RESPONSES CONDITIONS 4 1 Y N N N N 1. Is the error code = 24? N N Y 2. Is the error code = 25? Y 3. Is the error code = 26? N N N N N Y 4. Is the error code = 27? 5. Is the error code = 28? N SEQUENCE ACTIONS X 1. Go to sheet 9. 2. Go to sheet 27. X \_ X 3. Go to sheet 26. X X 4. Go to sheet 20.

5. Go to sheet 25.

CE Error Codes Index ASSUME						
ADSUM						
CONDITIONS			RESP	onse	s	
	- 1	2	3	4	5	6
1. Is the error code = 29?	N	N	N	N	N	Y
2. Is the error code = 2A?	N	N	N	N	Y	-
3. Is the error code = 2B or 2C?	N	N	N	Y	-	-
4. Is the error code = 2D?	N	N	Y	_	-	-
5. Is the error code = 2E?	N	Y	-	-	-	-
ACTIONS	SEQUENCE					
1. Go to sheet 10.	Х	-	-	-	-	
2. Go to sheet 20.	-	х	-	-	-	-
3. Go to sheet 32.	-	-	х	-	-	
4. Go to sheet 31.	-	-	-	х	-	
5. Go to sheet 30.	-	-	_	1	х	
6. Go to sheet 28.	-	-	-	-	-	х

## CE Error Codes Index

#### ASSUME

ASSUME				· ·	4		
		RESPONSES					
CONDITIONS	1	2	3	4	5	6	7
1. Is the error code = 2F?	N	N	N	N	N	N	Y
2. Is the error code = 30, 31, or 32?	N	N	N	N	N	Y	].
3. Is the error code = 33?	N	N	N	N	Y	-	
4. Is the error code = 34 or 35?	N	N	N	Y	-	-	_]
5. Is the error code = 36?	N	N	Y		-	-	_]
6. Is the error code = or greater than 37?	N	Y	-	-	-	-	-
ACTIONS		SEQUENCE					
1. You have misinterpreted an instruction. Go back to sheet 1 and try again.	х	-	-	-	-	-	-
2. Go to sheet 20.	_	Х	-	-	-	_	
3. Go to sheet 36.	-	_ ,	х	-	-	-	_
4. Go to sheet 35.	-	-	-	Х	-	-	_]
5. Go to sheet 34.	_	-	-	1.	Х	-	_
6. Go to sheet 33.	-	-	-	-	-	х	_
7. Go to sheet 20.	-	-	-	-	-	-	х

## CE Error Message O5 - CLA Address Error

## ASSUME

The worklist processor found a worklist entry with the CLA address equal to zero, or greater than the maximum allowed address (build time parameter). Most likely a bit of the CLA address field is erroneous.

	CONDITIONS	RESP	ONSES
	CONDITIONS  1. Has CE error message 05 been occurring more than 12 times a day?  ACTIONS  1. Run ODS load check and mainframe diagnostics.  2. Run MSMP 6000 Coupler diagnostics. Also run either TFF on native mode 255Xs or TFE on -100 255Xs.  3. Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).  4. Run MSMP MLIA diagnostics.  5. If other CE error messages are outstanding, follow DDLTs for those messages.  6. Call CE or analyst as appropriate.		
1.	Has CE error message 05 been occurring more than 12 times a day?	Y	N
-	ACTIONS	SEQU	ENCE
1.	Run ODS load check and mainframe diagnostics.	1	-
2.	The state of the s		
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	-
4.	Run MSMP MLIA diagnostics.	4	-
5.	If other CE error messages are outstanding, follow DDLTs for those messages.	5	-
6.	Call CE or analyst as appropriate.	6	-
7.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 05 should not be a matter for concern. However, the test operator can perform the six steps listed above at his discretion.	-	х

## CE Error Messages 04 and 07 - Unsolicited ODD or Input

## ASSUME

An unsolicited output data demand (ODD) or unsolicited input was detected by the worklist processor. This is usually caused 1) by connecting and activating a CLA with an address of another active CLA, or 2) by connecting and activating a CLA which happens to give an ODD or an input before the system has enabled it, or 3) by a defective CLA. (Error message 04 is caused by an unsolicited ODD; error message 07 is caused by an unsolicited input.)

	The state of the s				
		RE	SPONS	SES	
	CONDITIONS	1	2	3	
1.	Has CE error message 04 or 07 been occurring more than 12 times a day?	Y	Y	N	
2.	Have some CLAs been plugged in during this time?	Y	N	-	
	ACTIONS	SE	QUEN	CE	
1.	Check the addresses on the CLA handles for a duplicated address or for a switch set between two numbers. (The byte of the CE error message following the error code contains the CLA address.)	_	1	-	
2.	Run ODS load check and mainframe diagnostics.		2	_	
3.	Run MSMP MLIA diagnostics.	_	3	_	
4.	Run MSMP 6000 Coupler diagnostics. Also run either TFF on native mode 255%s or TFE on -100 255%s.	_	4	-	
5.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	_	5	_	
6.	If other CE error messages are outstanding, follow DDLTs for those messages.	_	6	_	
7.	Call CE or analyst as appropriate.	-	7	_	
8.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 04 or 07 should not be a matter for concern. However, the test operator can perform the seven steps listed above at his discretion.	x	_	х	

#### CE Error Message 03 - Abnormal DCD

#### ASSUME

Abnormal operation of the data carrier detect (DCD) signal was detected by the CLA status handler. Failure of the DCD in the middle of input or a 10-second timeout of DCD is abnormal. This error message indicates noise on a transmission line.

	CONDITIONS		RESPONSES	
			1	2
1.	The byte of the CE error message following the error code contains the CLA address. one CLA have more than 12 CE error messages 03 occurring during one hour?	Does	Y	N
	ACTIONS		SEQUI	3NCE
1.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the intermittent CLA line.		x	_
2.	Some noise on a transmission line is to be expected. Unless the customer has reason believe that some serious fault exists, an occasional CE error message 03 should not a matter of concern. However, the test operator can perform the above step at his discretion.	to be	_	x

## TABLE 2-1. CE ERROR CODES DDLT (Sheet 14 of 36)

## CE Error Message 02 - Abnormal DSR or CTS

## ASSUME

Abnormal operation of the data set ready (DSR) or clear to send (CTS) modem signals was detected by the CLA status handler. An invalid sequence of modem signal changes or the normal disconnect sequence on some types of line protocols will cause this error message.

#### NOTE

This message occurs in the normal sequence of disconnecting on some lines. Do not treat this as an error message.

## CONDITIONS

None.

#### ACTIONS

None.

## CE Error Messages OA and OB - TIP Event Receiver Timeout

## ASSUME

CE error message OA occurs when the TIP event receiver times out an output data demand (ODD) during the transmission of a message.

CE error message OB occurs when the TIP event receiver times out because the data carrier detect (DCD) signal was missing for a period of time longer than the threshold value. These errors can be caused by a noisy transmission line, a bad modem, or a bad CLA.

	CONDITIONS	RESP	ONSES 2
1.	The byte of the CE error message following the error code contains the CLA address. Is the CLA receiving more than 6 CE error messages OA or OB during one hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the intermittent CLA line.	X	_
2.	Some noise on a transmission line is to be expected. Unless the customer has reason to believe that some serious fault exists, an occasional CE error message OA or OB should not be a matter of concern. However, the test operator can perform the above step at his discretion.	· <u>-</u>	x

## CE Error Messages 08 and 09 - Mux Loop Error

## ASSUME

The CLA status handler has detected a loop error. This is usually caused by noise on the multiplexer loop. CE error message 08 is an input loop error (ILE); CE error message 09 is an output loop error (OLE).

	CONDITIONS	RESE	ONSES
	CONDITIONS  IS CE error message 08 or 09 occurred more than three times in one-half hour on the same ne number?  ACTIONS  Sin on-line diagnostics on the CLA specified by that line number using the CLA internal opback test.  place the primary loop multiplexer card in the loop multiplexer cage containing the ecified CLA.  place MLIA card 1 (slot D on core memory machines, slot E on MOS memory machines).  place MLIA card 2 (slot E on core memory machines, slot F on MOS memory machines).  place MLIA card 3 (slot F on core memory machines, slot G on MOS memory machines).  place loop multiplexer cables one at a time.  11 CE or analyst as appropriate.  less the customer has reason to believe some serious fault exists, an occasional CE for message 08 or 09 should not be a matter for concern. However, the test operator	1	2
1.	Has CE error message 08 or 09 occurred more than three times in one-half hour on the same line number?	Y	N
	ACTIONS	SEQU	ENCE
1.	Run on-line diagnostics on the CLA specified by that line number using the CLA internal loopback test.	1	-
2.	Replace the primary loop multiplexer card in the loop multiplexer cage containing the specified CLA.	2	_
3.	Replace MLIA card 1 (slot D on core memory machines, slot E on MOS memory machines).	3	-
4.	Replace MLIA card 2 (slot E on core memory machines, slot F on MOS memory machines).	4	-
5.	Replace MLIA card 3 (slot F on core memory machines, slot G on MOS memory machines).	5	-
6.	Replace loop multiplexer cables one at a time.	6	-
7.	Call CE or analyst as appropriate.	7	-
8.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 08 or 09 should not be a matter for concern. However, the test operator can perform the seven steps listed above at his discretion.	-	х

## CE Error Message 06 - Illegal Mux Loop Format

#### ASSUME

The worklist processor detected an illegal loop cell format in the CIB. This is usually caused by a bad MLIA or a loop multiplexer problem. The only formats accepted are: 1) a CLA address cell followed by a data cell with an end-of-line frame flag, 2) a CLA address cell followed by two supervision cells (the second supervision cell has the end-of-line frame flag), 3) a CLA address cell followed by a data cell and two supervision cells (the second supervision cell has the end-of-line frame flag).

		,			
	2017-77-019	]	RESP	ONSE	S
	CONDITIONS	1	2	3	4
1.	Has CE error message 06 occurred more than three times in one-half hour?	Y	Y	Y	N
2.	The byte of the CE error message following the error code contains the CLA address. Did the CE error message occur for one CLA address?	Y	Y	N	_
3.	Did the CE error message contain CLA addresses of CLAs that reside in one loop multiplexer cage?	-	Y	N	_
	ACTIONS		SEQ	UENC	Е
1.	Replace the primary loop multiplexer card in the loop multiplexer cage containing the CLAs whose addresses were in the error messages.	2	1	-	_
2.	Replace MLIA card 1 (slot D on core memory machines, slot E on MOS memory machines).	_	2	1	_
3.	Replace MLIA card 2 (slot E on core memory machines, slot F on MOS memory machines).		3	2	_
4.	Replace MLIA card 3 (slot F on core memory machines, slot G on MOS memory machines).	_	4	3	-
5.	Replace the CLA with the address indicated in the CE error message.	1	-	_	_
6.	Call CE or analyst as appropriate.	3	5	4	_
7.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 06 should not be a matter for concern. However, the test operator can perform the six steps listed above at his discretion.	-	-	_	x

## CE Error Messages OF and 10 - NCNA/Data Transfer Overrun Error

## ASSUME

CE error message OF occurs when the CLA status handler has detected a next character not available (NCNA) condition. This is caused by a synchronous CLA not having the next character for output in time to keep the output data stream in synchronization.

CE error message 10 occurs when the CLA status handler has detected a data transfer overrun condition. This is caused by a CLA receiving a second character before the loop multiplexer has accepted the first character. Either problem may occur due to system overloading or due to a bad CLA.

CONDITIONS	RESPONSES			
		1	2	3
1.	Has CE error message OF or 10 occurred more than three times in one-half hour?	Y	Y	N
2.	The byte of the CE error message following the error code contains the CLA address. Each loop multiplexer card cage is organized so the left-most card slot has highest priority and each succeeding slot to the right has lower priority than its neighbor to the left. On the CLA card, CLA1 has a higher priority than CLA2. If the system has more than one loop multiplexer, the loop multiplexer with the highest priority has its upper cable connected to the MLIA. Check the CLAs priority placement. Are the CLAs in the proper priority placement according to line speed?	Y	N	-
	ACTIONS	SE	QUEN	CE
1.	Replace the CLA with the address indicated in the CE error message.	1	-	-
2.	Place the CLAs in the proper priority positions according to line speed.	-	1	-
3.	Call CE or analyst as appropriate.	2	2	-
4.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message OF or 10 should not be a matter for concern. However, the test operator can perform the three steps listed above at his discretion.	_	_	х

## CE Error Message OD - Excessive CLA Status Messages

#### ASSUME

The CLA status handler detected more than 128 status messages from a CLA within one-half second. The byte of the CE error message following the error code contains the CLA line number. This flood of status messages is usually due to very noisy line conditions; however, it may also be caused by a bad CLA or a bad modem.

#### CONDITIONS

None.

#### ACTIONS

1. Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the intermittent CLA line.

## TABLE 2-1. CE ERROR CODES DDLT (Sheet 20 of 36)

## CE Error Messages 00, 01, 0E, 12 thru 1F, 22, 25, 26, 2E, 2F, and 37 or higher - Illegal

#### ASSUME

These are not valid CE error message codes. It is likely that the CE error code byte part of the message is garbled.

#### CONDITIONS

None.

#### ACTIONS

None.

#### NOTE

These CE error messages should not appear on the Hardware Performance Analyzer reports.

#### CE Error Message 11 - MLIA Error

#### ASSUME

The MLIA interrupt handler has detected MLIA error status. This status may be caused by a faulty MLIA, faulty loop cables, or a faulty loop multiplexer.

CONDITIONS	RESPONSES		
	CONDITIONS	1	2
1.	Has this CE error message occurred more than three times within one-half hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	Run MSMP MST041 diagnostics.	х	-
2.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 11 should not be a matter for concern. However, the test operator can perform the step listed above at his discretion.	_	х

#### TABLE 2-1. CE ERROR CODES DDLT (Sheet 22 of 36)

## CE Error Message 20 - Deadman Timeout

#### ASSUME

The host interface package (HIP) software has detected a deadman timeout error. Error detection occurs in HIP procedure PTSTART. CE error message 20 does not necessarily indicate a failure; it can merely mean that the host failed to communicate with the 2550 within the amount of time specified by the CCP global constant ADEADTO. When the error is detected, the HIP sends a host computer down message to all the interactive terminals in the system. The two bytes of the CE error message following the error code contain the last state of the HIP.

#### CONDITIONS

CE error message 20 normally is not an indication of a 2550 failure. The message occurs during normal operation if the host is locked out for ADEADTO time, due to higher priority local batch activity. During this period the host computer cannot communicate with the 2550 to prevent the deadman timer from expiring.

#### ACTIONS

None.

## CE Error Message 21 - Spurious Coupler Interrupt

#### ASSUME

The coupler spurious interrupt condition is detected by the host interface package (HIP) software; the error detection occurs in the procedure PTINTPROC. A spurious coupler interrupt occurs when a coupler status following an interrupt does not contain one of the following: 1) a chain address zero, 2) a hardware timeout, 3) transfer terminated by the PPU, 4) transmission complete, 5) parity error, or 6) protect fault. The error message shows the actual coupler status (look at the two bytes following the error code).

	CONDITATIONS	RESP	onses
	CONDITIONS	1	2
1.	Has CE error message 21 occurred more than three times within one-half hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	During the next PM period, run off-line MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics (depending on which coupler is present). Also run either TFF on native mode 255Xs or TFE on -100 255Xs.	1	_
2.	Replace the coupler I/O card (slot C for the 6000 Coupler, slot AA for the 6000 Expansion Coupler).	2	_
3.	Replace the coupler DMA card (slot D for the 6000 Coupler, slot A for the 6000 Expansion Coupler).	3	_
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	4	_
5.	Replace the status mode interrupt card (slot L).	5	
6.	Replace the I/O-TTY card (slot K).	6	_
7.	If other CE error messages are outstanding, follow DDLTs for those messages.	7	_
8.	Call CE or analyst as appropriate.	8	-
9.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 21 should not be a matter for concern. However, the test operator can perform the eight steps listed above at his discretion.	_	х

## CE Error Message 23 - Coupler Hardware Timeout on Input

#### ASSUME

The coupler hardware timeout condition is detected by the host interface package (HIP) software; the error detection occurs in procedure PTINTPROC. If the timeout occurs when the HIP is expecting input data (traffic from the 2550 to the host), the PTINTPROC procedure is in state 2 (BZSTATE = AOPT 2) during the detection of the error. If the host to 2550 channel is active longer than three seconds, the coupler deactivates the channel, sets bits 10 (timeout) and 15 (alarm) in the coupler status, and causes an interrupt. The CE error message contains the actual coupler status (look at the two bytes following the error code).

	CONDITIONS	RESP	ONSES
	CONDITIONS	1	2
1.	Has CE error message 23 occurred more than three times within one-half hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	During the next PM period, run off-line MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics (depending on which coupler is present). Also run either TFF on native mode 255Xs or TFE on -100 255Xs.	1	_
2.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	2	-
3.	Replace the coupler I/O card (slot C for the $6000$ Coupler, slot AA for the $6000$ Expansion Coupler).	3	-
4.	Replace the coupler DMA card (slot D for the 6000 Coupler, slot A for the 6000 Expansion Coupler).	4	_
5.	If other CE error messages are outstanding, follow DDLTs for those messages.	5	-
6.	Call CE or analyst as appropriate.	6	-
7.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 23 should not be a matter for concern. However, the test operator can perform the six steps listed above at his discretion.	-	х

# CE Error Message 24 - Input Data Transfer Terminated by PPU

#### ASSUME

The coupler transfer terminated by PPU condition is detected by the host interface package (HIP) software. The error detection occurs in procedure PTINPRCOC. If the HIP is expecting input (traffic from the 2550 to the host) when the transfer terminated by PPU occurs, PTINPRCOC is in state 2 (BZSTATE = AOPT2) during the detection of the error. If the host deactivates the data channel before a data transfer is complete, bit 1 of the coupler status word is set and an interrupt occurs. The error message shows the actual coupler status (check the two bytes following the error code).

		RESPO	ONSES
	CONDITIONS	1	2
1.	Has CE error message 24 occurred more than three times within one-half hour?	Y	N
	ACTIONS	SEQUI	ENCE
1.	During the next PM period, run off-line MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics (depending on which coupler is present). Also run either TFF on native mode 255Xs or TFE on -100 255Xs.	1	-
2.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	2	
3.	Replace the coupler I/O card (slot C for the $6000$ Coupler, slot AA for the $6000$ Expansion Coupler).	3	-
4.	Replace the coupler DMA card (slot D for the 6000 Coupler, slot A for the 6000 Expansion Coupler).	4	_
5.	If other CE error messages are outstanding, follow DDLTs for those messages.	5	_
6.	Call CE or analyst as appropriate.	6	-
7.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 24 should not be a matter for concern. However, the test operator can perform the six steps listed above at his discretion.		Х

## CE Error Message 27 - Output Data Transfer Terminated by PPU

## ASSUME

The coupler transfer terminated by PPU condition is detected by the host interface package (HIP) software. The error detection occurs in procedure PTINPROC. If the HIP is expecting output (traffic from the host to the 2550) when the transfer terminated by PPU occurs, then the PTINPROC program is in state 2 (BZSTATE = AOPT2) during the detection of the error. If the host deactivates the data channel before a data transfer is complete, bit 7 of the coupler status word is set and an interrupt occurs. The error message shows the actual coupler status (check the two bytes following the error code).

	CONDITIONS	RESP	onses
	CONDITIONS	1	2
1.	Has CE error message 27 occurred more than three times within one-half hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	During the next PM period, run off-line MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics (depending on which coupler is present). Also run either TFF on native mode 255Xs or TFE on -100 255Xs.	1	-
2.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	2	-
3.	Replace the coupler I/O card (slot C for the $6000$ Coupler, slot AA for the $6000$ Expansion Coupler).	3	_
4.	Replace the coupler DMA card (slot D for the 6000 Coupler, slot A for the 6000 Expansion Coupler).	4	_
5.	If other CE error messages are outstanding, follow DDLTs for those messages.	5	-
6.	Call CE or analyst as appropriate.	6	-
7.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 27 should not be a matter for concern. However, the test operator can perform the six steps listed above at his discretion.	_	х

## CE Error Message 28 - Hardware Timeout On Output

#### ASSUME

The coupler hardware timeout condition is detected by the host interface package (HIP) software. The error detection coding resides in procedure PTINTPROC. If the timeout occurs while the HIP is expecting output data (traffic from the host to the 2550) then the PTINTPROC program is in state 5 (BZSTATE = AOPT5) during the detection of the error. If the host to 2550 channel is active longer than three seconds, the coupler will deactivate the channel, set bit 10 (timeout) and bit 15 (alarm) in the coupler status, and cause an interrupt. The CE error message contains the actual coupler status (check the two bytes following the error code).

	CONDITIONS	RESP	ONSES
	CE error message 28 occurred more than three times within one-half hour?  ACTIONS  SEQUENTIAL TO SEQUENT ACTIONS  ACTIONS  ACTIONS  SEQUENT ACTIONS  SEQUENT ACTIONS  SEQUENT ACTIONS  SEQUENT ACTIONS  ACTIONS  SEQUENT ACTIONS  ACTIONS  SEQUENT ACTIONS  ACTIONS  SEQUENT ACTIONS  ACTIONS  ACTIONS  SEQUENT ACTIONS  Lace the next PM period, run off-line MSMP 6000 Coupler or 6000 Expansion Coupler mostics (depending on which coupler is present). Also run either TFF on native mode for or TFE on -100 255Xs.  Lace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core parametrizes, and slot AB if running through a secondary coupler on MOS memory machines).  Lace the coupler I/O card (slot C for the 6000 Coupler, slot AA for the 6000 Expansion pler).  Lace the coupler DMA card (slot D for the 6000 Coupler, slot A for the 6000 Expansion pler).  Action CE error messages are outstanding, follow DDLTs for those messages.  5 LCE or analyst as appropriate.  6 CE or analyst as appropriate.  6 CE or analyst as reason to believe some serious fault exists, an occasional CE error mage 28 should not be a matter for concern. However, the test operator can perform the	1	2
1.	Has CE error message 28 occurred more than three times within one-half hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	During the next PM period, run off-line MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics (depending on which coupler is present). Also run either TFF on native mode 255Xs or TFE on -100 255Xs.	1	_
2.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	2	_
3.	Replace the coupler I/O card (slot C for the $6000$ Coupler, slot AA for the $6000$ Expansion Coupler).	3	_
4.	Replace the coupler DMA card (slot D for the 6000 Coupler, slot A for the 6000 Expansion Coupler).	4	
5.	If other CE error messages are outstanding, follow DDLTs for those messages.	5	_
6.	Call CE or analyst as appropriate.	6	_
7.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 28 should not be a matter for concern. However, the test operator can perform the six steps listed above at his discretion.	_	X

## CE Error Message 29 - Missing EOP

## ASSUME

The host interface package (HIP) software detected a missing end of operation (EOP) flag. In the early coupler models this error was caused by a timing problem. This coupler problem has been corrected.

	CONDITIONS	RESP	ONSES
		1	2
1.	Has CE error message 29 occurred more than three times within one-half hour?	Y	N
	ACTIONS	SEQUI	ENCE
1.	Run MSMP 6000 Coupler diagnostics. Also run either TFF on native mode 255%s or TFE on -100 255%s.	1	_
2.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	2	_
3.	Run ODS load check and mainframe diagnostics.	3	-
4.	If other CE error messages are outstanding, follow DDLTs for those messages.	4	-
5.	Call CE or analyst as appropriate.	5	-
6.	Unless the customer has reason to believe some serious fault exists, an occasional CE error message 29 should not be a matter for concern. However, the test operator can perform the five steps listed above at his discretion.	-	X

## CE Error Message OC - Abnormal Secondary DCD

#### ASSUME

Abnormal secondary DCD (received-line signal detector) was detected by the CLA status handler. This signal can be used as an interrupt signal from the terminal equipment and is monitored for a level change.

		RE	SPONS	SES
	CONDITIONS	1	2	3
1.	The byte of the CE error message following the error code contains the CLA address. Is the CLA on a line using reverse channel interrupt in its protocol?	N	Y	Y
2.	Are there any complaints about the reverse channel interrupt function?	-	Y	N
	ACTIONS	SE	QUENC	CE
1.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the intermittent CLA line.	х	Х	_
2.	None. This is a normal message in response to a reverse channel interrupt.	_	-	х

## TABLE 2-1. CE ERROR CODES DDLT (Sheet 30 of 36)

## CE Error Message 2A - HASP too Many NAKS Received

## ASSUME

The HASP TIP has received a fifth NAK (negative acknowledge block) on a block and has declared the line to be inoperative. This condition can be caused by a noisy transmission line, a bad modem, a bad CLA, or a bad terminal.

		RESPO	ONSES
	CONDITIONS	1	2
1.	The byte of the CE error message following the error code conatins the CLA address. Has the CLA received more than three CE error messages 2A during one hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the failing line.	х	-
2.	Some noise on a transmission line is to be expected. Unless the customer has reason to believe that some serious fault exists, an occasional CE error message 2A should not be a matter of concern. However, the test operator can perform the above step at his discretion.	_	Х

# CE Error Messages 2B and 2C - Bad BCB From HASP TIP or HASP Workstation

#### **ASSUME**

The protocol between the HASP TIP and the HASP terminal has detected two or more lost blocks and declared the condition unrecoverable and the line inoperative. This condition can be caused by a noisy transmission line, bad modem, a bad CLA, or a bad terminal. CE error messages 2B occurs when the HASP terminal detects lost blocks. CE error messages 2C occurs when the HASP TIP detects lost blocks.

<del></del>		·	
	CONDITIONS	RESP	ONSES
1.	The byte of the CE error message following the error code contains the CLA address. Has the CLA received three or more CE error messages 2B or 2C during one hour?	Y	N
	ACTIONS	SEQU	ENCE
ı.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the failing line.	x	-
2.	Some noise on a transmission line is to be expected. Unless the customer has reason to believe that some serious fault exists, an occasional CE error message 2B or 2C should not be a matter of concern. However, the test operator can perform the above step at his discretion.	_	х

## CE Error Message 2D - HASP Workstation Restart

## ASSUME

The HASP TIP has detected an unexpected HASP workstation restart. This condition can be caused by the HASP workstation operator doing a restart or a noisy transmission line.

		RE	RESPON	
	CONDITIONS	1	2	3
1.	The byte of the CE error message following the error code contains the CLA address. Did the HASP workstation operating on this line do a restart?	Y	N	N
2.	Has this CLA received three or more CE error messages 2D during one hour?	_	Y	N
	ACTIONS	SEQUENCE		CE
1.	This should not be treated as an error.	х		_
2.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the failing line.	-	х	_
3.	Some noise on a transmission line is to be expected. Unless the customer has reason to believe that some serious fault exists, an occasional CE error message 2D should not be a matter of concern. However, the test operator can perform the above step at his discretion.	_	_	X

# CE Error Messages 30, 31, and 32 - No Response, Bad Response, Error Response From Mode 4 Terminal

#### ASSUME

CE error message 30 occurs when a response timeout occurs after transmitting to the terminal. CE error message 31 occurs when the terminal response is not the expected response. CE error message 32 occurs when the terminal indicates it has received incorrect information. These three CE error messages can be caused by a bad terminal, a bad modem or a noisy transmission line.

	CONDITIONS	RESP	ONSES 2	
1.	The byte of the CE error message following the error code contains the CLA address. Has the CLA received more than three CE error messages 30, 31, or 32 in the last half-hour?	Y	N	
	ACTIONS	SEQU	ENCE	
1.	Contact the terminal operator and have him verify that the terminal is correctly configured: all switches in normal positon, emulator loaded correctly, and power to modem and to terminal is on.	1	-	
2.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the failing line.	2	-	
3.	Some noise on a transmission line is to be expected. Unless the customer has reason to believe that some serious fault exists, an occasional CE error message 30, 31, or 32 should not be a matter of concern. However, the test operator can perform the above steps at his discretion.	_	х	

## CE Error Message 33 - LIP Timeout on Idle Block

## ASSUME

The link interface program (LIP) in the local NPU has timed out waiting for an idle block from a remote NPU. This condition can be caused by a remote NPU failure or a noisy transmission line.

	and the control of th		
	CONDITIONS	RESPO	NSES
		1	2
1.	The byte of the CE error message following the error code contains the CLA (trunk) address. The second byte of the message following the CLA address contains the node ID of the remote NPU. Has the NPU failed?	Y	N
	ACTIONS	SEQUE	NCE
1.	Run ODS load check and mainframe diagnostics on failed NPU. Also run either TFF on native mode 255Xs or TFE on -100 255Xs	1	_
2.	Run MSMP MLIA diagnostics on failed NPU.	2	
3.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the failing trunk.	3	1
4.	Call CE or analyst as appropriate.	4	2

# CE Error Messages 34 and 35 - HDLC Protocol Failure and Command Reject

#### ASSUME

CE error message 34 occurs when the local NPU link interface program (LIP) fails to receive a response to a block sent to the remote NPU. CE error message 35 occurs when the local NPU LIP sends a command to the remote NPU which is rejected. Both of these conditions can be caused by a remote NPU failure or a noisy transmission line.

	CONDITIONS	RESPO	ONSES
		1	2
1.	The byte of the CE error message following the error code contains the CLA (trunk) address. The second byte of the message following the CLA address contains the node ID of the remote NPU. Has the remote NPU failed?	Y	N
	ACTIONS	SEQUE	ENCE
1.	Run ODS load check and mainframe diagnostics on failed NPU. Also run either TFF on native mode 255Xs or TFE on -100 255Xs.	1	_
2.	Run MSMP MLIA diagnostics on failed NPU.	2	-
3.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the failing trunk.	3	1
4.	Call CE or analyst as appropriate.	4	2

## TABLE 2-1. CE ERROR CODES DDLT (Sheet 36 of 36)

## CE Error Message 36 - LIP Received Bad Frame (CRC Error)

## ASSUME

This message occurs when the local NPU link interface program (LIP) detects a CRC error on data received from the remote NPU. The condition can be caused by a noisy transmission line or a bad CLA.

	CONDITIONS	RESP	ONSES
	CONDITIONS	1	2
1.	The byte of the CE error message following the error code contains the CLA (trunk) address. The second byte of the message following the CLA address contains the node ID of the remote NPU. Has CE error message 36 occurred more than three times in one hour?	Y	N
	ACTIONS	SEQU	ENCE
1.	Using the communications line fault isolation procedures in section 4, run on-line diagnostics on the failing trunk.	x	_
2.	Some noise on a transmission line is to be expected. Unless the customer has reason to believe that some serious fault exists, an occasional CE error message 36 should not be a matter of concern. However, the test operator can perform the above step at his discretion.	-	х

# STATISTICS SERVICE MESSAGES

Each NPU maintains statistics data and a timer that generate statistics at intervals selected during CCP program build. Statistics message counters are maintained for the NPU and for each trunk and line. Each type of counter is dumped and cleared at each timer timeout. Reports are also sent regardless of the timer if you disconnect or disable a line or if a statistics counter overflows. The statistics block is dumped and cleared and the counter is set to ones.

Statistics reports are sent as unsolicited service messages.

The first bytes of statistics messages are the same for NPUs and trunks and lines. The remaining bytes (text) are unique to each message type. The format of the common bytes is:

Link header	DN	SN		P/RES/ BT=04	PFC =07	SFC =01 or 02	TEXT
----------------	----	----	--	-----------------	------------	---------------------	------

DN Destination node - 00 is the engineering file in the host

SN Source node - originating NPU

CN Connection number - 00 for statistics messages

P/RES Unused

BT Block type - 4 is CMD block

PFC Primary function code - 07 is statistics message

SFC Secondary function code


01 is NPU statistics
02 is line/trunk statistics

TEXT See appendix A for explanation

The information in the statistics messages is stored in host files. To access this information, run the Host Performance Analyzer Program (HPA) as described in the Communications Multiplex Hardware Maintenance manual.

Appendix A shows the format of the text, whose byte assignment and byte meaning are unique for each of the statistics message types.

Figure 2-2 shows two flowcharts that summarize DDLT procedures for the two types of statistics messages: NPU and trunk/line. The DDLTs for these messages are shown in table 2-2.






Figure 2-2. Flowcharts for Statistics Messages DDLTs

## Statistics Service Message Ol - NPU Statistics

#### ASSUME

1. Operator is familiar with DDLT format.

The NPU statistics give useful information about the 255x host interface and about system loading. The count of blocks discarded due to bad network addresses (word 4) and the count of blocks discarded due to bad format (word 5) could indicate possible coupler problems. Statistics messages are generated periodically as well as when the statistics count for an individual equipment exceeds the threshold level.

	CONDITIONS	RE	ISES	
	CONDITIONS	1	2	3
1.	Have there been any messages discarded for bad network addresses or bad format?	Y	N	N
2.	Has the TIP regulation occurred frequently?	-	Y	N
	ACTIONS	SE	QUEN	ICE
1.	Replace the coupler cards (slots B, C, and D in MOS memory machines, and slots A, B, and C in core memory machines) at next PM period.	х	_	_
2.	Check the 2550 Configurator to see if sufficient memory has been provided for the present load and configuration.	_	1	-
3.	Check the trunk/line statistics messages. Is the NPU running at its maximum capacity? If so, take no action. Otherwise, consider any problems that are using up buffers.	_	2	_
4.	Take no action.	-	_	х

## Statistics Service Message 02 - Trunk/Line Statistics

#### ASSUME

1. Operator is familiar with DDLT format.

The trunk/line statistics give a summary of the amount of activity by port number (line) for all ports. The most used parts of the message are: 1) the port number (first byte of text); 2) the count of the blocks transmitted from the terminal to the host (word 1 of text); and 3) the count of the blocks received from the host to the terminal (word 2 of text). These statistics would be most useful in discovering a port in a rotary configuration that was not working before the customer calls up and complains, or for comparing actual activity of the various ports to expected activity.

		RESP	ONSES
	CONDITIONS	1	2
1.	Does one of the rotary ports show an unusually low number of blocks of traffic compared to the rest of the rotary system? (Normally the amount of traffic should decrease as you get further away from the primary port of the rotary system.)		N
	ACTIONS	SEQUI	ENCE
1.	During the next PM period, run on-line diagnostics on the port with the unusually low traffic following the communications line fault isolation procedures in section 4.	X	_
2.	Take no action.	_	Х

# HALT CODES AND DUMP INTERPRETATION

When the Communications Control Program (CCP) stops the Network Processing Unit (NPU) because of an unrecoverable condition caused by either hardware or software errors, CCP delivers a halt message to the console if you have selected the console option. The format of the halt message is:

HALT xxxx yyyy www PORT zzzz BUFFER ADDR

xxxx The four digit hexadecimal halt code

yyyy The address of the program in control when the halt occurred

wwww The port number. It appears only with these CLA hardware halt codes:

CLA address out of range (0005) and CLA status overflow (000D)

zzzz The buffer address. It appears only with these buffer halt codes:

0009, 000A, 000B, and 000C

Following a halt, the host usually dumps the NPU main memory, micromemory, and the file l registers. After a dump, the host attempts to reload the NPU. The number of times the host attempts to reload the NPU is based on a parameter you specify at installation. Another installation option gives you a dump after the first two attempts at reloading; subsequent reloading attempts suppress dumps.

To reload the NPU after the installation option expires, you must use the MASTER CLEAR switch on the NPU maintenance control panel to clear the NPU.

You can locally stop the NPU by setting the MASTER CLEAR switch on the maintenance control panel.

If a halt code is not generated, you must consult the dump listing generated from the host by the Network Dump Analyzer (NDA) program to find the cause of the failure. If you are a CE, you also may want to consult the dump listing whenever the cause of the halt is not apparent.

## HALT CODES

Halt codes are caused by:

Incorrect switch settings

Hardware malfunctions

Either hardware or software problems

#### HARDWARE MALFUNCTIONS

These conditions are usually caused by some type of hardware failure:

Power failures (halt code 0001)

Memory parity error (halt code 0002)

Memory protect bit error (halt code 0003)

Bad MLIA initialization status (halt code 0011)

MLIA failure (halt code 0005)

If you are a host operator and one of these conditions occurs, it's best to allow the CE to repair the underlying hardware problem.

## HARDWARE OR SOFTWARE PROBLEMS

Halt codes other than those already specified are caused by either a hardware failure or a software error. If you are a host operator, you might want to call a systems analyst to correct any software problems and a CE to repair any hardware problems. Regardless of whom you consult, be sure to have any dumps that were taken by the host available for examination.

Figure 3-1 is a flowchart that summarizes the DDLT procedures for halt codes, and table 3-1 is a series of DDLTs you should consult to help you interpret halt codes.




Figure 3-1. Flowchart for Halt Codes DDLT

## ASSUME

- 1. The operator is familiar with the ODS DDLT format.
- 2. The system has halted or has not been successfully loaded.

TABLE 3-1. HALT CODES DDLT (Sheet 2 of 36)

	ASSUME							
	CONDITIONS		RESP	ONSES	; 			
		1	2	3	4			
1.	Has the system been successfully loaded and displayed the following:							
	CCP 3.5 NPU ID: 00xx							
	LEVEL: 00yy VARIANT: 00zz	N	N	N	Y			
2.	Check location 30 <sub>16</sub> (halt code) of the dump. Does this address have any bits set to 1?	N	N	Y	_			
3.	Is this a new build that has not loaded successfully before?	N	Y	-	-			
	ACTIONS		SEQUENCE		Ē			
1.	Go to sheet 3.	х	-	-	_			
2.	Try reloading CCP.		1	1	1			
3.	Try loading previous good load file. If this file loads successfully, have the system analyst check the build time parameters and program changes since the last good build operation.	-	2	-	-			
4.	Run ODS load check and mainframe diagnostics.	-	3	-	-			
5.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	-	4	-	-			
6.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	_	5	_	-			
7.	Call CE or analyst as appropriate.	-	6	-	-			
8.	Go to sheet 5.	-	-	2	_			
9.	Go to sheet 4.	_	T -	-	2			

# Halt Codes - No Halt Code Available

## ASSUME

	CONDITTIONS	RESPONSI
	CONDITIONS	1
1.	The system failed during initialization but did not generate a halt code message. Look up the NPINTAB entry in the address table (address of table is at 150 <sub>16</sub> ). The contents of this location is the start address of the NPINTAB table. (See dump interpretation subsection at end of section 3.) Look at the second entry in the NPINTAB table. This entry contains a group of flags that are set as each phase of initialization is completed as follows:	x
	Bit 0 is set to initialize page registers.	
	Bit l is set at the completion of setting up program protect bits.	
	Bit 2 is set at the completion of initializing buffers (assigning BCBs and releasing all buffers to buffer pools).	
	Bit 3 is set at the completion of initializing worklist control blocks (WLCBs).	
	Bit 4 is set at the completion of miscellaneous NPU console initialization.	
	Bit 5 is set at the completion of applications initialization.	
	Bit 6 is set at the completion of initializing the MLIA (stops NPU if two CLAs have duplicate addresses).	
	Bit 7 is set at the completion of initializing the lines.	
	Bit 8 is set when timer services are initialized.	
	Bits 9 thru 14 should be zeros. If not, none of the word is valid.	
	Bit 15 is set at the completion of the second phase of buffer initialization.	
	The P-register (contained in location $FF_{16}$ of the File 1 register dump area) shows the address where the NPU was looping at halt time.	
	ACTIONS	SEQUENCE
۱.	Try reloading CCP.	1
2.	Find whether load file has been modified.	2
١.	Run ODS load check and mainframe diagnostics.	3
	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	4
	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	5

## Halt Codes - Halt Code Available ASSUME RESPONSES CONDITIONS 3 1. Was the last message displayed on the console a halt code message? Halt code messages have the format HALT xxxx yyyy; xxxx is the halt and yyyy is the return Y Y N address of the program in control. Y N 2. Is the halt code non-zero? 3. Check location $30_{16}$ of the dump. This contains the halt code. Is this non-zero? Y SEQUENCE ACTIONS X X 1. Go to sheet 5. X 2. Go to sheet 17. 3. The program was looping. File 1 register $FF_{16}$ of the dump contains the P-register value. This value is the address of the program that was executing when the 2550 stopped. A link edit listing contains the program that resides at this address. Go to sheet 19.

# Halt Codes Index

## ASSUME

- 1. Operator is familiar with the ODS DDLT format.
- 2. Halt code message has halt code.

		RE	SPON	SES		
1	2	3	4	5	6	7
N	N	N	N	N	N	Y
N	N	N	N	N	Y	-
N	N	N	N	Y	-	_
N	N	N	Y	_	-	-
N	N	Y	_	-	-	-
N	Y	-	-	-	-	-
		S	EQUE	NCE		
х	-	-	-	1	-	-
-	X	-	_	_	-	-
-	-	x			-	-
_	_	-	х		_	-
ļI						
-	-	_	_	х	-	_
-	1	-	<u>-</u>	x -	- х	_
	N N N N N N N N N N N N N N N N N N N	N N N N N N N N Y Y	1 2 3 N N N N N N N N N N N N Y N Y -	1 2 3 4 N N N N N N N N N N N N N N Y N N Y - N Y - SEQUE  X X X -	N N N N N N N N N N N N N N N N N N N	1 2 3 4 5 6  N N N N N N N N N Y N N N N Y N N Y N Y SEQUENCE  X X X

#### Halt Codes Index ASSUME RESPONSES CONDITIONS 5 3 4 N Y N N N N 1. Is the halt code = 0006? N N N Y N 2. Is the halt code = 0007? N N Y 3. Is the halt code = 0008? N Y 4. Is the halt code = 0009? N Ÿ 5. Is the halt code = 000A? SEQUENCE ACTIONS X 1. Go to sheet 7. X 2. Go to sheet 22. X 3. Go to sheet 21. X 4. Go to sheet 20. x 5. Go to sheet 19.

6. Go to sheet 18.

	Halt Codes Index ASSUME						
1	CONDITIONS				ONSE	s	
	Is the halt code = 000B?	1	2	3	4	5	6
	1. Is the halt code = 000B?	N	N	N	N	N	Y
	2. Is the halt code = 000C?	N	N	N	N	Y	_
	3. Is the halt code = 000D?	N	N	N	Y	-	_
	4. Is the halt code = 000E?	N	N	Y	•	-	-
	5. Is the halt code = 000F?	N	Y	-	1	-	_
	ACTIONS			SEQ	UENC	E	
	1. Go to sheet 8.	X	-	-	1	-	_
	2. Go to sheet 27.	-	x	-	-	-	
	3. Go to sheet 26.	-	-	x	-	-	
	4. Go to sheet 25.	_	_	_	x	_	
	5. Go to sheet 24.	-	-	-	-	х	_
	6. Go to sheet 23.	-	-	-	-	-	х

TABLE 3-1. HALT CODES DDLT (Sheet 8 of 36)

Halt Codes Index						
ASSUME						
		RESPONSES				
CONDITIONS	1	2	3	4	5	6
1. Is the halt code = 0010?	N	N	N	N	N	Y
2. Is the halt code = 0011?	N	N	N	N	Y	-
3. Is the halt code = 0012?	N	N	N	Y	-	-
4. Is the halt code = 0013?	N	N	Y	-		_
5. Is the halt code = 0014?	N	Y		_	_	-
ACTIONS			SEQ	UENC	E	
1. Go to sheet 9.	х	_	_	_	-	-
2. Go to sheet 20.	_	x	_	_	_	_
3. Go to sheet 31.	<u> </u>	_	х	_	_	-
4. Go to sheet 30.	_	_	_	x	_	-
5. Go to sheet 29.	_	_	_	_	x	-
6. Go to sheet 28.	-	-	-	-	_	x

TABLE 3-1. HALT CODES DDLT (Sheet 9 of 36)

Halt Codes Index						
ASSUME						
			RESP	ONSE	s	
CONDITIONS	1	2	3	4	5	6
1. Is the halt code = 15?	N	N	N	N	N	Y
2. Is the halt code = 16?	N	N	N	N	Y	-
3. Is the halt code = 17?	N	N	N	Y	-	-
4. Is the halt code = 18?	N	N	Y	-	-	-
5. Is the halt code = 19?	N	Y	ı	-	1	-
ACTIONS			SEQ	UENC	E	
1. Go to sheet 10.	X	-	-	-	-	-
2. Go to sheet 20.	-	х	-	-	-	_
3. Go to sheet 20.	_	-	X	-	-	
4. Go to sheet 33.	-	-	-	х	-	_
5. Go to sheet 20.	_	-	-	-	х	-
6. Go to sheet 32.	-	-	-	-	-	х

TABLE 3-1. HALT CODES DDLT (Sheet 10 of 36)

ialt Codes Index	ASSUME						
	ADDUM						
			]	RESP	ONSE	S	
	CONDITIONS	1	2	3	4	5	
1. Is the halt code = 1A?		N	N	N	N	N	L
2. Is the halt code = 1B?		N	N	N	N	Y	L
3. Is the halt code = 1C?		N	N	N	Y	-	L
4. Is the halt code = 1D?		N	N	Y	_	_	L
5. Is the halt code = 1E?		N	Y	-	-	_	
	ACTIONS			SEQ	UENC	E	
1. Go to sheet 11.		X	-	-	-	_	
2. Go to sheet 34.		_	х	_	_	_	1
3. Go to sheet 20.				х	_	_	1
4. Go to sheet 20.		_	_	_	х	_	
5. Go to sheet 20.		-		-	_	х	
6. Go to sheet 20.		_	_	-	-	-	

TABLE 3-1. HALT CODES DDLT (Sheet 11 of 36)

Halt Codes Index					
ASSUME					
CONDITATIONS		RESPON:			
CONDITIONS	1	2	3		
1. Is the halt code = 1F?	N	N	N	,	
2. Is the halt code = 20?	N	N	Y		
3. Is the halt code $\geq$ 21?	N	Y	_		
ACTIONS		SEQUENC			
1. You have misinterpreted an instruction. Go back to sheet 1 and try again.	х	-	-		
2. Go to sheet 20.	-	х	_		
3. Go to sheet 36.		_	х		
4. Go to sheet 35.	-	-	-	:	

TABLE 3-1. HALT CODES DDLT (Sheet 12 of 36)

<u>Hal</u>	t Code 0000 - Master Clear			
	ASSUME			
			SPON	SES
	CONDITIONS	1	2	3
1.	Has Master Clear button been used?	Y	N	N
2.	Did NAM halt the 2550?	N	Y	N
	ACTIONS	SEQUENCE		CE
1.	No action; normal use.	1	-	_
2.	Check NAM dayfile for possible PIP coupler error.	_	1	_
3.	Possible firmware problem. Call an analyst.	-	-	1

# Halt Code 0001 - Power Failure

# ASSUME

Power failure may be caused by a power supply turning off or a momentary power fluctuation on the line.

					ŧ
		RE	SPON	SES	
	CONDITIONS	1	2	3	
1.	Has one or more power supplies turned off?	N	N	Y	
2.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBLN00 program? (The address of PBLN00 can be found in the CCP Link Edit listing - module memory map sorted by module address.)	N	Y	_	
	ACTIONS	SE	QUEN	ICE	
1.	Run ODS load check and mainframe diagnostics.	1	-	-	1
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	_	<u> </u>	4
3.	Run TFF on-line under MALET.	3	_	_	
4.	Call CE or analyst as appropriate.	4	_	<u> </u>	
5.	Reload CCP (there was a momentary power fluctuation on the line).	<u> </u>	х	_	
6.	Reapply power to the failed power supply or replace the power supply.	<u> </u> -	_	X	

# Halt Code 0002 - Memory Parity Error

## ASSUME

The NPU detected a memory parity error while executing a memory cycle during a program instruction, or during a memory cycle-stealing operation of a DMA-using device such as the coupler or MLIA. Memory parity error logic is described in the hardware reference manual.

	CONDITIONS	RESI	ONSES				
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBLN00 program? (The address of PBLN00 can be found in the CCP Link Edit listing - module memory map - sorted by module address.)	Y	N				
	ACTIONS	SEQU	ENCE				
1.	Run TFF on-line under MALET.	1	1				
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2				
3.	Run ODS load check and mainframe diagnostics.	3	3				
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	4	4				
5.	Call CE or analyst as appropriate.	5	6				
6.	Have analyst check that the program calling PBHALT did not mistakenly use halt code 0002.	-	5				

## Halt Code 0003 - Program Protect Error

## ASSUME

A program protect error was detected by the NPU. This is a valid condition if the protect system is active (using software breakpoints). Unexpected occurrence of this halt may indicate a violation of restrictions on use of software breakpoint. Program protect error logic is described in the hardware reference manual. Software breakpoint logic is described in the CCP 3 Internal Maintenance Specifications, available from Software Manufacturing Distribution.

	CONDITIONS	RE	SPON	SES 3
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBBREAKPOINT program? (The address of PBBREAKPOINT can be found in the CCP Link Edit listing — module memory map — sorted by module address.)	Y	N	_
2.	Was someone making use of the software breakpoints?	Y	-	N
	ACTIONS	SEQUENCE		CE
1.	Ensure that someone did not accidently leave a software breakpoint set (ask the operator, and so forth). Remove any software breakpoints.	1		_
2.	Run ODS load check and mainframe diagnostics (including protect bit tests).	2	1	1
3.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics and the MLIA diagnostics.	3	2	2
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	4	3	3
5.	Call CE or analyst as appropriate.	5	4	4

# Halt Code 0004 - Interrupt Count Less Than Zero

#### ASSUME

Either the PASCAL program has attempted to unlock interrupts more often than the interrupts were locked, or a program looped through instructions which included a lock interrupts instruction until the count overflowed  $(8000_{16})$ .

	CONDITIONS	RESI	PONSES			
<u> </u>		1	2			
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the UNLOCK program? (The address of UNLOCK can be found in the CCP Link Edit listing - module memory map - sorted by module address.)	Y	N			
	ACTIONS	SEQUENCE				
1.	Have system analyst look at the entry point of UNLOCK to find who called UNLOCK. Check the calling program to find if it was looping.	1	-			
2.	Run ODS load check and mainframe diagnostics.	2	1			
3.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	3	2			
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	4	3			
5.	Run MSMP MLIA diagnostics.	5	4			
6.	Call CE or analyst as appropriate.	6	5			

## Halt Code 0005 - MLIA Failure

## ASSUME

The multiplex loop interface adapter (MLIA) failed. Either a status was read from the MLIA with bit 00 equal to 1 (MLIA not ready), or more than 20 unprocessed MLIA error interrupts have accumulated. This condition can occur when the multiplex loop opens.

				]
	CONDITIONS		ONSES	
		1	2	-
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBMLIA program? (The address of PBMLIA can be found in the CCP Link Edit listing - module memory map - sorted by module address.)	Y	N	
	ACTIONS	SEQU	ENCE	
1.	Run ODS load check and mainframe diagnostics.	1	1	1
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2	1
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	3	
4.	Run MSMP MST041 diagnostics.	4	4	
5.	Call CE or analyst as appropriate.	5	6	
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.		5	

# Halt Code 0006 - Overran CIB

## ASSUME

The firmware pointer to read next loop cell from circular input buffer (CIB) exceeded present line frame pointer.

	CONDITIONS	RES	PONSES 2
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBMLIAOPS or PMMLEH program? (The address of PBMLIAOPS and PMMLEH can be found in the CCP Link Edit listing module memory map — sorted by module address.)	Y	N
	ACTIONS	SEQU	ENCE
1.	Run MSMP MLIA diagnostics.	1	1
2.	Run ODS load check and mainframe diagnostics.	2	2
3.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	3	3
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	4	4
5.	Call CE or analyst as appropriate.	5	6
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.	-	5

Halt Code 0007 - Branch to Zero Detected  ASSUME		
Branch to zero (less than 000E) has been detected.	·	
	RESPO	NSES
CONDITIONS	1	2
1. Has this build been successfully run before?	Y	N
ACTIONS	SEQU	ENCE
1. Run ODS load check and mainframe diagnostics.	1	-
2. Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	
3. Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	
4. Run MSMP MST041 diagnostics.	4	-
5. Call CE or analyst as appropriate.	5	
<ol> <li>Have system analyst check the MPLINK and MPEDIT listings for undefined externals or undefined LINKZAPs.</li> </ol>	6	_

# TABLE 3-1. HALT CODES DDLT (Sheet 20 of 36)

Halt Codes 0008, 0014, 0016, 0018 through 1D, and >20		
ASSUME		
The above-named halt codes are not used.		
CONDITIONS		÷
None.		
ACTIONS		
None.		

#### Halt Code 0009 - Ran Out of Buffers **ASSUME** RESPONSES CONDITIONS Check location 3116 of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBSTOP program? (The address of PBSTOP can be found in the CCP Link Edit listing - module memory map sorted by module address. PBSTOP is the firmware interface.) Y Y Y N Fine BECTLB in the CCP Link Edit listing - entry symbol list - sorted by entry name. Locate the entry point of BECTLB in the dump and check the contents of the lst, 11th, 21st, and 31st word (decimal) of BECTLB. Were any of these words equal to zero? Y Y N 3. Was the configuration changed recently? N Y ACTIONS SEQUENCE Run ODS load check and mainframe diagnostics. 1 2 Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics. 2 2 2 3 Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines). 3 3 3 Run MSMP MLIA diagnostics. 4 5 4 4 Call CE or analyst as appropriate. 5 6 5 5 Check the 2550 configurator to see if sufficient memory is available to handle the system configuration (based on terminal types, number of terminals, and so forth).

# Halt Code 000A - Duplicate Release of Buffer

## ASSUME

The buffer to be released has already been released.

				J
	CONDITIONS	RESP	onses	I
	CONDITIONS	1	2	
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBSTOP program? (The address of PBSTOP can be found in the CCP Link Edit listing - module memory map - sorted by module address. PBSTOP is the firmware interface.)	Y	N	
	ACTIONS	SEQU	ENCE	
1.	Run ODS load check and mainframe diagnostics.	1_	1	1
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2	1
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	3	
4.	Run MSMP MLIA diagnostics.	4	4	1
5.	Call CE or analyst as appropriate.	5	6	1
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.		5	

# Halt Code 000B - Buffer Chain Error

## ASSUME

The program tried to get a buffer from the free buffer pool. The chaining address of the buffer obtained did not point to the end of another buffer of the same size.

<u> </u>			
	CONDITIONS	RESP	ONSES
		1 1	2
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBSTOP program? (The address of PBSTOP can be found in the CCP Link Edit listing - module memory map - sorted by module address. The buffer address is printed following the halt code.)	Y	N
	ACTIONS	SEQUI	ENCE
1.	Run ODS load check and mainframe diagnostics.	1	1
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	3
4.	Run MSMP MLIA diagnostics.	4	4
5.	Call CE or analyst as appropriate.	5	6
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.	-	5

## Halt Code 000C - Buffer out of Range

### ASSUME

The program tried to release a buffer. The address of the buffer was not within the range of the buffer area.

1				l
	CONDITIONS	RESP	onses	
	CONDITIONS	1	2	
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the BUFMAI program? (The address of BUFMAI can be found in the CCP Link Edit listing — module memory map — sorted by module address. The buffer address is printed following the halt code.)	Y	N	
	ACTIONS	SEQU	ENCE	
1.	Run ODS load check and mainframe diagnostics.	1	1	
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2	4
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	3_	-
4.	Run MSMP MLIA diagnostics.	4	4	1
5.	Call CE or analyst as appropriate.	5	6	
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.	_	5	

## Halt Code 000D - Coupler Alarm Condition

### ASSUME

The coupler detected a memory parity error or a program protect bit error during data transfer.

	CONDITIONS	RESPONSES	
		1	2
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PTINIT program? (The address of PTINIT can be found in the CCP Link Edit listing - module memory map - sorted by module address.)	Y	N
	ACTIONS	SEQU	ENCE
1.	Run ODS load check and mainframe diagnostics.	1	1
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	3
4.	Run MSMP MST041 diagnostics.	4	4
5.	Call CE or analyst as appropriate.	5	6
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.	-	5

## Halt Code 000E - Monitor Stopped

#### ASSUME

The monitor stopped (OPS TIMEOUT) because a routine was running which did not reset the monitor timer often enough. Probably part of memory has become garbled.

	· · · · · · · · · · · · · · · · · · ·	RESPON	)NSES
	CONDITIONS	1	2
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PBTIMER program? (The address of PBTIMER can be found in the CCP Link Edit listing - module memory map sorted by module address.)	Y	N
	ACTIONS	SEQUE	NCE
1.	Run ODS load check and mainframe diagnostics.	1	1
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	3
4.	Run MSMP MST041 diagnostics.	4	4
5.	Call CE or analyst as appropriate.	5	6
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.	-	5

## Halt Code 000F - Too Many Worklist Entries From One CLA

#### ASSUME

Too many status messages were received from the CLA. Before PBHALT halts the system to avoid running out of buffers, PBHALT checks the worklist entry to see if a CLA is requesting too many worklists. If a CLA is detected to be bad, PBHALT sets halt code 000F and gives the CLA address at the end of the message.

	CONDITIONS	RESI	PONSES			
		1	2			
1.	Is there a CLA with port address (CLA address) given in the halt message?	Y	N			
	ACTIONS	SEQUENCE				
1.	Replace the CLA having the address given at the end of the halt message.	1	_			
2.	Run ODS load check and mainframe diagnostics.	2	1			
3.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	3	2			
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).					
5.	Run MSMP MST041 diagnostics.	5	4			
6.	Call CE or analyst as appropriate.	6	5			
7.	Have system analyst check the program calling PBHALT to find if it set some halt code other than 000F.	-	6			

## Halt Code 0010 - Force Load Service Message Received

### ASSUME

The force load service message is used to cause a remote NPU to halt so that the host can reload the NPU.

		RESP	ONSES
	CONDITIONS	1	2
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PNFRCELD program? (The address of PNFRCELD can be found in the CCP Link Edit listing - module memory map - sorted by module address.)	Y	N
	ACTIONS	SEQU	ENCE
1.	No action required, this halt is normal.	х	_
2.	Run ODS load check and mainframe diagnostics.		1
3.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.		2
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).		3
5.	Run MSMP MSTO41 diagnostics.		4
6.	Call CE or analyst as appropriate.	_	6
7.	Have system analyst check the program calling PBHALT to find if it set some halt code other than $0010_{16}$ .		5

## Halt Code 0011 - Bad MLIA Initialization Status

### ASSUME

At the end of initializing the multiplex subsystem, the MLIA status was read and found to contain some value other than  $0009_{16}$ .

<b></b>			
	CONDITIONS	RESPONSE	
<u></u>	JUNDITIONS	1	2
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PIMLIA program? (The address of PIMLIA can be found in the CCP Link Edit listing - module memory map sorted by module address.)	Y	N
	ACTIONS	SEQU	ENCE
1.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	1	2
2.	Run ODS load check and mainframe diagnostics.	2	1
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	3
4.	Run MSMP MST041 diagnostics.	4	4
5.	Call CE or analyst as appropriate.	5	6
6.	Have system analyst check the program calling PBHALT to find if it set the wrong halt code.	6	5

## Halt Code 0012 - Bad NCB

## ASSUME

CCP has received a bad network control block.

		RESP	onses
	CONDITIONS	1	2
1.	Has a recent change been made to NDLP input?	Y	N
2.	Has this NPU previously been successfully loaded with current load file?	N	Y
	ACTIONS	SEQU	ENCE
1.	Using previous NDLP input, reload NPU with old load file.	1	
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.		1
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).		2
4.	Run MSMP MST041 diagnostics.		3
5.	Call CE or analyst as appropriate.	-	4

## Halt Code 0013 - Chain Address Equal to Zero

#### ASSUME

The host interface program (HIP) detected that the coupler chain address was zero. This error detection is done in procedure PTHIPINT. The error is reported only for up-line transactions (traffic from the NPU to the host). The error occurs when the coupler has used up its current buffer, has not found the last buffer flag set, and has tried to chain to the next buffer but could not find that next buffer address.

-			
	CONDITIONS		PONSES 2
1	• Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PTHIPINT program? (The address of PTHIPINT can be found in the CCP Link Edit listing – module memory map – sorted by module address.)	Y	N
	ACTIONS	SEQUENCE	
1.	. Run ODS load check and mainframe diagnostics.	1	1
2.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	2
3.	<ul> <li>Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).</li> </ul>	3	3
4.	Run MSMP MST041 diagnostics.	4	4
5.	. Call CE or analyst as appropriate.	5	6
6.	. Have system analyst check the program calling PBHALT to find if it set some halt code other than $0013_{16}  extbf{.}$	-	5

## Halt Code 0015 - Invalid Coupler Orderword

#### ASSUME

The illegal orderword condition is detected by the host interface package (HIP) software. This error detection is done in procedure PTHIPINT. PTHIPINT is in state 3 (BZSTATE = AOPT3) during detection of this error. If the orderword sent from the host to the NPU is less than 1, or equal to 4, or greater than 6, the orderword is invalid and the coupler is cleared. The orderword register on the coupler DMA card causes a coupler interrupt when loaded.

		RESP	ONSES
	CONDITIONS	1	2
1.	Check location $31_{16}$ of the dump. This is the return address of the program calling PBHALT. Are the contents of location $31_{16}$ an address within the PTHIPINT program? (The address of PTHIPINT can be found in the CCP Link Edit listing — module memory map — sorted by module address.)	Y	N
	ACTIONS	SEQUENCE	
1.	Replace the coupler I/O card (slot C for the 6000 Coupler, slot AA for the 6000 Expansion Coupler).	1	_
2.	Run ODS load check and mainframe diagnostics.	2	1
3.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	3	2
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	4	3
5.	Run MSMP MST041 diagnostics.	5	4
6.	Call CE or analyst as appropriate.	6	6
7.	Have system analyst check the program calling PBHALT to find if it set some halt code other than $0015_{16}$ .	_	5

## Halt Code 0017 - Illegal Call to Non-existant Program

#### ASSUME

A call has been made to a module that is not defined in the 2550.

	CONDITIONS	RESP	ONSES	
		1	2	
1.	Determine who was calling JOILL (see MPLINK output).	Y	-	
2.	Check output from MPLINK.	Y	-	
	ACTIONS	SEQU	SEQUENCE	
1.	This is strictly a software problem. Call analyst who should change either the MPLINK input or CCP.	1	-	

#### TABLE 3-1. HALT CODES DDLT (Sheet 34 of 36)

## Halt Code 001E - Dynamic Stack Overflow

#### ASSUME

The area where parameters are stored for recursive program calls has overflowed.

	CONDITIONS	RESPONS	ONSES
		1	
1.	Is contents of location ${ m FF}_{16}$ in main memory between ${ m 40}_{16}$ and ${ m FC}_{16}$ ?	Y	N
	ACTIONS	SEQUENCE	
1.	Probably a software problem. Call CE or analyst for analysis of dump and resolution of problem.	-	х
2.	Run ODS load check and mainframe diagnostics.	1	_
3.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	2	-
4.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).		
5.	Run MSMP MST041 diagnostics.	4	-
		"	

## Halt Code 001F - Negative Interrupt Count

Halt Code 0020 - Output Over Input

1. Call analyst for problem analysis and resolution.

2. Examine last software call to determine which TIP is not waiting for OBT.

#### ASSUME

The software maintained count of disabled interrupts has become negative.

	CONDITIONS	RESP	onses
	CONDITIONS	1	2
1.	It is unlikely that the problem is caused by standard CDC software. This is typically a hardware problem.	Y	N
	ACTIONS	SEQU	ENCE
1.	Run MSMP 6000 Coupler or 6000 Expansion Coupler diagnostics.	1	
2.	Run ODS load check and mainframe diagnostics.	2	
3.	Replace the CYBER coupler interface card (slot B on MOS memory machines, slot A on core memory machines, and slot AB if running through a secondary coupler on MOS memory machines).	3	
4.	Run MSMP MST041 diagnostics.	4	_

#### TABLE 3-1. HALT CODES DDLT (Sheet 36 of 36)

## 

## **2550 DUMPS**

The dump format is similar to the one shown in figure 3-2.

During normal operation, NPU failures are communicated to both the NOP and the HOP. After the NPU fails, the host automatically dumps and reloads the contents of NPU memory (Record 3).




Figure 3-2. Sample NPU Dump

# INTERPRETING A DUMP WITHOUT A HALT CODE

A halt can happen at any time, even before initialization is finished. For example, the system can become trapped in a loop before the CCP header prints. Because CCP is not in control (initialization hasn't completed), you will receive none of the previsously mentioned halt codes. Without a halt code, you must interpret the dump to determine which halt occurred, or in which subroutine of the initiation section the program is looping.

See pages 2 and 3 of table 3-1 for the DDLT sequence for dump interpretation.

First, examine the contents of memory location 30 (hexadecimal) as shown in the dump printout. If

it's not zero, a halt has occurred and the halt code value is in that location. Note the value in table 3-1 and follow the suggested action for that halt.

If memory location 30 (hexadecimal) equals zero, examine the address of the NPINTAB entry in the address table. The address table, which is displayed at initialization, begins at fixed memory adress 150 (hexadecimal). See table 3-2 for the contents of the address table. Entry NPINTAB gives the starting address for the NPINTAB table, whose format is shown in figure 3-3. The NPISFL entry in the NPINTAB table contains the flags that mark the initialization subroutines that have completed running when the looping started. Give this information to the systems analyst along with the printout of the dump.

TABLE 3-2. ADDRESS TABLE

Location Hexadecimal)	Address	Title/Routine	
150	BYWLCB	Worklist control block	
151	JSWLADDR	WL entry by LEVELNO	
152	ВІТСВ	Internal processing TCB	
153	BIBUFF	Internal processing block	
154	JKMASK	Interrupt masks	
155	JKTMASK	PBAMASK save area Base	
156	CBTIMTBL	TIMAL table	
157	JACT	PD controller table	
158	BECTLBK	Buffer control block (BCB)	
159	BYSTAMP	Buffer stamp area	
15A	CLBFSPACE	Buffer space in number of small buffers	
15B	0		
15C	NAPORT	Port table Mux subsystem	1
15D	BQCIB	Circular input buffer (CIB)	
15E	0		
15F	CGLCBS	Line control blocks (LCB)	
160	CHSUBLCB	Sub line control blocks	
161	CGTCBS	Terminal control blocks (TBC) Lines and TIE	?s
162	BJTIPTYPT	TIP type table	
163	njtect	Terminal characteristics table	
164	0		
165	NPINTAB	Initialization complete table	
166	0		
167	CCPVER	CCP version address (0035) Initialization	on
168	ССРСҮС	CCP cycle address (xxxx) Information	
169	CCPLEV	CCP level address (PSR level)	
16A	CCPVAR	CCP variant ID	
16B	0		

	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Word 0 (NPSODD)	0	0	0	0	0	0	0	0	X	X	х	х	х	х	X	х
Word 1 (NPISFL)	B15	0	0	0	0	0	0	В8	В7	В6	В5	В4	В3	В2	В1	во
Word 2 (NPBMLS)	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y

- NPSODD Duplicate CLA address, where XX...XX is the duplicated CLA address between  $01_{16}$  and FE $_{16}$ .  $00_{16}$  indicates preset value (no duplicates), and FF $_{16}$  indicates no response.
- NPISFL Initialization completion sequence flags, where B15 and B8 through B0 indicate start or completion of various tasks as follows:
  - B15 All buffers initialized, system initialization completed
  - B8 Second phase of buffer initialization started/completed
  - B7 Initialization of fixed lines started/completed
  - B6 Initialization of MLIA started/completed
  - B5 Application initialization started/completed
  - B4 Miscellaneous NPU console initialization started/completed
  - B3 Initialization of worklist control blocks started/completed
  - B2 Initialization of buffers started/completed
  - Bl Set up program protect bits started/completed
  - BO Set up of page registers started/completed

A function is completed if the next higher bit is set, otherwise it was started but not completed.

NPBMLS - Bad MLIA initialization status, where any value for YY...YY other than 0009<sub>16</sub> indicates bad status. Call a Customer Engineer to run MLIA diagnostics.

Figure 3-3. NPINTAB Table Starting Address Format

The Communications Control Program (CCP) includes on-line diagnostic tests that you, the systems operator, can do from the Network Processing Unit (NOP) console. These tests give you data and status information for one or more communications lines.

The topics discussed in this section are:

NOP operating instructions

 $\ensuremath{\mathsf{DDLT}}$  interpretation of diagnostic response messages

Detailed information on using commands to isolate faults

# NOP CONSOLE OPERATING INSTRUCTIONS

If you are at the host console, assign the NOP to the K-display by entering:

K.NAM.

and

K.AP=CS

Precede each command with K. For example:

K.TXT, NPU=LOCA, MSG=INT=, 20,0,00

In the following command examples, each command is shown first with its full spelling, followed by the acceptable abbreviated command format.

#### DISABLE A TRUNK OR A LINE

Use this command to disable a trunk:

Use this command to disable a communications line:

The NPU at the other end of the disabled trunk will detect a trunk failure and will break the terminal connections of all affected logical lines.

## REQUEST CONNECTION TO ON-LINE DIAGNOSTICS

Use this command to connect to the on-line diagnostic tests:

$$\left\{ \begin{array}{l} TST \\ TS \end{array} \right\} , \left\{ \begin{array}{l} NPU \\ NP \end{array} \right\} = npu-name, \left\{ \begin{array}{l} REQUEST \\ RE \end{array} \right\}$$

The TST command must be accepted before you direct any other TST command to the NPU.

The message:

/OLD: REQUEST INITIATED.

is returned if the OLD facility is not in use in the NPU. Otherwise:

/OLD: IN USE.

is returned.

NOTE

A second request from the same NOP is responded to with IN USE.

After REQUEST INITIATED, the request is successfully accepted unless the OLD facility is not available to the specified NPU. If the OLD facility is not available, you will receive this message:

FROM NPU-name
NO ONLINE DIAGNOSTICS PRESENT.

The request has been processed when you receive this message:

READY..

If you send another TST command to an NPU before the REQUEST command is accepted, that command is not processed and you will receive this message:

/OLD: NO PRIOR REQUEST CMD.

## ON-LINE TESTS FOR CLAS AND MODEMS

Three tests allow you to do basic data and line turn-around to determine whether all data and status are normal. You can test one or more CLAs concurrently without impacting services to other lines in the network.

You can use commands to test communication lines by using these three tests:

A Communications Line Adapter (CLA) internal loopback test, which tests all CLA logic except modem drivers and receivers.

An external loopback test, which isolates modem and transmission line problems. Some of the tests require that the modem have loopback features. Be sure to install the loopback jumper plug during these tests.

 ${\tt CLA}$  modem loopback test, which tests modem drivers and receivers.

Table 4-1 shows modem classes.

## Start Testing of CLA Logic Using Internal Loopback Test

Use this command to test the CLA logic in the designated NPU:

TST, Test the CLA logic in the NPU NPU, and

INT Starts CLA internal loopback test

ii Port number (CLA address, 01-FE)

j CLA type

MSG

0 is synchronous RS-232 (2560-1)

l is asynchronous (2561-1)

2 is synchronous non RS-232 (2560-2,)

3 is synchronous SDLC (2563-1)

4 is synchronous SDLC non RS-232 buffered (2563-2)

kk Modem class (see table 4-1)

The ii,j, and kk parameters must appear exactly as shown. Insert leading zeros if necessary.

TABLE 4-1. MODEM CLASSES

Test Mode	CLA Type	Maximum Modem Speed	Modem Class (Hexadecimal)	Modems <sup>†</sup>
Internal and External Loopback	A11	Not Applicable	00	None
Modem Loopback	2560-1 2560-2 2560-3 2563-1 2563-2	Not Applicable	01	201B, 201A, 201C, 201D 208A, 208B, 209 358-2
	2561-1 Async	100 110 120 134.5 150 300 600 800 1050 1200 1600 2400 4800 9600	02 03 04 05 06 07 08 09 0A 0B 0D 0F 10	103 series, 113A, 113B, VA 3405 A thru G VA 3405 A thru G VA 3405 A thru G 358-1

<sup>†</sup>The modems listed constitute only a small fraction of all possible modems offerred by a variety of manufacturers.

Table 4-2 gives the responses you can expect to receive after starting this test.

This test continues either until you stop it or until an error code occurs followed by an associated error message. These error codes and their significance are shown in table 4-3.

Figure 4-1 shows the CLA status associated with the error codes in table 4-3.

H3 Stop Testing of CLA Logic Using Internal Loopback Test

Use this command to end testing of the line or trunk:

$$\left\{ \begin{matrix} TST \\ TS \end{matrix} \right\} \text{ , } \left\{ \begin{matrix} NPU \\ NP \end{matrix} \right\} \text{ =npu-name, } \left\{ \begin{matrix} MSG \\ MS \end{matrix} \right\} \text{ = } \left\{ \begin{matrix} TERM \\ T \end{matrix} \right\} \text{ ,ii}$$

TERM Terminates the test

ii Port number (CLA address, 01-FE)

Table 4-4 gives you the responses generated by this command if the test completed successfully or if you entered the command incorrectly.

TABLE 4-2. RESPONSES TO START ON-LINE DIAGNOSTIC TEST COMMAND FROM NOP CONSOLE

Initial Response	Meaning
From NPU-name	Test started
PORT 11 STARTED	
From NPU-name	No such port number
PORT 11 INV PORT	
From NPU-name	No such type of CLA
PORT ii INV CLA TYPE	
From NPU-name	Undefined test mode was entered (was not one of the
PORT 11 INV TEST MODE	following: INT, EXT, or MOD)
From NPU-name	That port was not taken out of service before starting
PORT ii NOT DISABLED	diagnostics
From NPU-name	Some diagnostic test is already being run on this port
PORT ii TEST IN PROC.	
From NPU-name	System is low on buffers
PORT ii LOW BUFFERS	
From NPU-name	Modem class parameter is outside the allowable range
PORT 11 INV MODEM CLS	
Second Response -	
If Error Occurred	Meaning
From NPU-name	Error responses are summarized in table 4-4. See also
PORT ii ERROR (error data)	table 4-7, DDLTs.

## PORT pp ERROR xx,yy,qqqq,rrrr

where:

pр = port number

= error code (see below)

= number of subtests being performed at error time

DATA 1

qqqq = 1 - NA for N-type errors 2 - expected CLA status for S-type errors

3 - operator/default data for D-type errors

DATA 2

rrrr = 1 - NA for N-type errors 2 - received CLA status for S-type errors

3 - received data for D-type errors

xx = Error Code (Hexadecimal)

Error Code	Significance	Error Type
00	Not legal in error message	
01	Unsolicited input detected	N
02	Unsolicited output data demand detected (ODD)	N
03	Input loop error (ILE)	s
04	Output loop error (OLE)	s
05	Parity error	s
06	Framing error	s
07	Data transfer overrun (DTO)	s
08	Next character not available (NCNA)	s
09	No CLA status after CLA status requested	s
0A	Unsolicited CLA status	s
0B	CLA status not cleared after input supervision ON (ISON)	s
0C	No status after request to send (RTS) or input status request (ISR)	s
0 D	No clear to send (CTS) after RTS	s
0E	No status after data terminal ready (DTR)	s
0F	No data set ready (DSR) after DTR	s
10	No signal quality detect (SQD) after DTR	s
11	No ring indicator (RI) after DTR	s
12	No status after secondary request to send (SRTS)	s
13	No secondary received line signal detector (SRLSD) after SRTS	s
14	No CLA status after local mode (LM)	s
15	No data carrier detect (DCD) after LM	s
16	Unsolicited status after originate mode (OM)	s
17	No status or improper operation of RI after terminal busy (TB)	s
18	No status after new sync (NSYN)	s
19	Improper operation of DCD, RI, or quality monitor (QM) or unsolicited status after NSYN	S
1A	No RI after RTS	s
1B	Unsolicited status after LM	s

TABLE 4-3. ON-LINE DIAGNOSTIC TEST ERROR CODES (Sheet 2 of 2)

Error Code	Significance	Error Type
1C	Input data timeout during data verification test (DVT)	N
1D	Unsolicited status during DVT	S
1E	No CRCs received during DVT of SDLC CLA	N
	Test Conditions	
1F	DVT failed (synchronous CLA even parity)	D
20	DVT failed (synchronous CLA odd parity)	D
21	DVT failed (synchronous CLA no parity)	D
22	DVT failed (HDLC CLA)	D
23	DVT failed (HDLC CLA)	D
24	DVT failed (HDLC CLA)	D
25	DVT failed (async CLA, 40 baud, even parity, 1 stop bit)	D -
26	DVT failed (async CLA, 85.4 baud, odd parity, 2 stop bits)	D
27	DVT failed (async CLA, 100 baud, no parity, 1 stop bit)	D
28	DVT failed (async CLA, 110 baud, even parity, 2 stop bits)	D
29	DVT failed (async CLA, 120 baud, odd parity, 1 stop bit)	D
2 A	DVT failed (async CLA, 134.5 baud, no parity, 2 stop bits)	D
2B	DVT failed (async CLA, 150 baud, even parity, 1 stop bit)	D
2C	DVT failed (async CLA, 300 baud, odd parity, 2 stop bits)	D
2D	DVT failed (async CLA, 600 baud, no parity, 1 stop bit)	D
2E	DVT failed (async CLA, 800 baud, even parity, 2 stop bits)	D
2F	DVT failed (async CLA, 1050 baud, odd parity, 1 stop bit)	D
30	DVT failed (async CLA, 1200 baud, no parity, 2 stop bits)	D
31	DVT failed (async CLA, 1600 baud, even parity, 1 stop bit)	D
32	DVT failed (async CLA, 1600 baud, odd parity, 2 stop bits)	D
33	DVT failed (async CLA, 2400 baud, no parity, 1 stop bit)	D
34	DVT failed (async CLA, 2400 baud, even parity, 2 stop bits)	D
35	DVT failed (async CLA, 4800 baud, odd parity, 1 stop bit)	D
36	DVT failed (async CLA, 9600 baud, no parity, 2 stop bits)	D D
37	DVT failed (async CLA, 9600 baud, even parity, 1 stop bit)	D ,
38	Multiplex subsystem buffer threshold detected	N N

## LEGEND:

- N qqqq = not used (ignore values) rrrr = not used (ignore values)
- S qqqq is expected CLA status (see figure 4-1)<sup>†</sup> rrrr is received CLA status (see figure 4-1)
- D qqqq is input data for verification  $^{\dagger}$  rrrr is expected data for verification  $^{\dagger\dagger}$

†qqqq will be X'FFFF' if no data or status is expected but is received.

<sup>††</sup>rrr will be X'FFFF' if no data or status is received but is expected.




Figure 4-1. CLA Status Word

TABLE 4-4. RESPONSES TO TERMINATE DIAGNOSTIC TEST COMMAND FROM NOP CONSOLE

Initial Response	Meaning
From NPU-name PORT ii TEST CMPL - OK	CLA line/trunk test completed without errors
From NPU-name PORT ii INV PORT	No such CLA port number
From NPU-name PORT ii NOT IN PROC.	CLA line/trunk with that number was not doing diag- nostics, or the diagnostics stopped because an error was detected and an error response was already given

## Start Testing Lines Using External Loopback Test

First, make sure that the proper external loopback plug is installed. Table 4-5 shows the correct connector number for each type of CLA. Also, ensure that all CLA interface switches are open. Only those switches shown in table 4-6 should be closed.

TABLE 4-5. CONNECTORS NEEDED TO RUN EXTERNAL LOOPBACK TEST

CLA Product Number	Connector Number
2560-1	74715000
2561-1	74715600
2563-2	74877033
2560-2 2560-3	None. Cannot run external loopback test

TABLE 4-6. CLA INTERFACE SWITCH SETTINGS

CLA Product Number	CLA Interface Switches Set to Closed Position <sup>†</sup>
2560-1	2.4 kHz
2561-1	OM an SRTS 19
2563-1	QM and 2.4 kHz
2563-2	2.4 kHz

<sup>†</sup> All other CLA interface switches should be in the open position.

Use this command to isolate modem and line problems:

TST, Test for modem and line problems NPU, and  $\ensuremath{\mathsf{MSG}}$ 

EXT External loopback

ii Port number (CLA address)

j CLA type

0 is synchronous RS-232 (2560-1)
1 is asynchronous (2561-1)
2 is synchronous non RS-232 (2560-2)
3 is synchronous SDLC (2563-1)
4 is synchronous SDLC buffered
(2563-2)

kk Modem class (see table 4-1)

Enter the ii, j, and kk parameters exactly as shown. Insert leading zeros if necessary.

Table 4-2 gives the responses you can expect to receive after starting this test.

This test continues either until you stop it or until an error code occurs followed by an associated error message. These error codes and their significance are shown in table 4-3.

## Stop Testing Lines Using External Loopback Test

Use this command to end testing of a line or a trunk:

Except for EXT, j, and kk, this command is identical to that given for starting testing of a line or a trunk in external loopback mode.

This test continues either until you stop it or until an error code occurs followed by an associated error message. These error codes and their significance are shown in table 4-3.

Table 4-4 gives the responses generated by this command if the test completed successfully or if you entered the command incorrectly.

Remove the external loopback plug.

## Start Testing Modem Drivers Using Modem Loopback Test

Use this command to begin testing modem drivers and receivers:

TST. Start testing modem drivers and receivers

MSG.

and

MOD

MOD Modem loopback

ii Port number (CLA address)

i CLA type

0 is synchronous RS-232 (2560-1)

1 is asynchronous (2561-1)

2 is synchronous non RS-232 (2560-2)

3 is synchronous SDLC (2563-1)

4 is synchronous SDLC non RS-232

buffered (2563-2)

kk Modem class (see table 4-1)

Enter the ii, j, and kk parameters exactly as shown. Insert leading zeros if necessary.

Table 4-2 gives the responses you can expect to receive after starting this test.

This test continues either until you stop it or until an error code occurs followed by an associated error message. These error codes and their significance are shown in table 4-3.

## Stop Testing Modem Drivers Using Modem Loopback Test

Use this command to end testing of modem drivers and receivers:

Except for TERM, j, and kk, this command is identical to the one for starting testing of modem drivers and receivers.

This test continues either until you stop it or until an error code occurs followed by an associated error message. These error codes and their significance are shown in table 4-3.

Table 4-4 gives you the responses generated by this command if you completed this test successfuly or if you entered this command incorrectly.

#### DISCONNECT FROM ON-LINE TESTING

After completing on-line testing for the internal loopback test, the modem loopback test, or the CLA external loopback test, use this command to break the connection with on-line diagnostics:

$$\begin{cases} TST \\ TS \end{cases}, \begin{cases} NPU \\ NP \end{cases} = npu-name, \begin{cases} DROP \\ DR \end{cases}$$

TST, Disconnect from testing NPU,

and

DROP

This command ends all tasks current1v being processed by the NPU.

#### REENABLE A TRUNK OR A LINE

After you have tested a trunk or a line and found that it is operating properly, you must reenable that trunk or line.

Use this command to reenable a previously disabled trunk:

Use this command to reenable a previously disabled communications line:

## DIAGNOSTIC DECISION LOGIC TABLES FOR ON-LINE DIAGNOSTICS

Figure 4-2 is a summary of the actions indicated in the on-line diagnostic DDLTs. Table 4-7 gives the individual DDLTs.




Figure 4-2. Flowchart for On-Line Diagnostic DDLT (Sheet 1 of 2)




Figure 4-2. Flowchart for On-Line Diagnostic DDLT (Sheet 2 of 2)

#### ASSUME

- 1. The Communications Control Program (CCP) is loaded, initialized and operating at least to the idle state.
- 2. MLIA is working since the system has not halted.
- 3. After each corrective action, the test should be retried.
- 4. The operator is familiar with the DDLT format.
- 5. The operating instructions for the on-line diagnostics are given in text.

TABLE 4-7. ON-LINE DIAGNOSTICS DDLT (Sheet 2 of 14)

Diagnostic Index ASSUME						
CONDITATIONS		F	ESPO	NSES	3	
CONDITIONS	1	2	3	4	5	6
l. Is diagnostic response = NO OVERLAY PROGRAM?	N	N	N	N.	N	Y
2. Is diagnostic response = PORT ii <sup>†</sup> STARTED?	N	N	N	N	Y	_
3. Is diagnostic response = PORT ii INV PORT?	N	N	N	Y	-	_
4. Is diagnostic response = PORT ii INV CLA TYPE?	N	N	Y	_	-	
5. Is diagnostic response = PORT ii INV TEST MODE?	N	Y	_	-	-	-
ACTIONS			SEQ	UENCI	3	
l. Go to sheet 3.	х	-	_	-	-	Ŀ
2. No overlay program loaded. Request diagnostic overlay be loaded.		-	<u> </u>	-	-	X
3. Test has started; no action required. Wait for error message or wait for test complete message. Go to sheet 4 to continue DDLT on either of these messages.		-	_	-	х	_
4. Port number is outside the allowable range of port numbers. Check for proper port number and reissue command.		_	-	х	-	
5. Not a valid CLA type. Check for proper CLA type and reissue command.		_	х	-	_	
<ol> <li>An undefined test mode was entered (was not one of the following: INT, EXT, or MOD). Check for proper test mode and reissue command.</li> </ol>	-	x	-	-	-	

#### Diagnostic Index ASSUME RESPONSES CONDITIONS Is diagnostic response = PORT ii NOT DISABLED? N N 2. Is diagnostic response = PORT ii TEST IN PROC.? N N N N Y Is diagnostic response = PORT ii LOW BUFFERS? N N Y N Is diagnostic response = PORT ii INV MODEM CLS? N N Y 5. Is diagnostic response = PORT ii NOT IN PROC.? Y N ACTIONS SEQUENCE 1. Go to sheet 4. X Port was not taken out of service before starting diagnostics. Contact the NOP or HOP and have the desired line/trunk disabled. X 3. Some diagnostic test is already being run on this port. Check for proper port X 4. System is low on buffers. Reissue command later. X 5. Modem class parameter is outside the allowable range. Check modem class and reissue command. X 6. CLA line/trunk number was not doing diagnostics, or diagnostics stopped because an error response was already given. Check that the proper CLA port number was used in each message. †ii = CLA port number

## Diagnostic Index ASSUME RESPONSES CONDITIONS 2 3 N Y 1. Is diagnostic response = PORT ii TEST CMPL - OK? Y 2. Is first part of diagnostic response = PORT ii $ERROR^{\dagger}$ ? N SEQUENCE ACTIONS 1. Terminate test, start next test or terminate diagnostics. 2. CLA line/trunk test found no errors. No action required. Х 3. An error has been detected during CLA testing. Go to sheet 5. †Test data follows in hexadecimal format: Not meaningful for N-type tests bbbb aaaa уу returned status (S) returned data (D) expected status (S) input data (D) Lsubtest in process at stop Lerror code The subtest is an index to the control parameters table (see Link Edit testing for diagnostics). An exception exists if the test has reached the data turnaround stage. In that case, subtest is an entry in the compare data address table.

Dia	gnostic Index		
	ASSUME		
		RESP	onses
	CONDITIONS		2
1.	Is the next piece of the diagnostic response (error code) = 00 or $\geq$ 39?	N	Y
	ACTIONS	SEQU	ENCE
1.	Go to sheet 6.	-	х
2.	This is not a legal response number for on-line diagnostics. Check over previous console messages to see if the console is misinterpreting some characters. If so, run the NPU off-line console diagnostics.	1	-
3.	Run the ODS off-line diagnostics on the mainframe.	2	-

TABLE 4-7. ON-LINE DIAGNOSTICS DDLT (Sheet 6 of 14)

Ch	ecking CLA Type				
	ASSUME				
	CONDITIONS		RESP	ONSE	s
		1	2	3	4
1.	Look at the port number (CLA address) in the diagnostic test response. Is this CLA being tested?	Y	Y	N	N
2.	Does the CLA (whose address is in the diagnostic test reponse at the console) product number match the type of CLA test being run? (Type 00 = 2560-1, type 01 = 2561-1, type 02 = 2560-2 or 2560-3, type 03 = 2563-1, or type 04 = 2563-2)	Y	N	_	_
3.	This is a system anomaly. Is this the second time down this path?	-	-	Y	N
	ACTIONS		SEQ	UENC	E
1.	Go to sheet 7.	х	-	-	<u> </u>
2.	Rerun test using the proper type of CLA test.	-	х	-	-
3.	Rerun the diagnostics on all the lines that were being tested when this error occurred. Keep the commands in the same order as previously run.	-	-	_	х
4.	Check over previous console messages to see if the console is misinterpreting some characters. If so, run off-line MSMP console diagnostics.	_	_	1	_
5.	Run the ODS off-line diagnostics on the mainframe.	-	_	2	_

	ASSUME			
		RE	SPON	SE
	CONDITIONS	1	2	
ι.	Look at test mode part of the start diagnostics command for this CLA. Is this CLA being tested in the internal loopback mode?	Y	N	
2.	Is this CLA being tested in the external loopback mode?	_	Y	
3.	Is this CLA being tested in the modem loopback mode?	-	- 1	
	ACTIONS	SE	QUEN	CE
	Go to sheet 8.	х	-	
•	Go to sheet 9.	-	х	
١.	Go to sheet 10.	-	-	Γ

TABLE 4-7. ON-LINE DIAGNOSTICS DDLT (Sheet 8 of 14)

	ASSUME				
		F	RESPO	ONSES	3
	CONDITIONS	1	2	3	4
1.	Look at the data following the word ERROR in the diagnostic test response at the console. Is this the response code. Is the response code = 01, 02, or 0A.?	Y	N	N	N
2.	Is the response code = 03 thru 09, or 0B thru 37?	-	Y	N	N
3.	Is the response code = 38?	-	-	Y	N
	ACTIONS	SEQUENCE		3	
1.	Check to see if there is more than one CLA set to the address given in the port number in the diagnostic test response at the console. If there are duplicated addreses, change them to give each CLA a unique address.	1	-	. <b>-</b>	-
2.	Replace the CLA whose address is in the port number in the diagnostic test response at the console.	2	1	-	_
3.	Replace the primary loop multiplex in the loop multiplexer card cage which contains the above CLA.	3	2	_	-
4.	The multiplexer subsystem is low on buffers. Reissue the test command.		_	х	_
	You have misinterpreted the directions. Return to sheet 2 and run DDLT again.	l _	_	_	,

TABLE 4-7. ON-LINE DIAGNOSTICS DDLT (Sheet 9 of 14)

CLA	External Loopback Test  ASSUME			
	CONDITIONS	RE	SPON	SES
1.	Look at the port number in the diagnostic test response. This is the CLA address.	1	2	3
2.	Is it the proper external test connector for this CLA product number? 2560-1 uses connector 74715000, 2561-1 uses connector 74715600, 2563-1 uses connector 74870830, 2563-2 uses connector 74877033. 2560-2 and 2560-3 cannot run an external loopback test.	Y	Y	_ N
	ACTIONS	SE	QUEN	CE
1.	Go to sheet 8.	х	_	-
2.	Rerun test with proper external test connector.	-	Х	х

#### CLA Modem Loopback Test ASSUME RESPONSES CONDITIONS 5 6 2 3 4 1. Is the communications line (address is in the port number of the diagnostic test response at the console) looped back towards the CLA at the local modem? N N N N 2. Is the communications line looped back towards the CLA at the local telephone Y N N N central office? 3. Is the communications line looped back towards the CLA at the remote telephone N N central office? Y N N 4. Is the communications line looped back towards the CLA at the remote modem? Y N 5. Are you sure there is a loopback condition in the communications line? SEQUENCE ACTIONS X 1. Go to sheet 11. X Go to sheet 12. X 3. Go to sheet 13. X 4. Go to sheet 14. 5. Choose the one of the four above loopback point descriptions that is the closest match to your loopback point and follow its directions. X 6. This mode of testing requires a loopback towards the CLA in the communications line between the CLA and the terminal. Place the loopback of your choice in the communications line and rerun the test.

CI	CLA Local Modem Loopback Test				
	ASSUME				
	CONDITIONS	RE	SPON	SES	
	CONDITIONS			3	
1.	<ol> <li>Look at the data following the word ERROR in the diagnostic test response at the console. This is the error code. Is the error code = 01 thru 38?</li> </ol>		Y	N	
2.	Have you already tested the CLA with the external loopback test using an external test connector successfully? If the CLA type does not allow an external loopback test, have you run the internal loopback test successfully?	Y	N	-	
	ACTIONS	SE	QUEN	CE	
1.	Replace the modem cable.	1	-		
2.	Replace the CLA.	2	-	-	
3.	Replace the modem.	3	-	-	
4.	Run the CLA external loopback test.	-	Х	-	
5.	You have misinterpreted the directions. Return to sheet 5 and run DDLT again.	-	-	х	

#### CLA Loopback at Local Central Office Test ASSUME RESPONSES CONDITIONS 3 4 1. Look at the data following the word ERROR in the diagnostic test response at the Y Y Y N console. This is the error code. Is the error code = 01 thru 38.? 2. Have you already tested the CLA with the external loopback test using an external test connector successfully? If the CLA type does not allow an external loopback test, have N Y Y you run the internal loopback test successfully? 3. Have you already run the modem loopback test on this communications line with the local Y modem looped back towards the CLA successfully? SEQUENCE ACTIONS 1 1. Replace the local modem. 2 5 2. Have local telephone central office check the local telephone line. 3. Run the CLA external loopback test. X X 4. You have misinterpreted the directions. Return to sheet 5 and run DDLT again. 5. Run the modem loopback test on this communications line with the local modem looped back towards the CLA. 1 2 6. If the local modem has no loopback, replace the modem cable.

7. If the local modem has no loopback, replace the CLA.

3

## CLA Loopback at Remote Telephone Central Office

## ASSUME

	· ·							
			RESPONSES					
	CONDITIONS	1	2	3	4	5		
1.	Look at the data following the word ERROR in the diagnostic test response. This is the error code. Is the error code = 01 thru 38.?	Y	Y	Y	Y	N		
2.	Have you already tested the CLA with the external loopback test using an external test connector successfully? If the CLA type does not allow an external loopback test, have you run the internal loopback test successfully?	Y	Y	Y	N	_		
3.	Have you already run the modem loopback test on this communications line with the local modem looped back towards the CLA successfully?	Y	Y	N	-	-		
4.	Have you already run the modem loopback test on this communications line with the local telephone central office looped back towards the CLA successfully?	Y	N	-	1	-		
	ACTIONS	SEQUENCE						
1.	Have the telephone company check the line from the local central office to the remote central office.	х	-	_	-	-		
2.	Run the modem loopback test on this communications line with the local central telephone office looped back towards the CLA.	-	X	-	-	-		
3.	Run the modem loopback test on this communications line with the local modem looped back towards the CLA.	_	-	X	_	-		
4.	Run the CLA external loopback test.	-	-	1	х	-		
5.	You have misinterpreted the directions. Return to sheet 5 and run DDLT again.	-	-	-	-	х		

## CLA Loopback at Remote Modem

### ASSUME

			RESPONSES				
	CONDITIONS	1	2	3	4	5	6
1.	Look at the data following the word ERROR in the diagnostic test response at the console. This is the error code. Is the error code = 00 thru 38?	Y	Y	Y	Y	Y	N
2.	Have you already tested the CLA with the external loopback test using an external test connector successfully? If the CLA type does not allow an external loopback test, have you run the internal loopback test successfully?	Y	Y	Y	Y	N	
3.	Have you already run the modem loopback test on this communications line with the local modem looped back towards the CLA successfully?	Y	Y	Y	N	-	_
4.	Have you already run the modem loopback test on this communications line with the local telephone central office looped back towards the CLA successfully?	Y	Y	Ŋ	1	-	
5.	Have you already run the modem loopback test on this communications line with the remote telephone central office looped back towards the CLA successfully?	Y	N	-	-	-	_
	ACTIONS		SEQUENCE				
1.	Replace the remote modem.	1	_	۲_	_	-	<u>-</u>
2.	Have the remote telephone central office check the telephone line to the remote modem.	2	_	_	_	_	_
3.	Run the modem loopback test on this communications line with the remote telephone central office looped back towards the CLA.	_	х	-	_	-	_
4.	Run the modem loopback test on this communications line with the local telephone central office looped back towards the CLA.	_	-	х	-	_	_
5.	Run the modem loopback test on this communications line with the local modem looped back towards the CLA.	_	_	-	х	_	L
6.	Run the CLA external loopback test.	<u> </u>	-	-	Ŀ	х	<u> </u> -
7.	You have misinterpreted the directions. Return to sheet 5 and run DDLT again.	-	-	-	-	-	х

# COMMUNICATIONS LINE FAULT ISOLATION

Use the on-line diagnostic test programs to isolate suspected faulty communications line problems to a particular piece of equipment. Three basic program modes are available within the on-line diagnostic terminal interface program (TIP) to accomplish this testing.

Two of the available test modes (CLA internal loopback mode and CLA external loopback mode using an external test connector) test the CLAs. The third mode (external data loopback mode), used after CLA operation is verified by the CLA modes, tests the local and remote modems and the transmission line facilities. The external data loopback mode includes analog and digital loopback tests, remote tests, self tests, and transceiver analog loopback tests.

## CLA INTERNAL AND EXTERNAL LOOPBACK TEST MODES

In the CLA internal loopback test mode, all CLA logic except the modem signal drivers and receivers are tested.

You can use the CLA external loopback mode only with CLA types 2560-1, 2561-1, 2563-1, and 2563-2. CLA type 2560-1 uses external test connector type 74715000, CLA type 2561-1 uses external test connector type 74715600, CLA type 2563-1 uses external test connector type 74870830, and CLA type 2563-2 uses external test connector type 74877033. These connectors are installed at the CLA in place of the normal connector to the local modem.

If you anticipate external loopback and you use a modem that lacks special test switches, inform the telephone company of any special connections to be made. See appendix C.

#### **EXTERNAL DATA LOOPBACK MODE**

Use the external data loopback mode after you verify CLA operation by running the CLA internal and external loopback mode tests.

#### PRELIMINARY INFORMATION REQUIRED

Before running the external data loopback tests, you should know:

The type of modem or Data Set (Bell 207C, CDC 358-2, and so forth) used on the line or lines to be tested.

The test modes (analog loopback, digital loopback, self test, and so forth) available for use with the modem or modems to be tested. See the applicable modem manual or Bell Telephone Data Set specifications for this information and/or step-by-step instructions for testing. Table 4-8 lists some of the more common modems and the test modes available for each.


The type of service (dial-up or dedicated). Dedicated lines have more loopback points than do dial-up lines.

The type of line operation used (simplex, half duplex, or full duplex). Simplex lines cannot be looped back past the analog loopback of the local modem. Half-duplex lines echo back transmitted data to the received data line at the modem interface. Full-duplex lines handle all types of loopback points.

TABLE 4-8. COMMON MODEMS AND LOOPBACK
TESTS AVAILABLE

Modem Type	Loopback Tests Available
Bell 103	Remote test
Bell 103A	Analog test, remote test
Bell 113A	Remote test
Bell 201A	Remote test
Bell 201B	Remote test
Bell 201C	Analog test, digital test, self test
Bell 202	Remote test
Bell 202S	Analog test, remote test
Bell 202T	Analog test, remote test
Bell 208A	Analog test, digital test, self test
Bell 208B	Analog test, self test
CDC 358-2	Transceiver analog loopback test

After obtaining this information, refer to figure 4-3 to determine the possible loopback points available for the particular configuration to be tested. Thereafter, adapt the suggested loopback test sequence contained in this section for the configuration to be tested. The suggested procedure assumes a full-duplex line with modems that accept all test modes available. If a proper loopback test fails, replace the faulty equipment or call the maintenance personnel responsible for the indicated faulty equipment.



# LOOPBACK POINTS

- 1 CLA IN INTERNAL LOOPBACK MODE
- FOR CLA TYPE 2561-1, SET TO ECHOPLEX MODE (ECHO ON) AND RECEIVED DATA IS LOOPED BACK TO TRANSMIT DATA SO THAT THE DATA RECEIVED FROM THE TERMINAL IS SENT BACK TO THE TERMINAL.
- USING THE EXTERNAL LOOPBACK CONNECTOR AT THE RS-232 CONNECTOR ON CLA TYPES 2560-1, 2561-1, 2563-1, AND 2563-2 (2560-1 USES LOOPBACK CONNECTOR 74715000, 2561-1 USES LOOPBACK CONNECTOR 74715600, 2563-1 USES LOOPBACK CONNECTOR 74870830, AND 2563-2 USES LOOPBACK CONNECTOR 74877033).
- 4 & (2) ANALOG LOOPBACK TEST MODE SWITCH ON MODEM CAUSES ANALOG LOOPBACK TOWARD TERMINAL (CLA ACTS AS TERMINAL).
- (5) & (1) DIGITAL LOOPBACK TEST MODE SWITCH ON MODEM CAUSES DIGITAL LOOPBACK TOWARD TELEPHONE LINES.
- 6 & (3) REMOTE TEST MODE SWITCH ON TELEPHONE DATA SETS (MODEMS) CAUSES SPECIAL LOOPBACK TOWARD TELEPHONE LINES FOR TELEPHONE COMPANY TESTING ONLY. THIS IS HARDWARE TESTING AND IS NOT INCLUDED IN THIS MANUAL.
- 7 THRU (10) ANALOG LOOPBACK ON TELEPHONE COMPANY TEST PANEL TOWARD EITHER TERMINAL (BY SPECIAL ARRANGEMENT WITH TELEPHONE COMPANY). THIS IS HARDWARE TESTING AND IS NOT DESCRIBED IN THIS MANUAL.
  - LOCAL MODE SWITCH ON TERMINAL CAUSES LOCAL TESTING OF TERMINAL. THIS HARDWARE TEST IS DESCRIBED IN THE APPROPRIATE HARDWARE MANUAL.
- (15) & (16) HALF-DUPLEX LINES WILL LOOP TRANSMIT DATA BACK TO RECEIVE DATA AT MODEM INTERFACE.
- (1) & (18) SELF-TEST MODE SWITCH ON MODEM CAUSES WORD GENERATOR AND WORD COMPARATOR BUILT INTO MODEM TO TEST MODEM LOGIC. REFER TO REFERENCE MANUAL FOR MODEM OR DATA SET TYPE. THIS IS AN OFF-LINE TEST THAT IS NOT DESCRIBED IN THIS MANUAL.

Figure 4-3. Loopback Points for Test Selection

## **EXTERNAL DATA LOOPBACK TESTS**

The external data loopback mode includes analog and digital loopback tests, remote tests, self tests, and transceiver analog loopback tests. Refer to table 4-8 for the test mode or modes that apply to each of the common types of modems or data sets.

In the analog loopback test (activated by the analog loopback test mode switch on the modem) you can use either the local or remote modem to loop analog data back toward the terminal (with the CLA acting as a terminal for the local modem). The digital analog loopback test is activated by the digital loopback test switch on the modem and loops digital data from the modem back toward the communications lines (local or remote central office).

Use the remote test mode only when requested by the telephone company maintenance personnel for telephone company testing of the modem and telephone lines.

If the modem being tested includes word generator and word comparator facilities, activating the self-test mode switch at the modem enables the modem to test its own logic. Additionally, for the CDC type 358-2 modem, the transceiver analog loopback test mode connects transmit data by jumper wire back to the receive data side of the modem.

# SUGGESTED LOOPBACK TEST SEQUENCE

When a communications line failure is suspected, run the following tests in the sequence indicated to isolate the problem to a particular piece of equipment or section of the transmission line or system cabling. If any test fails, replace the faulty equipment or call the maintenance personnel responsible for the indicated faulty equipment and report the test indications so that the trouble may be corrected.

- Execute the CLA internal loopback test to test all CLA logic except the modem signal drivers and receivers.
  - a. If the test fails, it indicates that the CLA is faulty. Replace the CLA.
  - b. If the test does not fail, proceed to the next step.
- 2. If the CLA is type 2560-1, install external test connector type 74715000, if type 2561-1, install external test connector type 74715600, if type 2563-1, install external test connector type 74870830, and if type 2563-2, install

external test connector 74877033. Execute the CLA external loopback test to test all logic of the CLA, including the modem signal drivers and receivers.

- a. If the test fails, it indicates that the CLA modem signal drivers or receivers are faulty. Replace the CLA.
- b. If the test does not fail, proceed to the next step.
- With the analog test button on the local modem depressed, execute the external data loopback test. This tests the data trnasmission capability of the local modem and the CLA-to-local modem cable.
  - a. If the test fails, either the local modem or the CLA-to-local modem cable is faulty. Proceed to step 6.
  - b. If the test does not fail, proceed to the next step.
- 4. Release the analog test button on the local modem and request that the digital test button on the remote modem be pressed. Again run the external data loopback test. This tests the transmission line and remote modem.
  - a. If the test fails, either the transmission line or remote modem is faulty. Proceed to step 8.
  - b. If the test does not fail, proceed to the next step.
- 5. Request release of the digital test button on the remote modem. If no errors were detected in steps 1 through 4, the CLA modems and transmission line may be assumed to be working properly. Request testing of the remote terminal and the remote terminal-to-remote modem cable using any available diagnostics. See steps 10 through 12.
- 6. Enter this step from step 3. Release the analog test button on the local modem. If the local modem has an analog loopback self-test mode (such as Bell 208A modem), run that test as described in the modem (Data Set) manual.
  - a. If the test fails, the local modem is bad. Request repair or replacement of the local modem.
  - b. If the test does not fail or if the modem does not have a self-test mode, proceed to the next step.

- Replace the CLA-to-local modem cable and, with the analog test button on the local modem depressed, execute the external data loopback test.
  - a. If the test fails and the modem is a telephone company modem without the self-test mode, read appendixes C, D, and E before calling the telephone company repair service and requesting assistance to test the modem and telephone line. Follow telephone company directions to test the modem and line.
  - b. If the test does not fail, the trouble was in the CLA-to-local modem cable and has been corrected.
- 8. Enter this step from step 4. If the remote modem has an analog loopback self-test mode, run that test as described in the modem (Data Set) manual.
  - a. If the test fails, the remote modem is bad. Request repair or replacement of the remote modem.
  - b. If the test does not fail or if the modem does not have a self-test mode, proceed to the next step.
- 9. If the modem is a telephone company modem without self-test mode, read appendixes C, D, and E before calling the telephone company repair service and requesting assistance to test the modem and telephone line. Follow the telephone company directions to test the modem and line.
  - a. If the test fails, request repair or replacement of the indicated faulty equipment.

- b. If the test does not fail or the modem is not a telephone company modem, proceed to the next step.
- 10. If the local and remote modem both tested properly, but step 4 continues to fail, a transmission line problem is indicated. Request the telephone company to loop back the telepone line at the voice frequency test panel in the local central office to return the signal toward the CLA. Execute the external data loopback test to verify that the telephone line is working properly to the local central office.
  - a. If this test fails, the telephone line between the local central office is bad. Have the telephone company check that line.
  - b. If this test does not fail, proceed to the next step.
- 11. Request the telepone company to loop back the telephone line at the voice frequency test panel in the remote central office and again run the external data loopback test.
  - a. If this test fails, have the telephone company check the telephone line.
  - b. If this test does not fail, proceed to the next step.
- 12. If the remote terminal is capable of self-test, or if the remote terminal can send messages that the terminal can copy on a looped back line request performance of those tests to indicate a fault in the remote terminal. Request repair or replacement of the terinal.

# **MESSAGES**

This appendix contains tables for alarm messages, CE error codes, CE message text definitions, statistics message text definitions, and halt codes.

TABLE A-1. ALARM MESSAGES

Message	Significance	Action	
From NPU-name MAINTENANCE ALARM COUPLER, n,ERROR=ec	Too many recent errors at host/NPU interface	Find coupler error codes in host dayfile.	
From NPU-name MAINTENANCE ALARM MLIA, ERROR=ec	Too many recent errors in mux subsystem	Find MLIA error codes in host dayfile.	
From NPU-name MAINTENANCE ALARM PORT, nn,ERROR=ec	Too many recent errors on this line (port)	Find CLA and modem messages in host dayfile.	

TABLE A-2. CE ERROR CODES

Code (Hexadecimal)	Significance	Action
00	Not used	None.
01	Not used	None.
02	Abnormal data set ready (DSR) or clear to send (CTS)	None. This is not an error. It occurs as part of the normal disconnect sequence on some lines.
03	Abnormal data carrier detect (DCD)	If this occurs occasionally, ignore it. Otherwise, call CE or analyst.
04	Unsolicited output data demand (ODD)	Check for CLA duplicate address or CLA address switch set between two numbers. This error should not cause concern unless it occurs frequently; if it does, call CE or analyst.
05	CLA address out of range	Same as code 04
06	Illegal mux loop cell format	Same as code 03
07	Unsolicited input	Same as code 04
08	Input mux loop error	Same as code 03
09	Output mux loop error	Same as code 03
OA.	TIP event receiver timeout for ODD	Same as code 03
ОВ	TIP event receiver timeout for DCD	Same as code 03
oc	Abnormal secondary data carrier detect (SDCD)	This is normal for channels using reverse channel interrupts. For other channels, call CE or analyst.
OD	Excessive CLA status messages	If this occurs frequenctly, call CE or analyst.

TABLE A-2. CE ERROR CODES (Contd)

Code (Hexadecimal)	Significance	Action
OE	Not used	None. The CE error code part of the CE message is evidently garbled.
OF	Next character not available (output)	Put CLAs in proper priority positions so higher speed or high-use channels are serviced first. If this does not solve problem, call CE or analyst.
10	Data transfer overrun (output)	Same as code OF
11	MLIA error status	Same as code 03
12 thru 1F	Not used	None. The CE error code part of the CE message is evidently garbled.
20	Deadman timeout	None. This can occur normally when the host locks out the 255x due to host processing higher priority batch tasks.
21	Spurious coupler interrupt	This will occur occasionally. If it occurs frequently, call CE or analyst.
22	Not used	Same as code OE.
23	Coupler hardware timeout on input	Same as code 03
24	Input data transfer terminated by PPU	Same as code 03
25	Not used	Same as code OE
26	Not used	Same as code OE
27	Output data transfer terminated by PPU	Same as code 03
28	Hardware timeout on output	Same as code 03
29	End of operation (EOP) missing	Same as code 03
2A	HASP TIP: Too many NAKs received	Same as code 03
2в	HASP TIP: Bad BCB from HASP TIP	Same as code 03
2C	HASP TIP: Bad BCB from HASP workstation	Same as code 03
2D	HASP TIP: Workstation restart	Not an error if workstation is restart- ing. Otherwise, call CE or analyst.
2E	Not used	Same as code OE
2 <b>F</b>	Not used	Same as code OE
30	Mode 4 TIP: No response from terminal	Contact terminal operator; have him verify that terminal is properly configured with all switches in correct position. Then call CE or analyst.
31	Mode 4 TIP: Bad response (unexpected response)	Same as code 30
32	Mode 4 TIP: Error response from terminal	Same as code 30
33	LIP: Timeout on idle block	Same as code 03
34	LIP: Protocol failure (no response to frame)	Same as code 03
35 36	LIP: Remote NPU rejected command from local NPU LIP: Bad frame detected by CRC	Same as code 03  An occasional bad frame is normal. If bad frames occur frequently, call CE or analyst.

TABLE A-3. CE ERROR MESSAGE TEXT DEFINITIONS

Error Codes (Hexadecimal)	Text Definition
01 thru 10	P 00 S1 S2
	where: P Port number (CLA address) S1 CLA status byte 1 (logical format) S1 and S2 not used for S2 CLA status byte 2 (logical format) ECs 04-07, 0A, 0B, 10
	CLA status byte 1
	bits CTS DSR DCD RI QM SQD ILE OLE
	CLA status byte 2
	bits DTO NCNA
	Unused Unused
	where: CTS Clear or send DSR Data Set ready DCD Data carrier detect RI Ring indicator QM Quality monitor SQD Signal quality detector ILE Input loop error OLE Output loop error DTO Data transfer overrun NCNA Next character not available
11	ET ILE LD AL
	where: ET Error type (00 = Error condition restored 01 = Error counts given 02 = MLIA failure)
	ILE Input loop error count  LD Lost data count  AL Alarm count
20	LS NS
	where: LS Last state NS Current state
21 thru 24	Where: CP and ST Coupler status word

TABLE A-3. CE ERROR MESSAGE TEXT DEFINITIONS (Contd)

Error Codes (Hexadecimal)	Text Definition
27 thru 29	CP ST
	where: CP and ST Coupler status word
2A thru 2D	P 00 where: P Port number (CLA address)
2E thru 32	where: P Port number (CLA address) CA Cluster address TA Terminal address DT Device type ERR Error count
33 thru 36	P 00 NID  where: P Port number (CLA address) NID Node ID of remote NPU
37	where: P Port number (CLA address) CA Cluster address TA Terminal address DT Device type TC Terminal class
Coupler Status Wo	
	Themoty parity error

TABLE A-4. STATISTICS MESSAGE TEXT DEFINITIONS

						Text	Defini	tion			
NPU ST	CATIS	TICS									:
	1	2	3	4	5	6	7	8	9	10	Statistics Word
Where	:	Word Word Word	2 3	Averag Lowest Number	ge numb regul	er of o	level r ejected	eache due	d to NPU	regulat	ion host
		Word Word Word Word	6 7 8 9	Averag Averag Numbei Numbei	ge char ge numb r of ac r of ac	acters er of v tive b tive b	per se worklis atch ou atch in	cond ts pr tput put d	sent t ocesse device evices	o host d per se s	
					sed of	two by	tes.				
	P	00	но	LRN	Word 1	Word 2	Word 3	Word 4	Word 5		
Where	:	P HO LRN		Host (	remote	node -	ID of s)	NPU a	t oppo	site end	of trunk
	Tr	unk/1	ine st	atist	ics wo	ds (2	bytes (	each)			
			2	Numbe:	r of bl	locks r naracte	eceive	i nsmitt	ed in	good blo	ocks
	Where NOTE:	Where:  NOTE: Eac  TRUNK/LINI  P  Where:	Where: Word Word Word Word Word Word Word Word	1	Where: Word 1 CPU ut Word 2 Averag Word 3 Lowest Word 4 Number Word 5 Averag Word 6 Averag Word 8 Number Word 9 Number Word 10 Number NOTE: Each word is compose  TRUNK/LINE STATISTICS  P 00 H0 LRN  Where: P Port HO Host LRN Link (alway)  Trunk/line statist Word 1 Number Word 2 Number	Where: Word 1 CPU utilizat Word 2 Average numb Word 3 Lowest regul Word 4 Number of in Word 5 Average char Word 6 Average char Word 7 Average numb Word 8 Number of ac Word 9 Number of ac Word 10 Number of co  NOTE: Each word is composed of  TRUNK/LINE STATISTICS  P 00 H0 LRN 1  Where: P Port H0 Host ordinal LRN Link remote (always 0 for  Trunk/line statistics word Word 1 Number of bl Word 2 Number of bl Word 2 Number of bl	NPU STATISTICS  1 2 3 4 5 6  Where: Word 1 CPU utilization % Word 2 Average number of word 3 Lowest regulation word 4 Number of inputs regulation word 5 Average characters word 6 Average characters word 7 Average number of word 8 Number of active be word 9 Number of active be word 10 Number of console of NOTE: Each word is composed of two by  TRUNK/LINE STATISTICS  P 00 H0 LRN 1 2  Where: P Port HO Host ordinal LRN Link remote node (always 0 for line)  Trunk/line statistics words (2 Word 1 Number of blocks to word 2 Number of 2 Number	NPU STATISTICS    1	Where: Word 1 CPU utilization % Word 2 Average number of data buffers Word 3 Lowest regulation level reache. Word 4 Number of inputs rejected due Word 5 Average characters per second Word 6 Average characters per second Word 7 Average number of worklists pr Word 8 Number of active batch output Word 9 Number of active batch input d Word 10 Number of console devices conn  NOTE: Each word is composed of two bytes.  TRUNK/LINE STATISTICS  TRUNK/LINE STATISTICS  P 00 H0 LRN 1 2 3 4  Where: P Port H0 Host ordinal LRN Link remote node - ID of NPU a (always 0 for lines)  Trunk/line statistics words (2 bytes each)  Word 1 Number of blocks transmitted Word 2 Number of blocks received	Where: Word 1 CPU utilization % Word 2 Average number of data buffers Word 3 Lowest regulation level reached Word 4 Number of inputs rejected due to NPU Word 5 Average characters per second receiv. Word 6 Average characters per second sent to Average characters per second sent word 7 Average number of worklists processe. Word 8 Number of active batch output devices Word 9 Number of active batch input devices Word 10 Number of console devices connected  NOTE: Each word is composed of two bytes.  TRUNK/LINE STATISTICS  Where: P Port HO Host ordinal LRN Link remote node - ID of NPU at opport (always 0 for lines)  Trunk/line statistics words (2 bytes each)  Word 1 Number of blocks transmitted Word 2 Number of blocks received	NPU STATISTICS    1

TABLE A-5. HALT CODES

Code (Hexadecimal)	Significance	Action
0000 0001	NPU master clear	Reapply power, reload CCP (for momentary failure).  Call CE or analyst.
0002 0003	Memory parity error  Program protect bit error	Call CE or analyst.  Check that software breakpoint not accidently left set. Call CE or analyst.

TABLE A-5. HALT CODES (Contd)

Code (Hexadecimal)	Significance	Action
0004	Interrupt count <0	Call CE or analyst.
0005	MLIA failure (reported by MLIA hardware status)	Call CE or analyst.
0006	Overran CIB	Call CE or analyst.
0007	Branch to zero detected	Call CE or analyst.
0008	Not used	
0009	Ran out of buffers	Check NOS 2 Installation Handbook to find if sufficient memory available to handle system configuration. Call CE or analyst.
000 <u>A</u> .	Duplicate release of buffer	Call CE or analyst.
000в	Buffer chain error during buffer get	Call CE or analyst.
000С	Buffer out of range	Call CE or analyst.
000Д	Coupler alarm condition	Call CE or analyst.
000E	Monitor stopped	Call CE or analyst.
000F	Too many worklists from one CLA	Call CE or analyst.
0010	Force load service message received	This is normal if a force load message was entered. Otherwise, take same action as code 0002.
0011	Bad MLIA initialization status	Call CE or analyst.
0012	Bad NCB	Call CE or analyst.
0013	Chain address = 0	Call CE or analyst.
0014	Not used	
0015	Invalid coupler orderword	Call CE or analyst.
0016	Not used	
. 0017	Illegal call to nonexistent program	Call CE or analyst.
0018	Not used	
0019	Not used	
001A	Not used	
001В	Not used .	
001C	Not used	
001D	Not used	
001E	Dynamic stack overflow	Call CE or analyst.
001F	Negative interrupt count	Call CE or analyst.
0020	Output over output	Call CE or analyst.

This glossary defines terms (both English language and mnemonic) unique to the descriptions contained in this manual or common terms whose definitions are different from or more restricted than, definitions commonly held. A glossary of English language terms is presented first, followed by a glossary of mnemonic terms.

## **ENGLISH LANGUAGE TERMS**

## Alarm Message -

A message generated by the NPU and sent to the NOP console. It informs the NOP that a network element (coupler, MLIA, or line) has suffered a large number of recent errors.

#### Block -

A unit of information used by the network. A message is divided into blocks to facilitate buffering, transmission, error detection, and correction of variable-length data streams. A transmission block includes the protocol envelope consisting of the transmission header and transmission trailer information. The envelope is used to delimit and control transmission of the block over the communications channel. A bad block is one which failed to be transmitted properly and was therefore rejected by the receiver or by the sender.

# Block Type -

One of the nine standard formats for system blocks (that is, blocks used in the block protocol between host and NPU).

## Breakpoint -

A programming utility aid that allows the operator to stop the program and computer execution at predetermined instructions (breakpoints) and to examine the program and/or change program parameters while the program is stopped.

## Buffer -

A collection of data in contiguous words. Buffers often hold a portion of a message. Chained buffers hold the entire message, regardless of size.

## Byte -

A group of contiguous bits. Unless prefixed (for example, 6-bit byte), the term implies 8-bit groups. When used for encoding character data, a byte represents a single character.

## CE Error Code -

A code appearing in a CE error message that designates the cause of the error.

## CE Error Message -

An NPU-generated message reporting a hardware failure. The messages are sent to the host's engineering file where they can be processed by the Hardware Performance Analyzer (HPA) program.

## Chain Address -

The address held at the end of one buffer pointing to the next buffer. The next buffer holds successive data that could not fit in the first buffer. Many buffers can be chained together in this fashion.

## CLA Priority -

The placement of CLA cards in the 255X card slots determines the order in which a CLA is serviced.

## Cluster -

A group consisting of a controller and all terminals that it supports. A cluster has its own address, known as a cluster address.

#### Command -

Information passed to a process which details the method of controlling the process in contrast to data destined for transmission by the process.

Communications Control Program (CCP) -The program that controls the NPU for network operations.

## Communications Line -

A communications circuit between a terminal and its network processing unit.

# Communications Line Adapter (CLA) -

A hardware unit that converts data between bit-serial and bit-parallel formats.

# Connection Number (CN) -

A number specifying the path (line) used to connect the terminal through the NPU to the host.

## Console -

A terminal devoted to network control processing. There are two such terminals concerned with diagnostics for CCP: the Network Operator's (NOP) terminal, and the Local Operator's (LOP) terminal.

## Control Blocks -

(1) The types of blocks used to transmit control (as opposed to data) information; (2) Blocks assigned for special configuration/status purposes in the NPU. These blocks include terminal control blocks (TCB), line control blocks (LCB), logical link control blocks (LLCB), queue control blocks (QCB), buffer maintenance control blocks (BCB), mux line control blocks (MLCB), text processing control blocks (TCCB), worklist control blocks (WLCB), and diagnostic control blocks (DCB).

## Controller -

A hardware device that interfaces multiple terminals to a single communications line, and performs some common functions for those terminals (such as protocol handling).

## Coupler -

The hardware interface between the local NPU and the host. Transmissions across the coupler use block protocol.

#### Data -

Any portion of a message as created by the source, exclusive of any information used to accomplish the transmission of such message.

#### Data Set -

A hardware interface that transforms analog data to digital data and the converse. Synonymous with modem.

## Destination Node (DN)

The node which directly interfaces to the destination.

#### Device -

A terminal or portion of a terminal.

# Diagnostic Decision Logic Table (DDLT) -

Special diagnostic programs that use a highly structured table technique to aid the troubleshooter in isolating a problem.

## Dial-Up -

A terminal that is switched; that is, it is connected to the network only when the phone connection is dialed to the computer's telephone number.

## Direct Memory Access (DMA) -

The high-speed I/O channel to the NPU main memory. This channel is used for host/NPU buffered transfers.

## Downline -

The direction of output information flow from host to terminal or NPU.

## Dump -

The process of transferring the contents of the NPU main memory, registers, and file 1 registers to the host. The dump can be processed by the Network Dump Analyzer in the host to produce a listing of the dumped hexadecimal information.

## File 1 Registers -

A set of registers in the microprocessor portion of the NPU. They are dynamically set at NPU initialization time.

## Frame -

(1) The basic communication unit used in trunk (NPU-to-NPU) communications. Frames are composed of control bytes, a CRC sum, and (in some cases) data bytes in sub-block sequence. A sub-block may be a block protocol block or a part of a block. Frames are transmitted as a sequence of bytes through the multiplex subsystem. (2) A frame is also a unit of data on the multiplexer input and output loops. It consists of one character of data to/from a line, surrounded by control information.

#### Front-End NPU -See Local NPU.

#### Full Duplex (FDX) -

Two-way simultaneous transmission, when applied to a communications line. Simultaneous, independent operation of the input and output devices, when applied to a terminal.

#### Function Codes -

Codes used by the service module to designate the type of function (command or status) being transmitted. Two codes are defined: primary function code (PFC) and secondary function code (SFC).

## Half Duplex (HDX) -

Two-way alternate transmission, when applied to a communications line. When applied to a terminal, it means that the terminal cannot simultaneously send one message while receiving another, usually because the output device locally copies the input while the terminal is in input mode.

#### Halt Codes -

Codes generated by the NPU when it executes a soft-stop. These codes indicate the cause of the stoppage.

# Hardware Performance Analyzer (HPA) -

A host program that processes the messages in the host's engineering file. The output contains information about network performance.

#### Host -

A digital computer that executes the programs of an application process. In this CCP release, a network has only one host; the host is directly connected to at least one NPU.

# Host Interface Package (HIP) -

The collection of programs resident in an NPU (part of CCP) that controls the transfer of data between a host and a local NPU.

## Host Operator (HOP) -

A network operator residing at the system console. The HOP monitors and controls activities of the network and application program. Contrast with network processing unit operator.

## Host Ordinal (HO) -

A number assigned to the host for use in service messages.

## Information -

A stream of bits that is communicated from one point to another, exclusive of synchronizing patterns that establish the sample point for the receiver.

## In-line Diagnostics -

That part of CCP that generates diagnostic information about on-line network performance. In-line diagnostics include alarm messages, CE error messages, statistics messages, halt code messages, and NPU dumps.

## Input -

Information flowing upline from terminal to host.

#### Line -

The connection between the NPU and a terminal.

## Line Control Block (LCB) -

A control block in the terminal node that records the status and operational parameters of the associated line.

#### Line Number -

The identifier of a specific terminal line, consisting of a CLA hardware address (port) and, where necessary, a multiplexer subport.

#### Link -

A point-to-point communications connection between two nodes consisting of one or more trunks. In this CCP release, also called a logical link and a trunk.

# Link Interface Program (LIP) -

The collection of programs resident in the NPU that controls the transfer of blocks over one or more links.

#### Local NPU -

An NPU that is attached by a coupler directly to the host. Also called front-end NPU.

#### Logical Connection -

A logical message path established between two application programs or between a network terminal and an application program. Until terminated, the logical connection allows messages to pass between the two entities.

## Logical Link Control Block (LLCB) -

A control block that maintains the operational parameters and status of a particular link.

# Loop Multiplexer (LM) -

The hardware that interfaces the CLAs (which convert data between bit-serial-digital and bit-parallel-digital (character) format) and the input and output loops.

# Loopback Tests -

A group of three on-line diagnostic tests that loop the data back toward the test source. Together, the tests are called the on-line diagnostic program. Data is looped back to the NPU internally, at the modem, or externally.

## Macromemory -

The main memory portion of the NPU. It is partly dedicated to resident programs and common areas; the remainder is a buffer area used for data and overlay programs. Word size is 16 data bits plus three additional bits for parity and program protection. Memory is packaged in 8K- and 16K-word increments; 32K is the minimum memory size.

## Message -

A logical unit of information, as processed by an application program. When transmitted over a network, a message can consist of one or more physical blocks.

#### Micromemory -

The micro portion of the NPU memory. This consists of 3072 words of 32-bit length. 1024 words are read-only memory (ROM); the remaining 2048 words are random access memory (RAM) and are alterable. The ROM memory contains the emulator microprogram that allows use of assembly language.

#### Microprocessor -

The portion of the NPU that processes programs.

#### Modem -

A hardware device for converting analog levels to digital signals and the converse. Long lines interface to digital equipment via modems. Modem is synonymous with Data Set.

#### MSMP/6000 Diagnostics -

A set of hardware diagnostics described in the MSMP Diagnostic Reference Manual.

## Multiplex Loop Interface Adapter (MLIA) -

The hardware portion of the multiplex subsystem that controls the multiplex loops (input and output) as well as the interface between the NPU and the multiplex subsystem.

#### Network Address -

A set of three 8-bit numbers, consisting of two node IDs followed by a connection number. The first node ID is the destination node. The second node ID is the source node.

# Network Dump Analyzer (NDA) -

An application program to the host that processes the NPU dump into an output listing of the dump contents together with appropriate heading information.

# Network Processing Unit Operator (NOP)

An operator who resides at a terminal and controls network elements such as NPUs, trunks, logical links, lines, terminals, and so forth. Contrast with host operator.

## Network Processor Unit (NPU) -

The collection of hardware and software that supports a set of one or more directly-connected 2550 series Communications Control Processor macromemory modules. These programs buffer and transmit data between terminals and host computer.

## Node -

A network element that creates, absorbs, switches, and/or buffers message blocks. Typical system nodes are NS and CS in the host, the coupler node of a local NPU, and a terminal node of a local NPU.

## Node ID -

An 8-bit binary serial number that represents a node.

#### NPUMST041 Diagnostics -

A set of off-line diagnostics described in the CYBER 18 Computer Systems Central Processor Field Repair Guide.

## ODS Loadcheck Diagnostics -

A set of off-line diagnostics for the NPU described in the ODS 2 Reference Manual.

## Off-Line Diagnostics -

Optional diagnostics for the NPU that require the NPU be disconnected from the network.

# On-Line Diagnostics -

Optional diagnostics for the NPU that can be executed while the NPU is connected to, and operating as a part of the network. Individual lines being tested must, however, be disconnected from the network.

#### Orderword -

A hardware register in the coupler used by the PPU to direct NPU operations.

#### Output -

Information flowing downline from host to terminal.

## Output Buffer -

Any buffer that is currently used to output information from the NPU to the host, to another NPU, to a peripheral device, or to a terminal via the multiplex subsystem.

#### Output Data Demand (ODD) -

A signal raised by a CLA indicating that the CLA is ready to receive the next character of an output message.

## Parity -

A data assurance method. Parity in the NPU is word-oriented and is ordinarily not controlled by the operator. A parity bit is added when words are stored in main memory and is discarded after checking when the word is read from main memory. A parity error causes the highest priority interrupt in the system.

## PASCAL -

A high-level programming language used for CCP programs. Almost all CCP programs are written in PASCAL language.

## PBHALT -

The CCP program that brings the NPU to a soft stop with the registers ready for saving, and the memory ready for a dump. This program also generates the halt message.

## Peripheral Processing Unit (PPU) -

The part of the host dedicated to performing I/O transfers. The coupler connects the PPU directly to an NPU.

Primary Function Code (PFC) - See function code.

#### Protect System -

A method of prohibiting one set of programs (unprotected) from accessing another set of programs (protected) and their associated data. The NPU uses a protect bit in the main memory word to implement the system. The protect fault is set when an unprotected program attempts to access a protected one.

#### Protocol -

The complete set of rules used to transmit data between two nodes. This includes format of the data and commands, and the sequence of commands needed to prepare the devices to send and receive data.

#### Read Mode -

The NPU console mode in which the NPU is ready to accept data/commands from the keyboard and echo the data (and some commands) on the CRT.

#### Real-Time Clock -

The basic computer clock. The clock is stopped and restarted periodiacally by the base system monitor (part of CCP) during on-line operation.

# Regulation -

The process of making an NPU or a host progressively less available to accept various classes of input data. The host has one regulation scheme, the host and multiplex interface of a local NPU have another scheme, and the multiplex interface to a neighboring NPU has a third regulation scheme. Some types of terminals (for instance, HASP workstations) may also regulate data. Regulation classificatons are usually based on batch, interactive, and control message criteria.

## Remote NPU -

An NPU connected only to other (local) NPUs. A remote NPU lacks a coupler; hence it can have no direct connection to the host.

## Service Message (SM) -

The network method of transmitting most command and status information to/from the NPU. Service messages use CMD blocks in the block protocol.

## Service Module (SVM) -

The set of NPU programs responsible for processing most service messages. SVM is a part of the network communications software.

## Source Node (SN) -

The network node originating a message or block of information.

# Statistics Service Message -

A subclass of service messages that contain detailed information about the characteristics and history of a network element such as a line or a terminal.

#### Status -

Information relating to the current state of a device, line, and so forth. Service messages are the principal carriers of status information. Statistics are a special subclass of status.

Subfunction Code (SFC) - See function code.

#### Subport -

One of several multiplexed addresses in a port. In this CCP configuration, subport is always equal to zero.

#### Terminal -

An element connected to a netwrk by means of a communications line. Terminals supply input messages to, and/or accept output messages from, an application program. A terminal can be a separately addressable device comprising a physical terminal or station, or the collection of all devices with a common address.

#### Terminal Class -

A classification of terminals. It is used by the service module in processing service messages.

#### Terminal Configuration -

That collection of information that identifies the addresses (if any), device types and characteristics, and operational mode of all terminals connected to a given communications line.

## Terminal Control Block (TCB) -

A control block containing configuration and status information for an active terminal. TCBs are dynamically assigned.

## Terminal Interface Programs (TIPs) -

NPU programs that provide the interface between real terminal format and virtual terminal format. The standard TIPs are the Async TIP, the Mode 4 TIP, and the HASP TIP. TIPs are responsible for some data conversion and for error processing.

## Terminal Node (TN) -

Network processing unit that supports one or more terminal interface programs and to which terminals are directly connected via communications lines.

#### Timeout -

The process of setting a time for completion of an operation and entering an error processing condition if the operation has not finished in the allotted time.

#### Trunk -

A line connecting two NPUs or an NPU and a host. The host/NPU trunk uses block protocol; the NPU/NPU trunk uses trunk protocol.

#### Trunk Protocol -

The protocol used for communicating between neighboring NPUs. It is the CDCCP protocol that uses the frame as the basic communiations element.

#### Upline -

The direction of message travel from a terminal through an NPU to the host.

#### Word .

The basic storage and processing element of a computer. The NPU uses 16-bit words (main memory) and 32-bit words (internal to the microprocessor only). All interfaces are 16-bit word (DMA and A/Q) or in character format (multiplex loop interface); characters are stored in main memory two per word. Hosts (CYBER series) use 60-bit words but a 12-bit byte interface to the NPU. Data characters at the host side of the inerface are stored in bits 19 through 12 and 7 through 0 of a dual 12-bit byte.

#### Wordlists -

Packets of information containing the parameters for a task to be performed. Programs use worklists to request tasks of OPS level programs. Worklist entries are queued to the called program. Entries are one to six words long and a given program always has entries of the same size.

## Wordlist Processor -

The base system programs responsible for creating and queuing worklist entries.

# **MNEMONICS**

	ASCII	American Standard Code for Information	MLCB	Multiplex line control block	
		Interchange	MLIA	Multiplex Loop Interface Adapter	
	BCD	Binary coded decimal	MOD	Modem	
1	BMCB	Buffer maintenance control block	MOS	Metal oxide semiconductor	
	BT	Block type	NAK	Negative acknowledgement	
	CA	Cluster addresses	NCB	Network control block	
	CCP	Communications Control Program	NCNA	Next character not available	
	CE	Customer engineer	NDA	Network Dump Analyzer	
	CIB	Circular input buffer	NOP	Network processing unit operator	
	CLA	Communications Line Adapter	NPINTAB	NPU Initialization Complete/Error Table	
	CN	Connection number	NPU	Network Processor Unit	
	CRC	Cyclic redundancy check	ODD	Output data demand	
	CRT	Cathode ray tube	ODS	Off-line diagnostic system	
	CTS	Clear to send	OLE	Output loop error	
	DA	Data	ORD	Orderword	
	DCB	Diagnostic control blocks	P	Port	
	DCD	Data carrier detect	PFC	Primary function code	
	DDLT	Diagnostic Decision Logic Table	PM	Preventive maintenance	
	DIS	Disable	POI	Point of interface	
	DMA	Direct memory access	PPU	Peripheral processing unit	
	DN	Destination node	QCB	Queue control block	
	DSR	Data set ready	RAM	Random access memory	
	DT	Device type	RC	Reason code	
1	DVT	Data Verification Test	ROM	Read only memory	
	EC	Error code	RTC	Real-time clock	
	EN	Enable .	RTS	Request to send	
	EOP	End of operation	SDCD	Secondary Data Carrier Detect	
	FDX	Full duplex	SFC	Secondary function code	
	HASP	Houston Automatic Spooling Protocol	SM	Service message	
	HDX	Half duplex	SN	Source node	
	HIP	Host Interface Program	SOH	Start of header	
_	НО	Host ordinal	SP	Subport	
	HOP	Host Operator	SVM	Service module	
	HPA	Hardware Performance Analyzer	T	Terminate	
	I	Internal (loopback test)	TA	Terminal address	
	ID	Identification number	TCB	Terminal control block	
	IDC	Internal data channel	TERM	Terminate	
	ILE	Input loop error	TIP	Terminal Interface Program	
	I/0	Input/output	TN	Terminal node	
	LCB	Line control block	TTY	Teletype	
	LI	Line	TUP	Test Utility Program	
	LIP	Link interface package	UT	User terminal	
	LLCB	Logical link control block	WLCB	Worklist control block	
1	LM	Loop multiplexer	WM	Write mode	
	LRN	Link remote node			

# CIRCUIT NUMBER

This number identifies the line to the telephone company. Keep it someplace (besides the site log) where it is readily accessible. A good place is the demarcation strip. A demarcation strip is the point where the telephone line terminates. This point is then connected to the modem. If you put the circuit number on the modem, you risk having it removed if the data set is replaced.

# STRAPPING OPTIONS

If your data set becomes inoperable and has to be replaced, the replacement may not have the correct strapping options. Therefore, you should keep a list of strapping options for future reference. Keep this list in the site log and a copy in the terminal cabinet, if convenient.

When a problem develops on your data line, certain information is necessary to help isolate the problem. Therefore, you should take time to find and record this information so that it is readily available when a problem arises.

# LINE TYPE

When requesting help from the telephone company, you need to know certain information about the line type.

Dedicated (sometimes called private or leased line)

Dial-up

# **EMERGENCY SERVICE PHONE NUMBER**

An emergency service phone number should be available on your modem or near the demarcation stip. If a number is not posted there, you will have to get it from your local sales


representative. After you get the emergency phone number, keep it handy. This number will put you in contact with the Private Line Service Board. For Long Lines, this board is open 24 hours a day, 7 days a week.

Now that you have all the necessary information, you can start checking your phone line problem.

If your phone line is a dial-up line, you can try hanging up and dialing again. This may give you a different line of better quality. If redialing does not solve your problem, or if redialing is necessary too often, you may have to work with the telephone account representative to resolve the problem.

Dedicated lines present unique problems that may prove difficult to define and correct. After you are reasonably sure that the problem is in the phone line, you should proceed as follows:

- 1. Call the emergency service number.
- Identify yourself and your circuit number. A typical line number would be:



The test board person will then check your line to see if it is properly terminated. If the problem cannot be resolved by talking to the test board person, call Regional Tech Support. They will have the test equipment and experience necessary to check futher into the problem.

The 2550 system hardware and software permit a communications line adapter (CLA) circuit card to be exchanged without impacting service to users connected to other CLAs within the system. To exchange a CLA in a system that is on line:

- 1. Ensure that neither of the two lines connected to the CLA to be exchanged is operational by taking a status report on the host console and observing the condition of each line. If either line is being used (user logged on), send a service message to the user to notify that the line is to be deactivated at a certain time (for example, in 10 minutes).
- After determining that neither line is being used, take the lines out of service by typing in appropriately coded disable line commands at the NPU operator (NOP) console.
- On the CLA circuit card to be exchanged, set the two switches to the OFF position.
- Disconnect the modem cables and remove the CLA cirucit card.
- On the CLA circuit card to be installed, set the two switches to the OFF position before inserting the card into the card slot.

- 6. Insert the replacement CLA circuit card into the card slot, dial the ADDRESS thumbwheel switches to the correct line number addresses, reconnect the modem cables, and set both switches to the ON position.
- Restore the lines to service by typing in appropriately coded enable line commands at the NOP console.

Here is an alternate procedure that you may use if a spare CLA circuit card and spare card slot are available:

- Remove the bad CLA circuit card from service as directed in steps 1, 2, and 3 above.
- Disconnect the modem cable at the bad CLA, move to the spare CLA, and reconnect.
- Dial the ADDRESS thumbwheels to the correct line number addresses and set the CLA enable switch to the ON position.
- Restore the lines to service by typing in appropriately coded enable line commands at the NOP console.

This appendix shows the relationship between the NOP commands and the responses used to run the on-line diagnostics through the service messages (SMs) sent to the NPU.

The format of statistics service messages sent to and from the host is:

Byte 0 1
| Link | DN | SN | CN=00 | BT=04 | Text | Header | |

where:

DN Destiation node
NPU ID (downline command), or
host ID (upline response)

SN Source node
host ID (downline), or
NPU ID (upline)

CN Connection number 00 for SMs

BT Block type 4 for CMD blocks

Table E-1 gives the text of each type of message and its response.

TABLE E-1. NOP COMMANDS AND ASSOCIATED SERVICE MESSAGES

NOP Command	Downline and Upline Service Messages
disable Trunk/Line	Message
	PFC SFC
	-08   -01   P   00   HO
•	
	Lfrom NPU to trunk
	PFC Primary function code
	SFC Secondary function code
	HO Host ordinal
	Response
	PFC   SFC
	=08 =41 <sub>16</sub> P 00 HO =00 LT CFS or NT
	RC Reason code, 00 is normal response
	LT Line type (see table E-2)
	CFS Configuration state (see table E-3)
	LRN Local/remote node ID (trunk) NT Number of terminals configured on a line
	NT Number of terminals configured on a line
	Error Response
	BITOL RESPONSE
	PFC SFC
· ·	=08 =81 <sub>16</sub> P 00 HO RC
	16 2 3 3
•	
	RC Reason code
	01 - Invalid line number, or no (lines/trunks) belong to requestor
	03 - (Line/trunk); illegal configuration state 04 - (Trunk); cannot disable last path to NS
	1 04 - (Trunk); cannot disable tast path to no

TABLE E-1. NOP COMMANDS AND ASSOCIATED SERVICE MESSAGES (Contd)

NOP Command	Downline and Upline Service Messages
Diagnostic Test Request	Message  PFC SFC = 20 <sub>16</sub> SFC  PFC SFC = 20 <sub>16</sub> SFC Secondary function code  4A <sub>16</sub> if accepted  8A <sub>16</sub> if rejected
Start Test Command	Message
	PFC SFC =20 <sub>16</sub> Data
	Data 1-22 ASCII words  ASCII is: test,ii,y,kk  Test INT or I - CLA internal loopback EXT or E - CLA external loopback
	MOD or M - Modem loopback  ii Port number 01 ≤ ii ≤ FE <sub>16</sub> y CLA type
Terminate Diagnostic Program	Message  PFC SFC = 0E 16  No response

TABLE E-1. NOP COMMANDS AND ASSOCIATED SERVICE MESSAGES (Contd)

NOP Command	Downline and Upline Service Messages
Enable Line/Trunk	Message
	PFC SFC P 00 HO
	Response (Normal)
	PFC SFC =08 =40 <sub>16</sub> P 00 HO RC LT CFS OF NT
	LRN - trunk NT = 00 - lines
	LT Line type (see table E-2) CFS Configuration state (see table E-3) RC 00 - (Trunk/line) enabled and operational 04 - (Trunk/line) inoperative 05 - (Line) enabled - wait for ring indicator or auto recognition resu
	Error Response  PFC SFC =08 =80 <sub>16</sub> P 00 HO RC  RC 01 - Invalid line number, or no (lines/trunks) belong to requestor
	02 - (Line/trunk) status request in process 03 - (Line/trunk) invalid configuration state 04 - (Trunk) cannot disable last path to NS
Start Test Response (Unsolicited Message)	Response to Start Test  PFC SFC = 20 16 Data
	PORT ii STARTED PORT ii INV PORT PORT ii INV CLA TYPE PORT ii INV TEST MODE PORT ii INOT DISABLED PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii INV MODEM CLS PORT ii INV MODEM CLS PORT ii TEST IN PROC. PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT ii TEST IN PROC. PORT ii LOW BUFFERS PORT II LOW BU

TABLE E-1. NOP COMMANDS AND ASSOCIATED SERVICE MESSAGES (Contd)

	Downline and Upline Service Messages			
Start Test Response (Unsolicited Message) (Contd)	Error Response (During Test)  Same as start test response except for ASCII data			
	ASCII Data			
	Port ii ERROR yy,pp,qqqq,rrrr			
	ii Port number expressed as two hexadecimal digits 01 $\leq$ ii $\leq$ FE $_{16}$			
	yy error code (see table 4-3)			
	pp Subsection number of test being performed by diagnostic program at the time of error detection			
	qqqq Additional data relative to the type of error received (see DDLTs and in section 4); each field represents a 16-bit word output as 4 rrrr hexadecimal digits			
Terminate Diagnostic Test	Message			
·	Same as start test except for ASCII data			
·	ASCII Data			
	TERM or T,,ii			
	ii Port number, 01 ≤ ii ≤ FE <sub>16</sub>			
	Response			
	Same as start test response except for ASCII data			
	ASCII Data Operator Action			
	PORT ii TEST CMPL - OK Start next test or end diagnostic PORT ii INV PORT Check port number and reenter command PORT ii NOT IN PROC.			

TABLE E-2. LINE TYPES

Line Type	CLA Type	Modem Type	Answer Mode	Carrier Type	Circuit Type
1	2560-1 Synchronous	201A/208B Compatible <sup>1</sup>	Switched	Controlled <sup>2</sup>	2-Wire HDX
2	2560-1 Synchronous	201B/208A Compatible <sup>1</sup>	Dedicated	Controlled <sup>2</sup>	4-Wire FDX <sup>3</sup>
3	2560-1 Synchronous	201B/208A Compatible <sup>1</sup>	Dedicated	Constant	4-Wire FDX
	2560-2 Synchronous	Bell 301/303 Compatible	Dedicated	Constant	4-Wire FDX
	2560-3 Synchronous	V.35 Interface	Dedicated	Constant	4-Wire FDX
4-5	Reserved for CDC				
6	2561-1 Asynchronous	103F/113/212A Compatible <sup>1</sup>	Switched	Constant <sup>4</sup>	2-Wire FDX
7	2561-1 Asynchronous	103F/113/212A Compatible <sup>1</sup>	Dedicated	Constant <sup>4</sup>	2-Wire FDX
8-9	Reserved for CDC				
10	2563-1 HDLC	201B Compatible <sup>1</sup>	Dedicated	Constant <sup>4</sup>	4-Wire FDX
	2563-2 HDLC	V.35 Modem	Dedicated	Constant <sup>4</sup>	4-Wire FDX
11-127	Reserved for CDC				
128-255	Reserved for installations				

# Legend:

- 1 RS232
- 2 Turnaround required. Turnaround not delayed.
- 3 Operating with HDX protocol.
- 4 Turnaround not required. Turnaround not delayed.

TABLE E-3. CONFIGURATION STATES

Value	Significance	
00	LCB not configured	
01	LCB configured, not enabled	
02	Enable requested to TIP	
03	Line operational, no TCBs	
04	Line Operational, TCBs configured	
05	Disabled requested to TIP	
06	Line inoperative, no TCBs	
07	Line inoperative, TCBs configured	
08	Disconnect requested to TIP	
09	Line inoperative, waiting for ring or auto recognition in process	

# **INDEX**

Abnormal DCD 2-3, 2-14	Clear to send (CTS) B-6
Abnormal DSR or CTS 2-3, 2-14	Communications Control Program (CCP)
Abnormal secondary DCD 2-3, 2-27	Alarm messages 1-1
Alarm message	Definition B-1
Block type 2-1	Communications line
Connection number 2-1	Definition B-1
Definition B-1	Fault isolation 4-22
Destination node $2-1$ Format $2-1$	Communications Line Adapter (CLA)  Definition B-l
Generation of 1-1, 2-1	Messages 2-2
Hardware Performance Analyzer 2-1	Priority B-1
Primary function code 2-1	Replacing D-1
Secondary function code 2-1	Types 4-2
Source node 2-1	Configuration states E-5
Text 2-1, A-1	Connection number (CN)
Automatic in-line diagnostics	Alarm messages 2-1
Alarm messages 1-1, 2-1	CE error messages 2-2 Definition B-1
CE errors 1-1, 2-2	For CLA types 4-7
Statistics service messages 1-1, 2-33	Statistics messages 2-33
	Console B-1
Bad BCB from HASP or workstation 2-3, 2-28	Control blocks
Bad MLIA initialization status 3-28, A-6	Definition B-1
Bad NCB 3-29, A-6	Types B-1
Binary coded decimal (BCD) B-6	Controller B-1
Block B-1	Coupler
Block type	Definition B-2
Alarm message 2-1	Messages 2-2
CE error message 2-2	Coupler alarm condition 3-24, A-6
Definition B-1	Coupler hardware timeout (input) 2-3, 2-22 Coupler hardware timeout (output) 2-3, 2-25
Statistics messages 2-33	Cyclic redundancy check (CRC) B-6
Branch to zero detected 3-19, A-6	Cyclic reduidancy check (CkC) b-0
Breakpoint B-1 Buffer	
Chain address B-1	Dash number C-1
Definition B-1	Data
Output B-4	Definition B-2
Buffer chain error 3-22, A-6	Regulation B-4
Buffer Maintenance Control Block (BMCT) B-1, B-6	Data carrier detect (DCD) B-6
Buffer out of range 3-23, A-6	Data line problems C-1
Byte B-1	Data set B-2
	Data set ready (DSR) B-6 Data transfer overrun 2-3, 2-18
<b>(77)</b>	Data verification test (DVT) B-6
CE errors Code A-1	Deadman timeout 2-3, 2-20
Message	Dedicated line C-1
Categories 2-2	Demarcation strip C-1
Definition B-1	Destination node
Diagnostic Decision Logic Tables 2-4	Alarm messages 2-1
Flowchart 2-3	CE error messages 2-2
Format 2-2	Definition B-2
Generation of 1-1, 2-2	Statistics messages 2-33
Text 2-2, A-3	Device Definition B-2
Chain address	Status B-5
Definition B-1 Halt code 3-30, A-6	Diagnostic Decision Logic Tables (DDLTs)
Circuit number C-1	CE errors 2-4
CLA address error 2-3, 2-12	Definition B-2
CLA circuit card D-1	Halt codes 3-3
CLA interface switches 4-7	How to use 1-2
CLA line types 4-2, E-5	Sample 1-2
CLA status word 4-6	Statistics 2-34
CLA tests 4-2	Diagnostic test request E-2

Diagnostics	Jumper plug 1-1
In-line 1-1, 2-1, 3-1	
Off-line 1-1	
On-line 1-1, 1-4	K-display 4-1
Dial-up	
Line C-1	
Terminal B-2	Line
Direct memory access (DMA) B-2	Definition B-3
Disable trunk/line 4-1, D-1	Operation 4-22
Disconnected line 2-3	Statistics 2-33
Downline B-2	Status B-5
Dump	Туре
Definition B-2	Dedicated C-1
Interpretation 3-1, 3-34	Dial-up C-1
2550 1-1, 3-34	Line Control Block (LCB) B-3
Duplicate release of buffer 3-21, A-6	Line number B-2
Dynamic stack overflow 3-32, A-6	Link B-2
	Link Interface Program (LIP) B-2
Enable line/trunk 4-8, E-3	Link remote node (LRN) B-6
Excessive CLA status messages 2-3, 2-19	LIP received bad frame 2-3, 2-32
External loopback tests 1-1, 4-2, 4-22	LIP timeout on idle block 2-3, 2-31 Local line C-1
	Local NPU B-2
	Logical connection B-2
File 1 register 3-1, 3-34, B-2	Logical Link Control Block (LLCB) B-3
Force load service message received 3-27, A-6	Long line C-1
Frame B-2	Loop multiplexer (LM) B-3
Front-end NPU B-2	Loopback points 4-22
Full duplex (FDX) B-2	Loopback tests 4-2, 4-22, B-3
Function codes	
Definition B-2	
Primary 2-1	
Secondary 2-1	Macromemory B-3
	Memory parity error 3-14, A-5
Holf durley (HDV) P 2	Message
Half duplex (HDX) B-2 Halt codes	Counters 2-33
Buffer address 3-1	Definition B-3
DDLTs 3-3	Metal oxide semiconductor (MOS) B-6
Definition B-2	Micromemory 3-1, B-3
Flowchart 3-2	Microprocessor B-3
Format 3-1	Missing EOP 2-3, 2-26 MLIA error 2-3, 2-20
Generation of 1-1, 3-1	MLIA failure 3-17, A-6
Port number 3-1	Mode 4 terminal response bad or missing 2-3, 2-30
Text A-5	Modem
Types of 3-1	Class 4-2
Hardware Performance Analyzer (HPA) 2-1, 2-33, B-2	Definition B-3
HASP received too many NAKs 2-3, 2-27	Local 4-24
HASP workstation restart 2-3, 2-29	Remote 4-24
HDLC protocol failure/command rejection 2-3, 2-32	Types 4-22
Host B-2	Modem loopback test 1-1, 4-2
Host Interface Program (HIP) B-2	Modem messages 2-2
Host operator (HOP) 1-1, B-2 Host ordinal B-2	Monitor stopped 3-25, A-6
nost ofurnar B-2	MSMP/6000 diagnostics B-3
	Multiplex Line Control Block (MLCB) B-6
Identification number B-6	Multiplex Loop Interface Adapter (MLIA)
Illegal call to nonexistent program 3-32, A-6	Definition B-3
Illegal MUX loop format 2-3, 2-17	Messages 2-2 MUX loop error 2-3, 2-16
Information B-2	100 100p error 2-3, 2-10
In-line diagnostics	
Alarm messages 1-1, 2-1	
CE errors 1-1, 2-2	Negative acknowledgement (NAK) B-6
Halt codes 1-1, 3-1	Negative interrupt count 3-33, A-6
Statistics 1-1, 2-33	Network address B-3
Input B-2	Network Control Block (NCB) B-6
Input data transfer terminated 2-3, 2-23	Network Dump Analyzer (NDA) 1-1, B-3
Input loop error (ILE) B-6	Network Processing Unit operator (NOP) 1-1,
Input/Output (I/O) B-6	3-1, B-3
Internal data channel (IDC) B-6	Network Processor Unit (NPU) 1-1, B-3
Internal loopback tests 1-1, 4-2, 4-22	Next character not available 2-3, 2-18
Interrupt count less than zero 3-16, A-6	Node B-3
Invalid coupler orderword 3-31, A-6	Node ID B-3

● Index-2

NOP commands	Reason code B-6
Diagnostic test request E-2	Reenable trunk/line 4-8
Disable trunk/line E-1	Regulation scheme B-4
Enable line/trunk E-3	Remote NPU B-4
Start test command E-2	Request to Send (RTS) B-6
Start test response E-3	
Terminate diagnostic program E-2	
Terminate diagnostic test E-4	Secondary Data Carrier Detect (SDCD) B-6
NOP console 4-1	Secondary function code (SFC)
NPINTAB table 3-4, 3-35, 3-36	Alarm messages 2-1
NPU	CE error messages 2-2
Dump 3-1	Statistics messages 2-33
Failures 3-34	Service message (SM) B-4, E-1
Reload 3-1	Service module (SVM) B-4
Sample 3-34	Source node (SN) B-4
Statistics messages 2-34	Spurious coupler interrupt 2-3, 2-21 Start of header (SOH) B-6
NPU master clear 3-12, A-5	Start test command E-2
NPUMSTO41 diagnostics B-4	Start test response E-3
	Statistics service messages
	Block type 2-33
Off-line diagnostic system (ODS) B-6	Connection number 2-33
Off-line diagnostics 1-1, 2-2	DDLTs 2-34
On-line diagnostics	Definition B-4
DDLTs 4-8	Destination node 2-33
Definition B-4	Flowcharts 2-33
Error codes 4-4	Format 2-33
Flowchart 4-9	Generation of 2-1
Generation of 1-1, 4-1	Primary function code 2-33
Tests 4-1	Secondary function code 2-33
Orderword B-4	Text A-5
Output buffer B-4	Strapping options C-1 Subfunction code B-5
Output data demand (ODD) B-4	Subport B-5
Output data transfer terminated 2-3, 2-24 Output loop error (OLE) B-6	Subport B-3
Output over input 3-33, A-6	
Overran CIB 3-18, A-6	Terminal
	Class B-5
	Node B-5
Parity B-4	Terminal class B-5
PASCAL B-4	Terminal configuration B-5
PBHALT B-4	Terminal Control Block (TCB) B-5
Peripheral Processing Unit (PPU) B-4	Terminal Interface Program (TIP) B-5
Point of Interface (POI) B-6	Terminal node B-5
Port number 3-1	Terminate diagnostic program E-2
Power failure 3-13, A-5	Terminate diagnostic test E-4 Test Utility Program (TUP) B-6
Primary function Code (PFC) Alarm messages 2-1	Timeout B-5
CE error messages 2-2	Timer 2-33
Definition B-4	TIP-detected terminal errors 2-2
Statistics messages 2-33	TIP event receiver timeout 2-3, 2-15
Program protect bit error 3-15, A-5	Too many worklists from one CLA 3-26, A-6
Protect system B-4	Trunk B-5
Protocol B-4	Trunk/line statistics 2-34
	Trunk protocol B-5
Queue Control Block (QCB) B-6	
	Unsolicited ODD or input 2-3, 2-13
m	Upline B-5
Ran out of buffers 3-20, A-6	User terminal (UT) B-6
Random access memory (RAM) B-6	
Read mode B-4	Word B-5
Read only memory (ROM) B-6 Real-time clock (RTC)	Wordlist processor B-5
Definition B-4	Wordlists B-5
Messages 2-2	Worklist Control Block (WCB) B-6

Index-3 ●

# COMMENT SHEET

welcomes your	: 60471500  ot intended to be used as an order blank. Control Description of this manual. Please indicate any encletions, or general comments on the back (please incl	rors, suggested
_	Please reply No reply necessa	ry FOLD
FOLD		NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES
	BUSINESS REPLY MAIL FIRST CLASS PERMIT NO. 8241 MINNEAPOLIS, MINN.	
	POSTAGE WILL BE PAID BY  CONTROL DATA CORPORATION  Publications and Graphics Division  P.O. BOX 3492  Sunnyvale, California 94088-3492	
FOLD		FOLD
	NO POSTAGE STAMP NECESSARY IF MAILED IN U.S.A. FOLD ON DOTTED LINES AND TAPE	
NAME: COMPANY:		
STREET ADDRESS:		

TAPE

CITY/STATE/ZIP:

